



**REPORT TO  
HEALTH INFRASTRUCTURE**

**ON  
PRELIMINARY (STAGE 1) SITE INVESTIGATION**

**FOR  
PROPOSED ALTERATIONS AND ADDITIONS**

**AT  
TEMORA HOSPITAL, 169-189 LOFTUS STREET,  
TEMORA, NSW**

Date: 8 June 2023  
Ref: E35822PRrpt

**JKEnvironments**  
[www.jkenvironments.com.au](http://www.jkenvironments.com.au)

T: +61 2 9888 5000  
JK Environments Pty Ltd  
ABN 90 633 911 403



Report prepared by:

**Craig Ridley**  
Associate | Environmental Scientist

Report reviewed by:

**Brendan Page**  
Principal Associate | Environmental Scientist  
CEnvP SC



For and on behalf of  
JKE  
PO BOX 976  
NORTH RYDE BC NSW 1670

### DOCUMENT REVISION RECORD

Report Reference	Report Status	Report Date
E35822PRrpt	Final Report	8 June 2023

© Document copyright of JK Environments (JKE)

This Report (which includes all attachments and annexures) has been prepared by JKE for the Client, and is intended for the use only by that Client.

This Report has been prepared pursuant to a contract between JKE and the Client and is therefore subject to:

- a) JKE's proposal in respect of the work covered by the Report;
- b) The limitations defined in the client's brief to JKE; and
- c) The terms of contract between JKE and the Client, including terms limiting the liability of JKE.

If the Client, or any person, provides a copy of this Report to any third party, such third party must not rely on this Report, except with the express written consent of JKE which, if given, will be deemed to be upon the same terms, conditions, restrictions and limitations as apply by virtue of (a), (b), and (c) above.

Any third party who seeks to rely on this Report without the express written consent of JKE does so entirely at their own risk and to the fullest extent permitted by law, JKE accepts no liability whatsoever, in respect of any loss or damage suffered by any such third party.



## Executive Summary

Health Infrastructure ('the client') commissioned JK Environments (JKE) to undertake a Preliminary (Stage 1) Site Investigation (PSI) for the proposed hospital redevelopment at Temora Hospital, 169-189 Loftus Street, Temora, NSW ('the site'). The purpose of the investigation is to make a preliminary assessment of site contamination. The site location is shown on Figure 1 and the investigation was confined to the site boundaries as shown on Figure 2 attached in the appendices.

This report has been prepared to inform the masterplan and design stage of the proposed hospital redevelopment. JKE note that a PSI is the first step in the contaminated land assessment process for planning approval with regards to Chapter 4 of State Environmental Planning Policy (Resilience and Hazards) 2021.

JKE understand that the proposed development is currently in the master planning and early design phase of the project. The proposed development will likely include additions to the existing buildings and/or new buildings constructed on the site. The development may also include refurbishment of the existing buildings. Conceptual drawings were not provided to JKE.

The primary aims of the investigation were to identify any past or present potentially contaminating activities at the site, identify the potential for site contamination, and make a preliminary assessment of the soil conditions. The scope of the investigation included a desktop review of historical information, a site walkover inspection and soil sampling from 12 locations. The site was historically used for residential and agricultural (grazing) purposes until the late 1930s, and has been used for a hospital since.

Potential contamination sources identified at the site and the immediate surrounds included:

- Historic filling activities;
- Historic agricultural activities;
- Use of pesticides;
- Hazardous building materials present within existing and/or former structures;
- On-site generator and associated fuel storage;
- Maintenance workshop; and
- On-site incinerator and hospital activities.

The investigation encountered fill and/or clay soils to depths of approximately, underlain by andesite bedrock. The maximum depth of fill encountered was 1.1m. Groundwater was not encountered during the investigation. The fill typically comprised of silty and/or sandy clay and silty sand, with inclusions of gravel and boulders, volcanic breccia, metal fragments and root fibres. Fibre cement fragments (FCF)/asbestos containing material (ACM) was observed in surficial fill in BH4.

The investigation identified fill soils impacted by asbestos and carcinogenic polycyclic aromatic hydrocarbons (PAHs) at concentrations that were above the adopted site assessment criteria (SAC). Elevated copper concentrations above the SAC were also identified in the majority of the analysed fill, natural soil and rock samples though were considered to be representative of the regional conditions.

Based on the available results, and at the time of reporting, the fill material is assigned the following preliminary classifications:

- Fill in the vicinity of BH4 is assigned a preliminary classification of **General Solid Waste (non-putrescible) containing Special Waste (asbestos)**;
- Fill in other areas tested as part of this investigation and the natural silty clay and sandy silty clay soil is assigned a preliminary classification of **General Solid Waste (non-putrescible)**; and
- The underlying andesite bedrock will likely meet the definition of **Virgin Excavated Natural Material (VENM)** for off-site disposal or re-use purposes. Though the bedrock will likely meet the definition of VENM, an assessment will also be required to confirm the bedrock is suitable from a contamination risk perspective in the context of the proposed re-use due to the elevated copper concentrations.



---

Based on the findings of the investigation, JKE is of the opinion that the site can be made suitable for the proposed development via remediation. The following is recommended:

- A surface walkover and 'emu-picking' of all visible FCF/ACM from the site surface should be undertaken and an asbestos clearance certificate obtained from a SafeWork NSW licensed asbestos assessor (LAA);
- Interim management of the site is to occur under an asbestos management plan (AMP), until remediation occurs;
- The earthworks and any re-use of material is to adequately consider the presence of copper in the soil in relation to waste classification and potential ecological risks;
- Undertake a detailed (stage 2) site investigation (DSI) to better assess the risks associated with the potential sources of contamination and inform preparation of a remediation action plan (RAP);
- A RAP is to be prepared to address the contamination issues identified at the site; and
- The site is to be managed, remediated and validated in accordance with the RAP and AMP.

In the context of remediation, asbestos-impacted soils and/or PAH-impacted soils may be remediated by:

- Consolidation of impacted soils in a dedicated containment cell, or capped in-situ, and managed long-term in accordance with an Environmental Management Plan (EMP); or
- Excavated and disposed off-site at an appropriately licensed landfill facility.

The remediation approach and validation requirements will need to be outlined in a RAP.

The conclusions and recommendations should be read in conjunction with the limitations presented in the body of this report.



## Table of Contents

<b>1</b>	<b>INTRODUCTION</b>	<b>1</b>
1.1	PROPOSED DEVELOPMENT DETAILS	1
1.2	AIMS AND OBJECTIVES	1
1.3	SCOPE OF WORK	2
<b>2</b>	<b>SITE INFORMATION</b>	<b>3</b>
2.1	BACKGROUND	3
2.2	SITE IDENTIFICATION	5
2.3	SITE LOCATION AND REGIONAL SETTING	6
2.4	TOPOGRAPHY	6
2.5	SITE INSPECTION	6
2.6	SURROUNDING LAND USE	8
2.7	UNDERGROUND SERVICES	9
2.8	LOCAL METEOROLOGY	9
2.9	SECTION 10.7 PLANNING CERTIFICATE	9
<b>3</b>	<b>GEOLOGY AND HYDROGEOLOGY</b>	<b>10</b>
3.1	REGIONAL GEOLOGY	10
3.2	ACID SULFATE SOIL (ASS) RISK AND PLANNING	10
3.3	HYDROGEOLOGY	10
3.4	RECEIVING WATER BODIES	10
<b>4</b>	<b>SITE HISTORY INFORMATION</b>	<b>11</b>
4.1	REVIEW OF HISTORICAL AERIAL PHOTOGRAPHS AND HISTORICAL MAPS	11
4.2	REVIEW OF HISTORICAL LAND TITLE RECORDS	12
4.3	REVIEW OF COUNCIL RECORDS	12
4.4	SAFework NSW RECORDS	12
4.5	NSW EPA AND DEPARTMENT OF DEFENCE RECORDS	13
4.6	HISTORICAL BUSINESS DIRECTORY AND ADDITIONAL LOTSEARCH INFORMATION	14
4.7	ANECDOTAL INFORMATION	15
4.8	SUMMARY OF SITE HISTORY INFORMATION	15
4.9	INTEGRITY OF SITE HISTORY INFORMATION	16
<b>5</b>	<b>CONCEPTUAL SITE MODEL</b>	<b>17</b>
5.1	POTENTIAL CONTAMINATION SOURCES/AEC AND COPC	17
5.2	MECHANISM FOR CONTAMINATION, AFFECTED MEDIA, RECEPTORS AND EXPOSURE PATHWAYS	18
<b>6</b>	<b>SAMPLING, ANALYSIS AND QUALITY PLAN</b>	<b>20</b>
6.1	DATA QUALITY OBJECTIVES (DQO)	20
6.2	SOIL SAMPLING PLAN AND METHODOLOGY	22
6.3	ANALYTICAL SCHEDULE	24
<b>7</b>	<b>SITE ASSESSMENT CRITERIA (SAC)</b>	<b>26</b>
7.1	SOIL	26
<b>8</b>	<b>RESULTS</b>	<b>29</b>
8.1	SUMMARY OF DATA (QA/QC) EVALUATION	29



---

8.2	SUBSURFACE CONDITIONS	29
8.3	FIELD SCREENING	30
8.4	SOIL LABORATORY RESULTS	30
9	PRELIMINARY WASTE CLASSIFICATION ASSESSMENT	34
9.1	PRELIMINARY WASTE CLASSIFICATION OF FILL	34
9.2	PRELIMINARY CLASSIFICATION OF NATURAL SOIL AND BEDROCK	34
10	DISCUSSION	35
10.1	CONTAMINATION SOURCES/AEC AND POTENTIAL FOR SITE CONTAMINATION	35
10.2	TIER 1 RISK ASSESSMENT AND REVIEW OF CSM	35
10.3	DECISION STATEMENTS	37
10.4	DATA GAPS	38
10.5	POTENTIAL REMEDIATION & MANAGEMENT OPTIONS	39
11	CONCLUSIONS AND RECOMMENDATIONS	41
12	LIMITATIONS	42



## List of Tables

Table 2-1: Site Identification	5
Table 4-1: Summary of Historical Aerial Photographs and Historical Maps	11
Table 4-2: Summary of SafeWork NSW Records	12
Table 4-3: NSW EPA and Department of Defence Records	13
Table 4-4: Historical Business Directory and other Records	14
Table 4-5: Summary of Historical Land Uses / Activities	16
Table 5-1: Potential (and/or known) Contamination Sources/AEC and Contaminants of Potential Concern	17
Table 5-2: CSM	18
Table 6-1: Soil Sampling Plan and Methodology	22
Table 6-2: Laboratory Details	25
Table 7-1: Details for Asbestos SAC	26
Table 7-2: Waste Categories	27
Table 8-1: Summary of Subsurface Conditions	29
Table 8-2: Summary of Field Screening	30
Table 8-3: Summary of Soil Laboratory Results – Human Health and Environmental (Ecological)	30
Table 8-4: Summary of Soil Laboratory Results Compared to CT and SCC Criteria	32
Table 8-5: Summary of Soil Laboratory Results Compared to TCLP Criteria	33
Table 10-1: Data Gap Assessment	38

## Attachments

Appendix A: Report Figures
Appendix B: Site Information and Site History
Appendix C: Laboratory Results Summary Tables
Appendix D: Borehole & Test Pit Logs
Appendix E: Laboratory Reports & COC Documents
Appendix F: Report Explanatory Notes
Appendix G: Data (QA/QC) Evaluation
Appendix H: Guidelines and Reference Documents



## Abbreviations

Asbestos Fines/Fibrous Asbestos	AF/FA
Ambient Background Concentrations	ABC
Asphaltic Concrete	AC
Asbestos Containing Dust	ACD
Added Contaminant Limits	ACL
Asbestos Containing Material	ACM
Area of Environmental Concern	AEC
Australian Height Datum	AHD
Aboriginal Heritage Information Management System	AHIMS
Acid Sulfate Soil	ASS
Above-Ground Storage Tank	AST
Below Ground Level	BGL
Benzo(a)pyrene Toxicity Equivalent Factor	BaP TEQ
Bureau of Meteorology	BOM
Benzene, Toluene, Ethylbenzene, Xylene	BTEX
Before You Dig Australia	BYDA
Cation Exchange Capacity	CEC
Contaminated Land Management	CLM
Carbon Dioxide	CO <sub>2</sub>
Contaminant(s) of Potential Concern	CoPC
Chain of Custody	COC
Conceptual Site Model	CSM
Contaminant Threshold	CT
Development Application	DA
Design Guidance Note	DGN
Data Quality Indicator	DQI
Data Quality Objective	DQO
Detailed Site Investigation	DSI
Ecological Investigation Level	EIL
Ecological Screening Level	ESL
Environmental Management Plan	EMP
Environment Protection Authority	EPA
Environmental Site Assessment	ESA
Environmental & Safety Professionals	ESP
Fibre Cement Fragment(s)	FCF
Hazardous Building Materials	HAZMAT
Health Investigation Level	HILs
Health Screening Level	HSL
International Organisation of Standardisation	ISO
JK Environments	JKE
JK Geotechnics	JKG
Licensed Asbestos Assessor	LAA
Lab Control Spike	LCS
Local Environment Plan	LEP
Map Grid of Australia	MGA
National Association of Testing Authorities	NATA
National Environmental Protection Measure	NEPM
No Set Limit	NSL
Organochlorine Pesticides	OCP
Organophosphate Pesticides	OPP
Polycyclic Aromatic Hydrocarbons	PAH
Polychlorinated Biphenyls	PCBs
Per- and Polyfluoroalkyl Substances	PFAS





Photo-ionisation Detector	PID
Protection of the Environment Operations	POEO
Practical Quantitation Limit	PQL
Preliminary Site Investigation	PSI
Quality Assurance	QA
Quality Control	QC
Remediation Action Plan	RAP
Relative Percentage Difference	RPD
Site Assessment Criteria	SAC
Sampling, Analysis and Quality Plan	SAQP
State Environmental Planning Policy	SEPP
Synthetic Mineral Fibres	SMF
Site Specific Assessment	SSA
Source, Pathway, Receptor	SPR
Specific Contamination Concentration	SCC
Standard Penetration Test	SPT
Standing Water Level	SWL
Trip Blank	TB
Toxicity Characteristic Leaching Procedure	TCLP
Total Recoverable Hydrocarbons	TRH
Trip Spike	TS
Upper Confidence Limit	UCL
Unexpected Finds Protocol	UFP
Urban Residential and Public Open Space	URPOS
Virgin Excavated Natural Material	VENM
Volatile Organic Compounds	VOC

**Units**

Kilometres	km
Litres	L
Metres BGL	mBGL
Metres	m
Millivolts	mV
Millilitres	ml or mL
Micrograms per Litre	µg/L
Milligrams per Kilogram	mg/kg
Milligrams per Litre	mg/L
Parts Per Million	ppm
Percentage	%
Percentage weight for weight	%w/w



## 1 INTRODUCTION

Health Infrastructure ('the client') commissioned JK Environments (JKE) to undertake a Preliminary (Stage 1) Site Investigation (PSI) for the proposed hospital redevelopment at Temora Hospital, 169-189 Loftus Street, Temora, NSW ('the site'). The purpose of the investigation is to make a preliminary assessment of site contamination. The site location is shown on Figure 1 and the investigation was confined to the site boundaries as shown on Figure 2 attached in the appendices.

This report has been prepared to inform the masterplan and design stage of the proposed hospital redevelopment. JKE note that a PSI is the first step in the contaminated land assessment process for planning approval with regards to Chapter 4 of State Environmental Planning Policy (Resilience and Hazards) 2021<sup>1</sup>.

A geotechnical investigation and a visual hazardous building materials (HAZMAT) survey were undertaken in conjunction with this PSI by JK Geotechnics (JKG) and JKE respectively. The results of the geotechnical investigation and HAZMAT survey are presented in separate reports (Ref: 35822BFrpt<sup>2</sup> and Ref: E35822HLrpt-HAZ<sup>3</sup>). This report should be read in conjunction with the JKG and JKE HAZMAT reports.

### 1.1 Proposed Development Details

JKE understand that the proposed development is currently in the master planning and early design phase of the project. The proposed development will likely include additions to the existing buildings and/or new buildings constructed on the site. The development may also include refurbishment of the existing buildings.

Conceptual drawings were not provided to JKE. However, we anticipate that the proposed development will likely be constructed consistent with the existing levels and expect that only minor earthworks (cut/fill) would be required to accommodate the proposed development.

### 1.2 Aims and Objectives

The primary aims of the investigation were to identify any past or present potentially contaminating activities at the site, identify the potential for site contamination, and make a preliminary assessment of the soil conditions. The objectives were to:

- Provide an appraisal of the past site use(s) based on a review of historical records;
- Assess the current site conditions and use(s) via a site walkover inspection;
- Identify potential contamination sources/areas of environmental concern (AEC) and contaminants of potential concern (CoPC);
- Assess the soil contamination conditions via implementation of a preliminary sampling and analysis program;
- Prepare a conceptual site model (CSM);
- Assess the potential risks posed by contamination to the receptors identified in the CSM (Tier 1 assessment);

<sup>1</sup> State Environmental Planning Policy (Resilience and Hazards) 2021 (NSW) (referred to as SEPP Resilience and Hazards 2021)

<sup>2</sup> JKG (2023). Report to Health Infrastructure on Geotechnical Investigation for Proposed Alterations and Additions at Temora Hospital, 169-189 Loftus Street, Temora, NSW. (Ref: 35822YFrpt2) (referred to as JKG report)

<sup>3</sup> JKE, (2023). Report to Health Infrastructure on Hazardous Building Materials Survey for Proposed Alterations and Additions at Temora Hospital, 169-189 Loftus Street, Temora, NSW. (Ref: 35822PLrpt-HAZ) (referred to as JKE HAZMAT report)



- Provide a preliminary waste classification for off-site disposal of soil;
- Assess whether the site is suitable or can be made suitable for the proposed development (from a contamination viewpoint);
- Assess whether further intrusive investigation and/or remediation is required; and
- Provide high-level commentary on possible remediation approaches, if required.

### 1.3 Scope of Work

The investigation was undertaken in accordance with a JKG proposal (Ref: P57854BF) of 9 December 2022 and commissioned by a signed Consultancy Agreement (HI22656). The scope of work included the following:

- Review of site information, including background and site history information from various sources outlined in the report;
- Preparation of a CSM;
- Design and implementation of a sampling, analysis and quality plan (SAQP);
- Interpretation of the analytical results against the adopted Site Assessment Criteria (SAC);
- Data Quality Assessment; and
- Preparation of a report including a Tier 1 risk assessment.

The scope of work was undertaken with reference to the National Environmental Protection (Assessment of Site Contamination) Measure 1999 as amended (2013)<sup>4</sup>, other guidelines made under or with regards to the Contaminated Land Management Act (1997)<sup>5</sup>, SEPP Resilience and Hazards 2021, Design Guidance Note No. 030 (2021)<sup>6</sup> and Design Guidance Note No. 060 (2020)<sup>7</sup>. A list of reference documents/guidelines is included in the appendices.

---

<sup>4</sup> National Environment Protection Council (NEPC), (2013). *National Environmental Protection (Assessment of Site Contamination) Measure 1999 (as amended 2013)*. (referred to as NEPM 2013)

<sup>5</sup> Contaminated Land Management Act 1997 (NSW) (referred to as CLM Act 1997)

<sup>6</sup> Health Infrastructure, (2021). *Design Guidance Note No. 030. Site Investigations: Project Opportunities and Constraints*. (referred to as DGN 030)

<sup>7</sup> Health Infrastructure, (2020). *Design Guidance Note No. 060. Contaminated Land Management Framework*. (referred to as DGN 060)



---

## 2 SITE INFORMATION

### 2.1 Background

#### 2.1.1 Asbestos Analysis & Risk Assessment

An asbestos analysis and risk assessment was undertaken at the site by Robson Environmental in 2018<sup>8</sup>. The purpose of the assessment was to investigate the presence and condition of suspected asbestos containing material (ACM) within the first-floor ceiling space of the nurses' accommodation.

The assessment identified friable asbestos within the hot water pipe lagging, and within surface dust samples collected from the ceiling space. The corrugated roof sheeting and fibre cement fragments (FCF) within the ceiling space were considered to be bonded/non-friable ACM.

Friable asbestos was identified in the pipe lagging and surface dust samples within the ceiling space. Bonded asbestos was identified within the corrugated sheeting roof tiles, an access hatch and fibre cement debris within the ceiling space.

Robson Environmental recommended the removal of all ACM roof sheeting, pipe lagging, FCF and asbestos containing dust (ACD) from within the first-floor ceiling space.

#### 2.1.2 HAZMAT Survey Update

A hazardous materials survey update was undertaken at the site by Environmental & Safety Professionals (ESP) in 2018<sup>9</sup>. The purpose of the assessment was to update the existing HAZMAT register following refurbishments at the site. The scope of work included a visual inspection of ACM, synthetic mineral fibres (SMF), polychlorinated biphenyls (PCBs), lead-based paint, and ozone depleting substances within the buildings. Samples of suspected ACM and lead-based paint were also collected for laboratory analysis.

The report identified the following:

- Bonded/non-friable ACM present in the main hospital building, boiler room, nurses' accommodation, workshop, and plant room;
- There was potential friable asbestos (FA) to be present within old boilers in the hospital, nurses' accommodation or boiler room buildings;
- SMF present in the main hospital building, day centre building, boiler room, and nurses' accommodation;
- Lead-based paint systems and ozone depleting substances in the main hospital building and nurses' home;
- PCB containing materials were not identified. However, a licensed electrician should confirm the whether light fittings installed prior to 1980 contain PCB filled capacitors.

The majority of identified ACM was considered low risk. The following was recommended:

---

<sup>8</sup> Robson Environmental, (2018). *Temora Hospital Nurses Home – Asbestos Analysis and Risk Assessment of 1<sup>st</sup> floor ceiling space insulation, sheeting and surface dust samples collected on Tuesday 22 May 2018*. (Ref: T-05862)

<sup>9</sup> Environmental & Safety Professionals, (2018). *Report for Murrumbidgee LHD Asset Management. Hazardous Materials Survey Update: Temora Hospital, 169 Temora Young Road Temora NSW*. (Ref: J39256)



- The vinyl floor tiles in the staff dining room required damaged/broken tile edges to be sealed;
- The table tops within the linen store room were required to be removed and/or replaced; and
- The remaining identified ACM was to be managed in accordance with the asbestos management plan (AMP).

### 2.1.3 Asbestos Site Assessment & Scope of Works for Remediation

An asbestos site assessment was undertaken at the site by Regional EnviroScience in 2019<sup>10</sup>. The scope of works included sampling (using adhesive tape) to assess the potential for migration of asbestos fibres throughout the nurses' accommodation building. Friable asbestos was previously identified within the ceiling cavity, and there was considered to be potential for fibre migration through exposed manholes and access hatches.

The assessment identified asbestos fibres (considered as friable asbestos) in two rooms on the first floor. Regional EnviroScience considered there was potential for further migration of fibres and the entire first floor should be treated as impacted by friable asbestos. The following was recommended:

- Immediately isolate and restrict access to the first floor of the nurses' accommodation. This should be sealed off from the base of the stairs; and
- Remediation must be conducted by a Class A licensed asbestos removalist. All porous furnishing must be disposed of as asbestos waste. Non-porous furniture may be decontaminated and re-used.

### 2.1.4 Due Diligence Report

A due diligence report was prepared for the site by Northrop Consulting Engineers in 2022<sup>11</sup> to inform the master planning for the hospital redevelopment. The contamination-related information was reviewed and is summarised below.

The due diligence report included a review of the ESP Hazmat Survey update (summarised in Section 2.1.2 of this report), and also referred to an asbestos clearance report undertaken by EnviroScience Solutions in 2020. JKE was not supplied with a copy of the asbestos clearance report for review.

The due diligence report indicated the following materials were removed from the nurses' accommodation building over a period of time:

- Bonded/non-friable ACM corrugated roofing, fibre cement ceiling and wall sheeting from first floor veranda, and fibre cement external sheeting of the ground floor kitchen and storage room;
- Friable asbestos lagged pipes in the ceiling cavity space and from room 10; and
- The vinyl floor tiles from the first-floor landing, however the asbestos containing adhesive layer remained.

The due diligence report did not include information relating to potential soil and/or groundwater contamination.

<sup>10</sup> Regional EnviroScience Pty Ltd (2019). *Asbestos Site Assessment and Scope of Works for Remediation; Nurses Accommodation, Temora Hospital* (Ref: 22408R01)

<sup>11</sup> Northrop Consulting Engineers, (2022). *Temora Hospital – Site Due Diligence Report* (Ref: SY221522-00-MD01, Revision 2).



### 2.1.5 Aboriginal Heritage Due Diligence Assessment

An Aboriginal heritage due diligence assessment was undertaken by NGH in 2023<sup>12</sup>. The assessment included a desktop review of the Aboriginal Heritage Information Management System (AHIMS) database and a site walkover inspection.

The desktop review identified 108 Aboriginal sites registered within the local area. However, the nearest was located approximately 1.7km from the site. The site inspection did not identify any Aboriginal sites, objects, places or areas of potential Aboriginal archaeological sensitivity. The site was considered to have been highly disturbed by vegetation clearing, cut/fill operations and the construction of the hospital and associated buildings.

NGH considered it unlikely that Aboriginal heritage objects or areas of archaeological potential were present within the site. NGH recommended the development could proceed with caution.

## 2.2 Site Identification

Table 2-1: Site Identification

<b>Current Site Owner (Certificate of Title):</b>	Health Administration Corporation
<b>Site Address:</b>	169 – 189 Loftus Street, Temora, NSW
<b>Lot &amp; Deposited Plan:</b>	Lot 2 DP 572392
<b>Current Land Use:</b>	Hospital
<b>Proposed Land Use:</b>	Hospital
<b>Local Government Authority:</b>	Temora Shire Council
<b>Current Zoning:</b>	SP2: Infrastructure
<b>Site Area (m<sup>2</sup>) (approx.):</b>	31,770
<b>RL (AHD in m) (approx.):</b>	308-321
<b>Geographical Location (decimal degrees) (approx.):</b>	Latitude: -34.44276 Longitude: 147.5434
<b>Site Location Plan:</b>	Figure 1
<b>Sample Location Plan:</b>	Figure 2

<sup>12</sup> NGH Pty Ltd, (2023). *Aboriginal Heritage Due Diligence Assessment; Temora Hospital Redevelopment*. (Ref: 22-610, draft issued 2 February 2023)

### **2.3 Site Location and Regional Setting**

The site is located in a predominantly residential and rural area of Temora and is bound by Loftus Street to the south and Gloucester Street to the west. The site is located approximately 4km to the south-east of Lake Centenary (a man-made lake across Trigalong Creek).

### **2.4 Topography**

The regional topography is characterised by gently undulating terrain. The site is located towards the crest of a gently undulating slope which grades down towards the south-west at approximately 5°. Parts of the site appear to have been levelled to account for the slope and accommodate the existing development.

### **2.5 Site Inspection**

A walkover inspection of the site was undertaken by JKE on 2 May 2023. The inspection was limited to accessible areas of the site and immediate surrounds. An internal inspection of the main hospital and staff accommodation buildings was not undertaken. Selected site photographs obtained during the inspection and throughout the course of the PSI are attached in the appendices.

A summary of the inspection findings is outlined in the following subsections:

#### **2.5.1 Current Site Use and/or Indicators of Former Site Use**

At the time of the inspection, the majority of site was utilised as a hospital with associated accommodation and maintenance areas. Former uses could not be discerned.

#### **2.5.2 Buildings, Structures and Roads**

The buildings were mostly located within the northern and central portions of the site and appeared to be generally in good condition based on cursory inspections. The main hospital building was a three-storey building of brick and fibre cement construction, with metal roofing and timber and concrete flooring. A single-storey storage building of brick construction with metal roofing and concrete flooring adjoined to the west of the main hospital building.

A single-storey day centre building was located to the north-east of the main hospital building and was of brick construction with metal roofing and concrete flooring. The internal walls were lined with fibre cement.

A single-storey building of brick construction with concrete flooring and metal roofing was located to the north-west of the main hospital building. This building housed the boiler room and infectious waste storage areas. An incinerator was located within the boiler room.

A single-storey maintenance office and workshop building was located to the north of the main hospital building. The maintenance building was of brick construction with concrete flooring, metal roofing, with brick and fibre-cement lined internal walls. A small single-storey plant room of brick construction with a metal roof was located to the east of the main hospital building.

A two-storey building of brick and metal construction with tile roofing was located to the south-east of the main hospital building and was used for staff accommodation. The flooring was of timber construction with fibre cement lining on internal walls. A single-storey shed of fibre cement construction with metal roofing was adjacent to the east of the nurses' accommodation building.

An asphaltic concrete (AC) paved driveway provided vehicular access to the site from Loftus Street in the south-west of the site, and extended to the north-east to and around the main hospital building, connecting with another AC paved driveway providing vehicular egress from the site to Gloucester Street in the north-west of the site. Several on-grade carparks and concrete pathways were observed across the site. The pavement conditions varied from moderate to poor condition based on a cursory inspection, with several cracks and potholes observed. Evidence of repairs to the AC pavements were also noted.

### **2.5.3 Boundary Conditions, Soil Stability and Erosion**

The site was fenced on all boundaries, and was accessible from driveways in the south-west from Loftus Street and the north-west from Gloucester Street. No visible evidence of erosion was observed at the site boundaries or across the site during the course of the PSI.

### **2.5.4 Presence of Drums/Chemical Storage and Waste**

Various chemicals associated with site maintenance were stored on concrete flooring or shelves within the maintenance building. The following chemicals were observed:

- Minor quantities of paints stored in 4-15L containers and pressurised cannisters (for line-marking);
- A 250L flammable liquid storage cabinet containing jerry cans of fuel;
- A 160L toxic substance storage cabinet containing various domestic-grade herbicides stored in 2-5L containers; and
- Minor quantities of sealants, lubricants and grease.

An infectious waste storage area was located within the boiler room building and contained several sharps containers and 240L bins. All waste appeared to be stored in their appropriate containers.

Two gas stores were located across the site, being adjacent to the maintenance building, and adjacent to the main hospital building. The gas stores included oxygen and nitrous oxide cylinders contained within a metal cage. General waste and recycling bins were observed predominantly in the northern portion of the site.

Fire extinguishers were observed in several locations across the site. The fire extinguishers were predominantly carbon dioxide (CO<sub>2</sub>) and dry powder type extinguishers. A foam-type fire extinguisher was observed within the maintenance building. The extinguisher was marked as 'Fluorine-free', indicating it did not contain per-and polyfluoroalkyl substances (PFAS) within the foam matrix. During the inspection, no visible evidence of discharge/use of the fire extinguishers was observed.

Based on the above, JKE considered that the use of fuels, oils and lubricants within the maintenance building may represent a potential source of contamination, though it is likely any impacts would be localised.





Due to the relatively small quantities and/or domestic-grade constituents of the remaining identified chemicals/wastes, these were not considered to represent a potential source of contamination that would pose an unacceptable risk.

### **2.5.5 Evidence of Cut and Fill**

Exposed fill soils were observed in the formed garden areas of the site. A steep batter was observed in the south of the site with a large flat area at the base. The provided survey indicated this was a former tennis court.

### **2.5.6 Visible or Olfactory Indicators of Contamination**

Surficial staining of the AC pavement was observed in the northern carpark, adjacent to the maintenance building. The staining was likely associated with localised leaks/spills of fluids from vehicles in this area. JKE note that the staining was minor and was considered unlikely to have impacted the underlying ground to the extent that it would pose an unacceptable risk.

An incinerator was observed within the boiler room located within the north-west of the site.

### **2.5.7 Drainage and Services**

Surface water run-off was expected to generally flow in a south-westerly direction (in sympathy with the local topography) and eventuate in the open concrete drain along the western boundary and/or in off-site stormwater infrastructure along Loftus Street. Infiltration of rainwater would also be expected within the landscaped areas on-site.

Three substations were observed to the west of the boiler room, and a self-contained back-up generator was located adjacent to the west of the main hospital building.

### **2.5.8 Sensitive Environments**

Sensitive environments such as wetlands, ponds, creeks or extensive areas of natural vegetation were not identified on site or in the immediate surrounds.

### **2.5.9 Landscaped Areas and Visible Signs of Plant Stress**

Medium to large trees were observed generally along the site boundaries. Smaller shrubs and trees were located within the courtyard to the north and south of the main hospital building, as well as in other formed garden areas across the site. The on-site vegetation appeared healthy based on a cursory inspection, with no visible evidence of stress or die-back.

## **2.6 Surrounding Land Use**

During the site inspection, JKE observed the following land uses in the immediate surrounds:

- North – low-density residential, the Temora campus of TAFE NSW and residential care facility (Whiddon Group);

- South – Loftus Street with low-density residential beyond;
- East – Utilities infrastructure (transmission tower, substation, pumping station and reservoirs) with vacant agricultural land (possibly grazing) beyond; and
- West – Residential care facility (Whiddon Group) with Gloucester Street beyond.

JKE did not observe any land uses in the immediate surrounds that were identified as potential contamination sources for the site.

## **2.7 Underground Services**

The 'Before You Dig Australia' (BYDA) plans were reviewed for the investigation in order to establish whether any major underground services exist at the site or in the immediate vicinity that could act as a preferential pathway for contamination migration. Major services were not identified that would be expected to act as preferential pathways for contamination migration.

## **2.8 Local Meteorology**

Key meteorological data for the weather station at the Temora Airport available on the Bureau of Meteorology (BOM)<sup>13</sup> website has been reviewed and JKE note the following:

- The highest mean rainfall occurs in November, with a total of 58.4mm;
- The lowest mean rainfall occurs in April, with a total of 31.1mm; and
- In the week leading up to the JKE site inspection, a total of 28mm of rainfall was recorded.

## **2.9 Section 10.7 Planning Certificate**

The section 10.7 (2 and 5) planning certificates were reviewed for the investigation. Copies of the certificates are attached in the appendices. A summary of the relevant information is outlined below:

- The land is not restricted by: contamination; acid sulfate soils (ASS) or salinity;
- The land is not biodiversity certified;
- The land is not located in a conservation area; and
- There are no items of environmental heritage located on the land.

---

<sup>13</sup>[http://www.bom.gov.au/climate/averages/tables/cw\\_073151.shtml](http://www.bom.gov.au/climate/averages/tables/cw_073151.shtml)

---

### **3 GEOLOGY AND HYDROGEOLOGY**

#### **3.1 Regional Geology**

Regional geological information was reviewed for the investigation. The information was sourced from the Lotsearch report attached in the appendices. The information reviewed indicates that the site is underlain by Temora Volcanics comprising andesite, trachyandesite, latite and basaltic andesite, though may be obscured by quaternary aged alluvial soils. The alluvial soils are likely present on the lower slopes and toe of the hillside and not within the site boundaries.

#### **3.2 Acid Sulfate Soil (ASS) Risk and Planning**

The site is not located in an ASS risk area according to the risk maps prepared by the Department of Land and Water Conservation.

#### **3.3 Hydrogeology**

Hydrogeological information presented in the Lotsearch report indicated that the regional aquifer on-site and in the areas immediately surrounding the site includes fractured or fissured, extensive aquifers of low to moderate productivity. There was one registered bore within the report buffer of 2,000m. In summary:

- The registered bore was located approximately 330m to the west of the site;
- The registered bore was intended for use for recreational purposes (assumed to be used for irrigation of recreational areas); and
- The drillers log information identified clay soils to a depth of approximately 41mBGL (with a weathered sandstone layer between approximately 30-32mBGL), underlain by siltstone bedrock.

The information reviewed for the PSI indicates that the subsurface conditions at the site are likely to consist of relatively low permeability (residual) soils overlying shallow bedrock. The potential for viable groundwater abstraction and use of groundwater under these conditions is considered to be low. There is a reticulated water supply in the area and consumption of groundwater is not expected to occur. Use of groundwater is not proposed as part of the development as far as we are aware.

Considering the local topography and surrounding land features, JKE anticipate groundwater to flow towards the north-west.

#### **3.4 Receiving Water Bodies**

Surface water bodies were not identified in the immediate vicinity of the site. The closest surface water body is an unnamed dam approximately 320m to the north-east from site. This is up-gradient from site and is not considered to be a potential receptor.

The nearest down-gradient surface water body is Trigalong Creek, located approximately 3.8km to the west of the site, which in turn flows into Lake Centenary, approximately 4km to the north-west of the site. Due to the distances from the site, these water bodies are not considered to be potential receptors which could readily be impacted by direct migration of contaminated groundwater.

## 4 SITE HISTORY INFORMATION

### 4.1 Review of Historical Aerial Photographs and Historical Maps

Historical aerial photographs were reviewed for the investigation. The information was sourced from the Lotsearch report. JKE has reviewed the photographs and historical maps, and summarised relevant information in the following table:

Table 4-1: Summary of Historical Aerial Photographs and Historical Maps

Year	Details
1945	<p><b>On-site:</b> two inter-connected rectangular buildings (main hospital building) were visible within the north of the site, with a small building/structure adjoining the south-western corner. An 'L'-shaped building was visible to the east of the main hospital building. A small building/shed was visible to the west of the main hospital building, adjacent to the northern site boundary. A large rectangular building (nurses' accommodation) was visible in the south-east of the site. The area between the buildings, and extending to the northern boundary on the north-side of the main buildings, appeared to be paved or cleared, with a driveway extending to the south-western corner of the site. Trees were visible along the driveway and within the north-eastern corner of the site.</p> <p><b>Off-site:</b> The surrounds appeared to be predominantly cleared and used for agricultural (grazing) purposes. A few residential dwellings and associated yards were adjacent to the north-west of the site. The township of Temora (comprised predominantly of low-density residential) was visible to the south-west of the site. A water tower was visible adjacent to the east of the site.</p>
1961	<p><b>On-site:</b> The southern and western portions of the site appeared to be densely vegetated. A rectangular cleared section of land (possible tennis courts) was visible to the south of the nurses' accommodation.</p> <p><b>Off-site:</b> Three large rectangular buildings had been constructed approximately 100m to the north of the site. The surrounds otherwise appeared generally similar to the previous photograph.</p>
1978	<p><b>On-site:</b> The building in the east had been replaced with a small square building (2023 configuration of plant room), and a large rectangular building had been constructed to the north of the main hospital building, adjacent to the northern site boundary (2023 configuration of maintenance building). The small building in the west of the site (adjacent to the northern boundary) had been extended to the east, and a northerly extension had been constructed adjoining the east of the main hospital building.</p> <p><b>Off-site:</b> Several buildings were visible immediately adjacent to the west of the site (Whiddon Temora nursing home). An additional water tower and a house/residence was visible to the east/south-east of the site. A residential subdivision had been constructed to the south of the site, beyond Loftus Street.</p>
1986	<p><b>On-site:</b> An additional rectangular building had been constructed to the north-east of the main hospital building (2023 configuration of day centre). Small additions were visible to the south-western portion of the main hospital building.</p> <p><b>Off-site:</b> The surrounds appeared generally similar to the previous photograph.</p>
1997 2005	<p>The site and surrounds appeared generally similar to the previous photograph. A large 'X'-shaped building was visible by the 1997 photograph, located approximately 150m to the north-east of the site.</p> <p>Several additional houses were visible to the south-east of the site (to the east of the existing subdivision) by the 2005 photograph.</p>

Year	Details
2011	<p><b>On-site:</b> The site appeared relatively similar to the previous photograph.</p> <p><b>Off-site:</b> Several large rectangular buildings were visible approximately 150m to the north of the site. The buildings appear to be consistent with the 2023 configuration of the TAFE NSW Temora campus.</p>
2017 2022	The site and surrounds appeared relatively similar to previous photographs. Construction of a small subdivision (cul-de-sac and residences) approximately 100-150m north-west of the site was visible in these photographs.

## 4.2 Review of Historical Land Title Records

Historical land title records were reviewed for the investigation. The record search was undertaken by InfoTrack. Copies of the title records are attached in the appendices. The title records indicate the following:

- Prior to the 1930s, the site was owned by individuals. The professions listed including a farmer;
- Between 1930 and 2019, the site was owned by the Temora and District Hospital;
- The site was subdivided in 1974; and
- The site was compulsorily acquired in 2019 by the Health Administration Corporation.

The historical land title records identified the site was likely used for agricultural purposes (likely grazing). Historical agricultural land use could potentially have resulted in contamination.

## 4.3 Review of Council Records

Council records were sourced under an informal access to information request and were reviewed for the investigation. The council records indicated that a Development Application (DA) was approved in 2012 for the construction of a lift shaft and 1.5m x 2.5m lift car (Ref: 1213/012D).

## 4.4 SafeWork NSW Records

SafeWork NSW records in relation to the registered storage of dangerous goods were reviewed for the investigation. Copies of relevant documents are attached in the appendices. The search identified licences to store dangerous goods including above ground storage tanks (ASTs) at the site.

A summary of the relevant information is provided in the following table:

Table 4-2: Summary of SafeWork NSW Records

Date	Record Number	License Details
6 November 1992	35/028071	<p>An application to store dangerous goods at the site was lodged. The application related to:</p> <ul style="list-style-type: none"> <li>• 1x 7,500L liquified petroleum gas (LPG) above-ground tank; and</li> <li>• 1x 2,500L LPG above-ground tank.</li> </ul>
27 September 1995	35/028071	A conditional licence was issued for the storage of dangerous goods. The licence was conditional upon receipt of a site sketch within one month of issue.



Date	Record Number	License Details
20 May 1998	35/028071	A renewal application was lodged.

#### 4.5 NSW EPA and Department of Defence Records

A review of the NSW EPA and Department of Defence databases was undertaken for the PSI. Information from the following databases were sourced from the Lotsearch report:

- Records maintained in relation to contaminated land under Section 58 of the CLM Act 1997;
- Records of sites notified in accordance with the Guidelines on the Duty to Report Contamination under Section 60 of the CLM Act 1997 (2015)<sup>14</sup>;
- Licensed activities under the Protection of the Environment Operations Act (1997)<sup>15</sup>;
- Sites being investigated under the NSW EPA per-and polyfluoroalkyl substances (PFAS) investigation program;
- Sites being investigated by the Department of Defence for PFAS contamination; and
- Sites being managed by the Department of Defence for PFAS contamination.

The search included the site and surrounding areas in the report buffer. A summary of the information is provided below:

Table 4-3: NSW EPA and Department of Defence Records

Records	On-site	Off-site
Records under Section 58 of the CLM Act 1997	None	There was one property listed within the report buffer. This property was a service station location approximately 880m to the west and down-gradient of site. Due to the distance from site and down-gradient location, the property is not considered to represent an off-site source of contamination.
Records under the Duty to Report Contamination under Section 60 of the CLM Act 1997	None	As above.
Licences under the POEO Act 1997	None	Historical licences were identified for several properties within the report buffer for activities including concrete works and the application of herbicides along waterways. However, these activities are considered unlikely to pose a contamination risk to the site or represent an off-site source of contamination.
Records relating to the NSW EPA PFAS Investigation Program	None	None

<sup>14</sup> NSW EPA, (2015). *Guidelines on the Duty to Report Contamination under Section 60 of the CLM Act 1997*. (referred to as Duty to Report Contamination)

<sup>15</sup> Protection of the Environment Operations Act 1997 (NSW) (referred to as POEO Act 1997)



Records	On-site	Off-site
Records relating to the Department of Defence PFAS management and investigation programs	None	None

#### 4.6 Historical Business Directory and Additional Lotsearch Information

Historical business records and other relevant information were reviewed for the investigation. The information was sourced from the Lotsearch report and summarised in the following table:

Table 4-4: Historical Business Directory and other Records

Records	On-site	Off-site
Historical dry cleaners, motor garages and service stations	None	<p>There was one service station located approximately 400m to the south-east and cross-gradient of the site. Due to the distance from the site, this property was not considered to represent an off-site source of contamination.</p> <p>The records identified four other motor garage/service stations and two dry cleaner businesses within the report buffer. However, the businesses could only be matched to the road corridors of Loftus Street and Victoria Street. Loftus Street is adjacent to the south of the site, and extends south-west into the town centre, and Victoria Street is located further to the south.</p> <p>Review of the historical aerial photographs indicate the businesses were likely located to the south or west of the site and down/cross-gradient. On this basis, the businesses are considered unlikely to represent an off-site source of contamination.</p>
Other historical businesses that could represent potential sources of contamination	None	<p>The records identified automotive wrecking/scrap metal, panel beating/spray painting, motor trimming and upholstery, and engineering businesses within the report buffer. The businesses were mapped to the road corridor of Loftus Street.</p> <p>Review of the historical aerial photographs indicate the businesses were likely located to the south or west of the site and down/cross-gradient. On this basis, the businesses are considered unlikely to represent an off-site source of contamination.</p>
National waste management site database	None	None
National liquid fuel facilities	None	Five liquid fuel facilities were mapped within the report buffer. These were operational service stations located at



Records	On-site	Off-site
		least 780m from the site. Due to distances from the site, the service stations were not considered to represent a potential source of site contamination.
Mapped heritage items	The site in its entirety is heritage-listed under the Temora Local Environment Plan (LEP) 2010. Any remediation (if required) will be classified as Category 1 remediation and will require development consent.	Various heritage items were mapped in the report buffer. These are not considered to have any relevance in the context of the PSI objectives.
Mapped ecological constraints	None	Various ecological items were mapped in the report buffer. These are not considered to have any relevance in the context of the PSI objectives.
Mapped naturally occurring asbestos	None	None
Mining and exploration titles	There were several historical and current mining and exploration titles recorded for the site. The identified titles related to metallic minerals and mineral sands.	There was one current exploration title and one historical mining/exploration title for properties approximately 500m to the south-east and 960m to the north of the site. The titles related to metallic minerals and diamonds.

#### 4.7 Anecdotal Information

The Aboriginal Heritage Due Diligence Assessment report (refer to Section 2.1.5) identified that the foundation stone of the hospital was unveiled in 1938. The hospital was opened in 1940. An old house was originally sited on the location of the main hospital building and was relocated to the east and renovated for use as the nurse's quarters.

#### 4.8 Summary of Site History Information

A time line summary of the historical land uses and activities is presented in the following table. The information presented in the table is based on a weight of evidence assessment of the site history documentation and observations made by JKE.





Table 4-5: Summary of Historical Land Uses / Activities

Year(s)	On-site - Potential Land Use / Activities	Off-site - Potential Land Use / Activities
Prior to 1938	Residential and possibly agricultural (grazing).	Residential and agricultural (grazing).
1930 – 1940	Temora Hospital was constructed.	Residential and agricultural (grazing).
1940 - present	Hospital and associated activities.	Residential and agricultural (grazing).  2010s: Vocational education centre (TAFE) was constructed to the north of the site.

#### 4.9 Integrity of Site History Information

The majority of the site history information was obtained from government organisations as outlined in the relevant sections of this report. The veracity of the information from these sources is considered to be relatively high. A certain degree of information loss can be expected given the lack of specific land use details over time. JKE has relied upon the Lotsearch report and have not independently verified any information contained within. However, it is noted that the Lotsearch report is generated based on databases maintained by various government agencies and is expected to be reliable.

## 5 CONCEPTUAL SITE MODEL

NEPM (2013) defines a CSM as a representation of site related information regarding contamination sources, receptors and exposure pathways between those sources and receptors. The CSM for the site is presented in the following sub-sections and is based on the site information (including the site inspection information) and the review of site history information. Reference should also be made to the figures attached in the appendices.

A review of the CSM in relation to source, pathway and receptor (SPR) linkages has been undertaken as part of the Tier 1 risk assessment process, as outlined in Section 10.

### 5.1 Potential Contamination Sources/AEC and CoPC

The potential contamination sources/AEC and CoPC are presented in the following table:

Table 5-1: Potential (and/or known) Contamination Sources/AEC and Contaminants of Potential Concern

Source / AEC	CoPC
<u>Fill material</u> – The site appears to have been historically filled to achieve the existing levels. The fill may have been imported from various sources and could be contaminated.	Heavy metals (arsenic, cadmium, chromium, copper, lead, mercury, nickel and zinc), petroleum hydrocarbons (referred to as total recoverable hydrocarbons – TRHs), benzene, toluene, ethylbenzene and xylene (BTEX), polycyclic aromatic hydrocarbons (PAHs), organochlorine pesticides (OCPs), organophosphate pesticides (OPPs), PCBs and asbestos.
<u>Maintenance Workshop</u> – The site includes a maintenance workshop. It is possible that leaks/spills and/or releases of oils, solvents and fluids (e.g. turpentine/mineral spirits associated with typical painting activities, rather than chlorinated compounds) may have occurred.	Heavy metals, TRHs and PAHs.
<u>On-site Generator</u> – A back-up generator was observed to the west of the main hospital building. The generator appeared to be self-contained. Minor leaks and/or spills of fuel/oils may have occurred during maintenance and/or use.	TRH, BTEX and PAHs.
<u>Historical agricultural use</u> – Prior to 1938, the site was potentially used for agricultural purposes (likely grazing). This could have resulted in contamination across the site via use of machinery, application of pesticides and building/ demolition of various structures. Irrigation pipes made from asbestos cement may also be associated with this AEC.	Heavy metals, TRH, PAHs, OCPs, PCBs and asbestos.  JKE note that OCPs only became commercially available in the 1940s. Prior to this time pesticides were predominantly heavy metal compounds.
<u>Use of pesticides</u> – Pesticides may have been used beneath the buildings and/or around the site.	Heavy metals and OCPs.
<u>Hazardous Building Material</u> – Hazardous building materials may be present as a result of former building and demolition activities. These materials have also	Asbestos, lead and PCBs.

Source / AEC	CoPC
been identified by various HAZMAT surveys within the existing buildings/ structures on site.	
<u>On-site incinerator and Hospital Waste</u> – The site has been used as a hospital since at least 1940. An incinerator is located within the boiler room. Waste generated from the incinerator could have been disposed of on-site during the earlier years of operations, although there was no evidence identified by JKE confirming this. Disposal of human waste is unlikely to have occurred at the site.	Heavy metals, PAHs, heavy fraction TRH.

## 5.2 Mechanism for Contamination, Affected Media, Receptors and Exposure Pathways

The mechanisms for contamination, affected media, receptors and exposure pathways relevant to the potential contamination sources/AEC are outlined in the following CSM table:

Table 5-2: CSM

<b>Potential mechanism for contamination</b>	The potential mechanisms for contamination are most likely to include ‘top-down’ impacts and spills. There is a potential for sub-surface releases to have occurred if deep fill (or other buried industrial infrastructure) is present, although this is considered to be the least likely mechanism for contamination.
<b>Affected media</b>	Soil has been identified as the potentially affected medium. The potential for groundwater impacts is considered to be relatively low. However, groundwater would need to be considered in the event significant contamination (e.g. high concentrations of mobile/leachable contaminants) was identified in soil.
<b>Receptor identification</b>	Human receptors include site occupants/users (including adults and children) in a healthcare setting, construction workers and intrusive maintenance workers. Off-site human receptors include adjacent land users (in a residential setting) and groundwater users (recreation/irrigation use).  Ecological receptors include terrestrial organisms and plants within unpaved areas (including the proposed landscaped areas).
<b>Potential exposure pathways</b>	Potential exposure pathways relevant to the human receptors include ingestion, dermal absorption and inhalation of dust (all contaminants) and vapours (volatile TRH, naphthalene and BTEX), and primary/secondary contact with groundwater used for irrigation. The potential for exposure would typically be associated with the construction and excavation works, on-going and future use of the site, or groundwater use associated with the use of bore water. Potential exposure pathways for ecological receptors include primary/direct contact and ingestion.  Exposure during future site use could occur via direct contact with soil in unpaved areas such as gardens, inhalation of airborne asbestos fibres during soil disturbance, or inhalation of vapours within enclosed spaces such as buildings.
<b>Potential exposure mechanisms</b>	The following have been identified as potential exposure mechanisms for site contamination: <ul style="list-style-type: none"> <li>• Vapour intrusion into the buildings (from soil contamination);</li> <li>• Contact (dermal, ingestion or inhalation) with exposed soils in landscaped areas and/or unpaved areas; and</li> </ul>



	<ul style="list-style-type: none"><li>• Migration of groundwater off-site into areas where groundwater is being utilised as a resource (i.e. for irrigation).</li></ul>
<b>Presence of preferential pathways for contaminant movement</b>	Major services (i.e. on the BYDA plans) were not identified that would be expected to act as preferential pathways for contamination migration. However, it is noted that localised services are likely to exist that are not shown on those plans and the details of such services must be reviewed/considered in further detail in the event mobile contamination is identified.

---

## **6 SAMPLING, ANALYSIS AND QUALITY PLAN**

### **6.1 Data Quality Objectives (DQO)**

Data Quality Objectives (DQOs) were developed to define the type and quality of data required to achieve the project objectives outlined in Section 1.2. The DQOs were prepared with reference to the process outlined in Schedule B2 of NEPM (2013). The seven-step DQO approach for this project is outlined in the following sub-sections.

The DQO process is validated in part by the Data Quality Assurance/Quality Control (QA/QC) Evaluation. The Data (QA/QC) Evaluation is summarised in Section 8.1 and the detailed evaluation is provided in the appendices.

#### **6.1.1 Step 1 - State the Problem**

The CSM identified potential sources of contamination/AEC at the site that may pose a risk to human health and the environment. Investigation data is required to assess the contamination status of the site, assess the risks posed by the contaminants in the context of the proposed development/intended land use, and assess whether remediation is required.

#### **6.1.2 Step 2 - Identify the Decisions of the Study**

The objectives of the investigation are outlined in Section 1.2. The decisions to be made reflect these objectives and are as follows:

- Did the site inspection, or does the historical information identify potential contamination sources/AEC at the site?
- Are any results above the SAC?
- Do potential risks associated with contamination exist, and if so, what are they?
- Is remediation required?
- Is the site characterisation sufficient to provide adequate confidence in the above decisions?
- Is the site suitable for the proposed development, or can the site be made suitable subject to further characterisation and/or remediation?

#### **6.1.3 Step 3 - Identify Information Inputs**

The primary information inputs required to address the decisions outlined in Step 2 include the following:

- Site information, including site observations and site history documentation;
- Sampling of soil and FCF (if FCF was visible on the ground surface or in fill);
- Observations of sub-surface variables such as soil type, photo-ionisation detector (PID) concentrations, odours and staining;
- Laboratory analysis of soils and FCF for the CoPC identified in the CSM; and
- Field and laboratory QA/QC data.

#### **6.1.4 Step 4 - Define the Study Boundary**

The sampling was confined to the site boundaries as shown in Figure 2 and was limited vertically to a maximum borehole depth of 6mBGL (spatial boundary). The sampling was completed between 2 May 2023 and 5 May 2023 (temporal boundary). The assessment of potential risk to adjacent land users has been made based on data collected within the site boundary.

Sampling was not undertaken within the existing building footprints due to access constraints.

#### **6.1.5 Step 5 - Develop an Analytical Approach (or Decision Rule)**

##### **6.1.5.1 Tier 1 Screening Criteria**

The laboratory data will be assessed against relevant Tier 1 screening criteria (referred to as SAC), as outlined in Section 7. Exceedances of the SAC do not necessarily indicate a requirement for remediation or a risk to human health and/or the environment. Exceedances are considered in the context of the CSM and valid SPR-linkages.

For this investigation, the individual results have been assessed as either above or below the SAC. Statistical evaluation of the dataset via calculation of mean values and/or 95% upper confidence limit (UCL) values has not been undertaken due to the spatial distribution of the data and the number of samples submitted for analysis.

##### **6.1.5.2 Field and Laboratory QA/QC**

Field QA/QC included analysis of inter-laboratory duplicates, intra-laboratory duplicates, trip spike, trip blank and rinsate samples. Further details regarding the sampling and analysis undertaken, and the acceptable limits adopted, is provided in the Data Quality (QA/QC) Evaluation in the appendices.

The suitability of the laboratory data is assessed against the laboratory QA/QC criteria which is outlined in the attached laboratory reports. These criteria were developed and implemented in accordance with the laboratory's National Association of Testing Authorities, Australia (NATA) accreditation and align with the acceptable limits for QA/QC samples as outlined in NEPM (2013) and other relevant guidelines.

In the event that acceptable limits are not met by the laboratory analysis, other lines of evidence are reviewed (e.g. field observations of samples, preservation, handling etc) and, where required, consultation with the laboratory is undertaken in an effort to establish the cause of the non-conformance. Where uncertainty exists, JKE typically adopt the most conservative concentration reported (or in some cases, consider the data from the affected sample as an estimate).

##### **6.1.5.3 Appropriateness of Practical Quantitation Limits (PQLs)**

The PQLs of the analytical methods are considered in relation to the SAC to confirm that the PQLs are less than the SAC. In cases where the PQLs are greater than the SAC, a discussion of this is provided.

### 6.1.6 Step 6 – Specify Limits on Decision Errors

To limit the potential for decision errors, a range of quality assurance processes are adopted. A quantitative assessment of the potential for false positives and false negatives in the analytical results is undertaken with reference to Schedule B(3) of NEPM (2013) using the data quality assurance information collected.

Decision errors can be controlled through the use of hypothesis testing. The test can be used to show either that the baseline condition is false or that there is insufficient evidence to indicate that the baseline condition is false. The null hypothesis is an assumption that is assumed to be true in the absence of contrary evidence. For this investigation, the null hypothesis has been adopted which is that, there is considered to be a complete SPR linkage for the CoPC identified in the CSM unless this linkage can be proven not to (or unlikely to) exist. The null hypothesis has been adopted for this investigation.

Quantitative limits on decision errors were not established as the sample plan was not probabilistic.

Data Quality Indicators (DQI) for field and laboratory QA/QC samples are defined in the QA/QC Data Evaluation in the appendices. An assessment of the DQI's was made in relation to precision, accuracy, representativeness, completeness and comparability.

### 6.1.7 Step 7 - Optimise the Design for Obtaining Data

The most resource-effective design will be used in an optimum manner to achieve the investigation objectives. Adjustment of the investigation design can occur following consultation or feedback from project stakeholders. For this investigation, the design was optimised via consideration of the various lines of evidence used to select the sample locations, the media being sampled, and also by the way in which the data were collected concurrently with the geotechnical drilling.

The sampling plan and methodology are outlined in the following sub-sections.

## 6.2 Soil Sampling Plan and Methodology

The soil sampling plan and methodology adopted for this investigation is outlined in the table below:

Table 6-1: Soil Sampling Plan and Methodology

Aspect	Input
Sampling Density	<p>Samples were collected from 12 locations (BH1 to BH8 inclusive and TP13 to TP16 inclusive) as shown on the attached Figure 2. Based on the site area (31,770m<sup>2</sup>), this number of locations corresponded to a sampling density of approximately one sample per 2,650m<sup>2</sup>.</p> <p>The sampling plan was for a preliminary intrusive investigation and was not designed to meet the minimum sampling density for hotspot identification, as outlined in the NSW EPA Sampling Design Part 1 – Application (2022)<sup>16</sup> contaminated land guidelines, nor the minimum frequency of one sample location per 500m<sup>2</sup> outlined in DGN 030.</p>

<sup>16</sup> NSW EPA, (2022). *Sampling design part 1 - application*. (referred to as EPA Sampling Design Guidelines 2022)

Aspect	Input
	<p>The sampling plan was designed in accordance with the project brief outlined in the tender documentation.</p>
<p>Sampling Plan</p>	<p>The sampling locations were placed on a judgemental sampling plan targeting the proposed locations outlined in the tender documentation. JKE consider the locations were broadly positioned for site coverage. The final locations were determined onsite based on access constraints.</p> <p>This sampling plan was considered suitable to make a preliminary assessment of potential risks associated with the non-point source AEC and CoPC identified in the CSM, and assess whether further investigation is warranted.</p>
<p>Set-out and Sampling Equipment</p>	<p>Sampling locations were set out using a tape measure from existing site features. In-situ sampling locations were checked for underground services by an external contractor prior to sampling.</p> <p>Samples were collected using a combination of a drill rig equipped with spiral flight augers (150mm diameter) and an excavator.</p> <p>Soil samples collected from boreholes obtained from a Standard Penetration Test (SPT) split-spoon sampler, and/or directly from the auger. Soil samples collected from test pits were obtained from the test pit walls or directly from the bucket by hand. Where sampling occurred from the bucket, JKE collected samples from the central portion of large soil clods, or from material that was unlikely to have come into contact with the bucket.</p>
<p>Sample Collection and Field QA/QC</p>	<p>Soil samples were obtained between 2 and 5 May 2023 in accordance with our standard field procedures. Soil samples were collected from the fill and natural profiles based on field observations. The sample depths are shown on the logs attached in the appendices.</p> <p>Samples were placed in glass jars with plastic caps and Teflon seals with minimal headspace. Samples for asbestos analysis were placed in zip-lock plastic bags. During sampling, soil at selected depths was split into primary and duplicate samples for field QA/QC analysis. The field splitting procedure included alternately filling the sampling containers to obtain a representative split sample.</p>
<p>Field Screening</p>	<p>A portable PID fitted with a 10.6mV lamp was used to screen the samples for the presence of volatile organic compounds (VOCs). PID screening for VOCs was undertaken on soil samples using the soil sample headspace method. VOC data was obtained from partly filled zip-lock plastic bags following equilibration of the headspace gases. PID calibration records are maintained on file by JKE.</p> <p>The sensitivity of the PID is dependent on the organic compound and varies for different mixtures of hydrocarbons. Some compounds give relatively high readings and some can be undetectable even though present in identical concentrations. The portable PID is best used semi-quantitatively to compare samples contaminated by the same hydrocarbon source. The PID is calibrated before use by measurement of an isobutylene standard gas. All the PID measurements are quoted as parts per million (ppm) isobutylene equivalents.</p>



Aspect	Input
	<p>The field screening for asbestos quantification included the following:</p> <ul style="list-style-type: none"> <li>• A representative bulk sample was collected from fill at 1m intervals, or from each distinct fill profile. The quantity of material for each sample varied based on whatever return could be achieved using the auger. The bulk sample intervals are shown on the attached borehole and test pit logs;</li> <li>• Each sample was weighed using an electronic scale;</li> <li>• Each bulk sample was passed through a sieve with a 7.1mm aperture to the extent possible and inspected for the presence of fibre cement;</li> <li>• Due to the cohesive nature of some of the soils, some soil samples were placed on a contrasting support (blue tarpaulin) and inspected for the presence of fibre cement. Any soil clumps/nodules were disaggregated;</li> <li>• The condition of fibre cement or any other suspected asbestos materials was noted on the field records; and</li> <li>• If observed, any fragments of fibre cement in the bulk sample were collected, placed in a zip-lock bag and assigned a unique identifier. Calculations for asbestos content were undertaken based on the requirements outlined in Schedule B1 of NEPM (2013), as summarised in Section 7.1.</li> </ul> <p>A calibration/check of the accuracy of the scale used for weighing the fibre cement fragments was undertaken using a set of calibration weights. Calibration/check records are maintained on file by JKE. The scale used to weigh the 10L samples was not calibrated, however this is not considered significant as this method of providing a weight for the bulk sample is considered to be considerably more accurate than applying a nominal soil density conversion.</p>
Decontamination and Sample Preservation	<p>Sampling personnel used disposable nitrile gloves during sampling activities. Re-usable sampling equipment was decontaminated using Decon and potable water.</p> <p>Soil samples were preserved by immediate storage in an insulated sample container with ice. On completion of the fieldwork, the samples were stored temporarily in fridges in the JKE warehouse before being delivered in the insulated sample container to a NATA registered laboratory for analysis under standard chain of custody (COC) procedures.</p>

### 6.3 Analytical Schedule

The soils analysis typically targeted the fill soils and upper natural soils with samples from each location analysed for the CoPC relevant for fill soils. Deeper fill and natural soil samples were selected for heavy metals, BTEX/TRH and PAH, and asbestos in some instances, based on the encountered site conditions and to provide spatial coverage of the site.

JKE note that soil samples were not collected from BH9 to BH12 inclusive. These locations were shallow boreholes drilled by JKG to assess ground conditions for pavement design information. The soil contamination testing was targeted to the surrounds of the existing hospital buildings and areas that may be used for new builds.



### 6.3.1 Laboratory Analysis

Samples were analysed by an appropriate, NATA Accredited laboratory using the analytical methods detailed in Schedule B(3) of NEPM 2013. Reference should be made to the laboratory reports attached in the appendices for further details.

Table 6-2: Laboratory Details

Samples	Laboratory	Report Reference
All primary samples and field QA/QC samples including (intra-laboratory duplicates, trip blanks, trip spikes and field rinsate samples)	Envirolab Services Pty Ltd NSW, NATA Accreditation Number – 2901 (ISO/IEC 17025 compliance)	322581 & 322581-A
Inter-laboratory duplicates	Envirolab Services Pty Ltd VIC, NATA Accreditation Number – 2901 (ISO/IEC 17025 compliance)	37227 & 37227-A



## 7 SITE ASSESSMENT CRITERIA (SAC)

The SAC were derived from the NEPM 2013 and other guidelines as discussed in the following sub-sections. The guideline values for individual contaminants are presented in the attached report tables and further explanation of the various criteria adopted is provided in the appendices.

### 7.1 Soil

Soil data were compared to relevant Tier 1 screening criteria in accordance with NEPM (2013) as outlined below.

#### 7.1.1 Human Health

- Health Investigation Levels (HILs) for a ‘residential with accessible soils’ exposure scenario (HIL-A). HIL-A were selected as a conservative measure due to the extent of landscaping/unsealed areas and the limited information regarding potential development details;
- Health Screening Levels (HSLs) for a ‘low-high density residential’ exposure scenario (HSL-A & HSL-B). HSLs were calculated based on conservative assumptions including a ‘sand’ type and a depth interval of 0m to 1m;
- HSLs for direct contact presented in the CRC Care Technical Report No. 10 – Health screening levels for hydrocarbons in soil and groundwater Part 1: Technical development document (2011)<sup>17</sup>; and
- Asbestos was assessed against the HSL-A criteria in soil and as present or absent in FCF. A summary of the asbestos criteria is provided in the table below:

Table 7-1: Details for Asbestos SAC

Guideline	Applicability
Asbestos in Soil	<p>The HSL-A criteria were adopted for the assessment of asbestos in soil. The SAC adopted for asbestos were derived from the NEPM 2013 and are based on the Guidelines for the Assessment, Remediation and Management of Asbestos-Contaminated Sites in Western Australia (2021)<sup>18</sup>. The SAC include the following:</p> <ul style="list-style-type: none"> <li>• No visible asbestos at the surface/in the top 10cm of soil;</li> <li>• &lt;0.01% w/w bonded asbestos containing material (ACM) in soil; and</li> <li>• &lt;0.001% w/w asbestos fines/fibrous asbestos (AF/FA) in soil.</li> </ul> <p>Concentrations for bonded ACM concentrations in soil are based on the following equation which is presented in Schedule B1 of NEPM (2013):</p> $\% \text{ w/w asbestos in soil} = \frac{\% \text{ asbestos content} \times \text{bonded ACM (kg)}}{\text{Soil volume (L)} \times \text{soil density (kg/L)}}$ <p>However, we are of the opinion that the actual soil volume in a 10L bucket varies considerably due to the presence of voids, particularly when assessing cohesive soils. Therefore, each bucket sample was weighed using electronic scales and the above equation was adjusted as follows (we note that the units have also converted to grams):</p>

<sup>17</sup> Cooperative Research Centre for Contamination Assessment and Remediation of the Environment (CRC Care), (2011). Technical Report No. 10 - Health screening levels for hydrocarbons in soil and groundwater Part 1: Technical development document

<sup>18</sup> Western Australian (WA) Department of Health (DoH), (2021). Guidelines for the Assessment, Remediation and Management of Asbestos-Contaminated Sites in Western Australia. (referred to as WA DoH 2021)

Guideline	Applicability
	$\% \text{ w/w asbestos in soil} = \frac{\% \text{ asbestos content} \times \text{bonded ACM (g)}}{\text{Soil weight (g)}}$

### 7.1.2 Environment (Ecological – terrestrial ecosystems)

- Ecological Investigation Levels (EILs) and Ecological Screening Levels (ESLs) for an ‘urban residential and public open space’ (URPOS) exposure scenario. These have only been applied to the top 2m of soil as outlined in NEPM (2013). The criterion for benzo(a)pyrene has been increased from the value presented in NEPM (2013) based on the Canadian Soil Quality Guidelines<sup>19</sup>;
- ESLs were adopted based on the soil type; and
- EILs for selected metals were calculated based on the most conservative added contaminant limit (ACL) values presented in Schedule B(1) of NEPM (2013) and published ambient background concentration (ABC) values presented in the document titled Trace Element Concentrations in Soils from Rural and Urban Areas of Australia (1995)<sup>20</sup>. This method is considered to be adequate for the Tier 1 screening.

### 7.1.3 Management Limits for Petroleum Hydrocarbons

Management limits for petroleum hydrocarbons (as presented in Schedule B1 of NEPM 2013) were considered. Management limits were selected on the conservative assumption of ‘coarse’ type soils.

### 7.1.4 Waste Classification

Data for the waste classification assessment were assessed in accordance with the Waste Classification Guidelines, Part 1: Classifying Waste (2014)<sup>21</sup> as outlined in the following table:

Table 7-2: Waste Categories

Category	Description
General Solid Waste (non-putrescible)	<ul style="list-style-type: none"> <li>• If Specific Contaminant Concentration (SCC) ≤ Contaminant Threshold (CT1) then Toxicity Characteristics Leaching Procedure (TCLP) not needed to classify the soil as general solid waste; and</li> <li>• If TCLP ≤ TCLP1 and SCC ≤ SCC1 then treat as general solid waste.</li> </ul>
Restricted Solid Waste (non-putrescible)	<ul style="list-style-type: none"> <li>• If SCC ≤ CT2 then TCLP not needed to classify the soil as restricted solid waste; and</li> <li>• If TCLP ≤ TCLP2 and SCC ≤ SCC2 then treat as restricted solid waste.</li> </ul>
Hazardous Waste	<ul style="list-style-type: none"> <li>• If SCC &gt; CT2 then TCLP not needed to classify the soil as hazardous waste; and</li> <li>• If TCLP &gt; TCLP2 and/or SCC &gt; SCC2 then treat as hazardous waste.</li> </ul>
Virgin Excavated Natural Material (VENM)	Natural material (such as clay, gravel, sand, soil or rock fines) that meet the following: <ul style="list-style-type: none"> <li>• That has been excavated or quarried from areas that are not contaminated with manufactured chemicals, or with process residues, as a result of industrial, commercial mining or agricultural activities;</li> </ul>

<sup>19</sup> Canadian Council of Ministers of the Environment, (1999). *Canadian soil quality guidelines for the protection of environmental and human health: Benzo(a)Pyrene (1997)* (referred to as the Canadian Soil Quality Guidelines)

<sup>20</sup> Olszowy, H., Torr, P., and Imray, P., (1995), *Trace Element Concentrations in Soils from Rural and Urban Areas of Australia. Contaminated Sites Monograph Series No. 4.* Department of Human Services and Health, Environment Protection Agency, and South Australian Health Commission

<sup>21</sup> NSW EPA, (2014). *Waste Classification Guidelines, Part 1: Classifying Waste.* (referred to as Waste Classification Guidelines 2014)



Category	Description
	<ul style="list-style-type: none"><li>• That does not contain sulfidic ores or other waste; and</li><li>• Includes excavated natural material that meets such criteria for virgin excavated natural material as may be approved from time to time by a notice published in the NSW Government Gazette.</li></ul>

## 8 RESULTS

### 8.1 Summary of Data (QA/QC) Evaluation

The data evaluation is presented in the appendices. In summary, JKE is of the opinion that the data are adequately precise, accurate, representative, comparable and complete to serve as a basis for interpretation to achieve the investigation objectives.

### 8.2 Subsurface Conditions

A summary of the subsurface conditions encountered during the investigation is presented in the following table. Reference should be made to the borehole and test pit logs attached in the appendices for further details.

Table 8-1: Summary of Subsurface Conditions

Profile	Description
Pavement	AC pavement was encountered at the surface in BH7 and BH8 and was approximately 20mm thick.
Fill	Fill was encountered at the surface or beneath the pavement in BH2 to BH4, BH6 to BH8, and TP13 to TP15, and extended to depths of approximately 0.2mBGL to 1.1mBGL.  The fill typically comprised of silty and/or sandy clay and silty sand, with inclusions of gravel and boulders, volcanic breccia, metal fragments and root fibres. FCF was observed in fill in BH4.  No stained or odorous fill was encountered.
Natural Soil	Residual silty clay and sandy silty clay was encountered at the surface in BH1, BH5, BH9 to BH12 and TP16, and beneath the fill in all other locations with the exception of BH7. BH10, BH12, TP13 and TP15 were terminated in residual soil at depths of approximately 1.05mBGL to 1.5mBGL.  No stained or odorous soils were encountered during the investigation.
Bedrock	Weathered andesite bedrock was encountered beneath the fill in BH7 and beneath the residual clays in BH1 to BH6, BH8, BH9, BH11, TP14 and TP16 at depths of approximately 0.5mBGL to 2.1mBGL. The bedrock was typically extremely weathered on first contact.
Groundwater	Groundwater seepage was not encountered in the boreholes during auger drilling or in the test pits during excavation.  Some boreholes were advanced into the bedrock using rock coring methods, which introduces potable water into the boreholes. This inhibits meaningful observations of groundwater conditions during core drilling.

### 8.3 Field Screening

A summary of the field screening results is presented in the following table:

Table 8-2: Summary of Field Screening

Aspect	Details
PID Screening of Soil Samples for VOCs	PID soil sample headspace readings are presented in attached report tables and the COC documents attached in the appendices. The results ranged from 0ppm to 3.8ppm equivalent isobutylene. The results indicated that relatively low concentrations of PID detectable VOCs were detected in the majority of samples.
Bulk Screening for Asbestos	The bulk field screening results are summarised in Table S5 attached in the appendices. The ACM concentration in the sample screened from BH4 (0-0.2m) exceeded the SAC. All other results were below the SAC.

### 8.4 Soil Laboratory Results

The soil laboratory results were assessed against the SAC presented in Section 7.1. Individual SAC are shown in the report tables attached in the appendices. A summary of the results is presented below:

#### 8.4.1 Human Health and Environmental (Ecological) Assessment

Table 8-3: Summary of Soil Laboratory Results – Human Health and Environmental (Ecological)

Analyte	N	Max. (mg/kg)	N> Human Health SAC	N> Ecological SAC	Comments
Arsenic	30	15	0	0	-
Cadmium	30	<PQL	0	NSL	-
Chromium (total)	30	91	0	0	-
Copper	30	490	0	25	<p>Copper concentrations exceeded the ecological SAC in eight fill soil samples collected from BH2 (0-0.2m), BH3 (0.3-0.5m), BH4 (0-0.1m), BH6 (0-0.1m), BH7 (0.02-0.3m), BH7 (0.02-0.3m) TP13 (0-0.1m), and TP14 (0-0.1m).</p> <p>Copper concentrations exceeded the ecological SAC in 17 natural soil/rock samples collected from BH1 (0.8-1m), BH2 (0.3-0.5m, and 0.8-1m), BH3 (1.3-1.5m), BH4 (0.3-0.5m and 0.8-1m), BH5 (0-0.1m and 0.8-1m), BH6 (0.3-0.5m and 0.8-1m), BH7 (0.3-0.5m), BH8 (0.3-0.5m), TP13 (0.5-0.6), TP14 (0.4-0.5m and 0.9-1m), TP15 (1.3-1.5m) and TP16 (0-0.1 and 0.4-0.5m).</p> <p>The copper concentrations recorded in the majority of the field and laboratory</p>



Analyte	N	Max. (mg/kg)	N> Human Health SAC	N> Ecological SAC	Comments
					duplicate samples also exceeded the ecological SAC.
Lead	30	170	0	0	-
Mercury	30	0.7	0	NSL	-
Nickel	30	18	0	0	-
Zinc	30	140	0	0	-
Total PAHs	30	85	0	NSL	-
Benzo(a)pyrene	30	5.4	NSL	0	-
Carcinogenic PAHs (as BaP TEQ)	30	7.7	3	NSL	Carcinogenic PAH concentrations exceeded the human health SAC in three fill soil samples collected from BH3 (0.3-0.5m), BH8 (0.02-0.2m), and TP15 (0.9-1m).
Naphthalene	30	2	0	NSL	-
DDT+DDE+DDD	14	<PQL	0	NSL	-
DDT	14	<PQL	NSL	0	-
Aldrin and dieldrin	14	<PQL	0	NSL	-
Chlordane	14	<PQL	0	NSL	-
Heptachlor	14	<PQL	0	NSL	-
Chlorpyrifos (OPP)	14	<PQL	0	NSL	-
PCBs	14	<PQL	0	NSL	-
TRH F1	30	<PQL	0	0	-
TRH F2	30	<PQL	0	0	-
TRH F3	30	320	0	0	-
TRH F4	30	230	0	0	-
Benzene	30	<PQL	0	0	-
Toluene	30	<PQL	0	0	-
Ethylbenzene	30	<PQL	0	0	-



Analyte	N	Max. (mg/kg)	N> Human Health SAC	N> Ecological SAC	Comments
Xylenes	30	<PQL	0	0	-
Asbestos (in soil) (%w/w)	14	ACM <0.01 AF/FA <0.001	0	NA	Asbestos was not identified within the 500mL samples submitted for laboratory analysis.
Asbestos in fibre cement	2	Detect	2	NSL	Laboratory analysis confirmed the two FCF collected from BH4 (0-0.2m) during bulk quantification contained asbestos.

**Notes:**

N: Total number (primary samples)

NSL: No set limit

NL: Not limiting

### 8.4.2 TRH Management Limits

The laboratory results were assessed against the criteria presented in Section 7.1.3. All TRH results were below the TRH management limits. The results are presented in Table S4 attached in the appendices.

### 8.4.3 Waste Classification Assessment

The laboratory results were assessed against the criteria presented in Section 7.1.4. The results are presented in the report tables attached in the appendices. A summary of the results is presented in the following table:

Table 8-4: Summary of Soil Laboratory Results Compared to CT and SCC Criteria

Analyte	N	N > CT Criteria	N > SCC Criteria	Comments
Arsenic	30	0	0	-
Cadmium	30	0	0	-
Chromium	30	0	0	-
Copper	30	NSL	NSL	-
Lead	30	1	0	The lead concentrations exceeded the CT1 criterion in the primary fill soil sample collected from TP14 (0-0.1m) and in the field duplicate sample (SDUP3). The maximum lead concentration was 170mg/kg.
Mercury	30	0	0	-
Nickel	30	0	0	-
Zinc	30	NSL	NSL	-

Analyte	N	N > CT Criteria	N > SCC Criteria	Comments
TRH (C <sub>6</sub> -C <sub>9</sub> )	30	0	0	-
TRH (C <sub>10</sub> -C <sub>36</sub> )	30	0	0	-
BTEX	30	0	0	-
Total PAHs	30	0	0	-
Benzo(a)pyrene	30	3	0	Benzo(a)pyrene concentrations exceeded the CT2 criterion in two fill soil samples collected from BH3 (0.3-0.5m) and TP15 (0.9-1.0m). A benzo(a)pyrene concentration exceeded the CT1 criterion in one fill soil sample collected from BH8 (0.02-0.2m) The maximum benzo(a)pyrene concentration was 5.4mg/kg.
OCPs & OPPs	14	0	0	-
PCBs	14	0	0	-
Asbestos in soil	14	-	-	Asbestos was not detected in the soil samples analysed.
Asbestos in fibre cement	2	-	-	Asbestos was identified in two FCF collected from BH4 (0-0.2m).

N: Total number (primary samples)

NSL: No set limit

Table 8-5: Summary of Soil Laboratory Results Compared to TCLP Criteria

Analyte	N	N > TCLP Criteria	Comments
Lead	1	0	The primary fill soil sample (and its field duplicate) with lead concentration above the CT1 criterion was analysed for TCLP lead. The TCLP lead results were below the TCLP1 criterion of 5mg/L. The maximum TCLP lead concentration was 0.3mg/L.
Benzo(a)pyrene	3	0	Three fill soil samples with benzo(a)pyrene concentrations above the CT1/CT2 criteria were analysed for TCLP benzo(a)pyrene. All TCLP benzo(a)pyrene results were below the TCLP1 criterion of 0.04mg/L. The maximum TCLP benzo(a)pyrene concentration was 0.0086mg/L.

N: Total number (primary samples)



---

## 9 PRELIMINARY WASTE CLASSIFICATION ASSESSMENT

### 9.1 Preliminary Waste Classification of Fill

Based on the available results, and at the time of reporting, the fill material is assigned the following preliminary classifications:

- Fill in the vicinity of BH4 is assigned a preliminary classification of **General Solid Waste (non-putrescible) containing Special Waste (asbestos)**; and
- Fill in other areas tested as part of this investigation is assigned a preliminary classification of **General Solid Waste (non-putrescible)**.

Further assessment including additional testing is required to confirm the extent of asbestos impacts, the above preliminary classifications and the final waste classification prior to off-site disposal. The anticipated waste quantities should also be confirmed at that time and documented in the report.

### 9.2 Preliminary Classification of Natural Soil and Bedrock

Based on the available results, and at the time of reporting, the natural silty clay and sandy silty clay soil is assigned a preliminary classification of **General Solid Waste (non-putrescible)** due to the elevated PAH concentrations recorded in several samples. JKE note that low levels of PAHs may be naturally occurring, though there is uncertainty as to the source of the elevated PAH concentrations at each location. It is also acknowledged that some samples were collected from near the interface with overlying fill, and that deeper natural soils may record negligible PAH concentrations.

Based on the available results, and at the time of reporting, JKE is of the opinion that the andesite bedrock within the site will likely meet the definition of **VENM** for off-site disposal or re-use purposes. JKE note that naturally elevated copper concentrations were recorded within the bedrock (up to 470mg/kg) which may pose risk to ecological receptors depending on the proposed re-use scenario. Though the bedrock will likely meet the definition of VENM, an assessment will also be required to confirm the bedrock is suitable from a contamination risk perspective in the context of the proposed re-use.

Further assessment is required to confirm these classifications prior to off-site disposal of the waste. The anticipated waste quantities should also be confirmed at that time and documented in the report.

## **10 DISCUSSION**

### **10.1 Contamination Sources/AEC and Potential for Site Contamination**

Based on the scope of work undertaken for this investigation, JKE identified the following potential contamination sources/AEC:

- Historic filling activities;
- Historic agricultural activities;
- Use of pesticides;
- Hazardous building materials present within existing and/or former structures;
- On-site generator and associated fuel storage;
- Maintenance workshop; and
- On-site incinerator and hospital activities.

Considering the above, and based on a qualitative assessment of various lines of evidence as discussed throughout this report, JKE is of the opinion that there is a potential for site contamination. The preliminary soil data collected for the investigation is discussed further in the following subsection, as part of the Tier 1 risk assessment.

### **10.2 Tier 1 Risk Assessment and Review of CSM**

For a contaminant to represent a risk to a receptor, the following three conditions must be present:

1. Source – The presence of a contaminant;
2. Pathway – A mechanism or action by which a receptor can become exposed to the contaminant; and
3. Receptor – The human or ecological entity which may be adversely impacted following exposure to contamination.

If one of the above components is missing, the potential for adverse risks is relatively low.

JKE note that the SAC selected were based on conservative assumptions to account for the extent of landscaped/unsealed areas and the limited information regarding potential development details. The SAC may be reviewed once further development details are known.

#### **10.2.1 Asbestos**

Asbestos, in the form of bonded (non-friable) FCF/ACM, was identified in the surficial (0-200mm) fill soil in BH4 at a concentration above the human health SAC. BH4 was located in the eastern portion of the site, to the north of the nurses' accommodation building, as shown on Figure 4 attached in the appendices. The source of the asbestos was considered to likely be associated with historic demolition and disposal activities and/or impacted fill historically imported to the site.

BH4 was located in an unsealed area within the east of the site. The site is currently occupied and the area in the vicinity of BH4 is readily accessible to site occupants/workers and visitors. As such, the soils in these areas may be disturbed. On this basis, a complete SPR linkage could be realised and the asbestos is considered to pose a potential risk to human health if the soil/asbestos is disturbed. Remediation will be required to

address the potential risk. Interim measures should be undertaken to mitigate potential risk to the current site occupants/workers and visitors.

On completion of all boreholes and test pits, a walkover inspection of the surface of all sampling locations and their immediate vicinity was undertaken by JKE. No visible FCF/ACM remained at the surface on the completion of reinstating the test pit and borehole locations.

JKE recommend preparing an Asbestos Management Plan (AMP) to outline the management strategy for addressing the risks posed by the FCF/ACM in soils.

### **10.2.2 Heavy Metals**

Copper was identified in the majority of soil samples and at all sampling locations (BH1 to BH8 inclusive, TP13 to TP16 inclusive), at concentrations above the ecological SAC. The SAC exceedances are shown on Figure 4 attached in the appendices. The concentrations typically increased with depth, with the highest concentrations recorded within the deeper residual silty clay, sandy silty clay and underlying andesite bedrock.

JKE note that the Lotsearch report identified current and historic mining and exploration titles within the vicinity of the site. The mining and exploration titles related to metallic minerals and mineral sands, and specifically identified copper, gold and silver as targeted metallic minerals, indicating that elevated concentrations of copper within the regional area is to be expected.

Considering multiple lines of evidence, JKE is of the opinion that the copper concentrations recorded within the soil and rock samples are representative of regional conditions rather than indicative of potential soil contamination resulting from a site-specific activity. Further, the existing vegetation appeared healthy (based on a cursory inspection) with no obvious indications of stress/die-back. On this basis, JKE is of the opinion it is unlikely for unacceptable, copper-related risk to exist for ecological receptors at the site.

Though the elevated copper concentrations are considered unlikely to pose an unacceptable risk to ecological receptors in the context of the proposed development, consideration should be given during the development planning of any required cut/fill to avoid placement of deeper soils and rock near the surface. Within new landscaping areas, the use of appropriate growing mediums (i.e. approved topsoil) and/or copper-tolerant plantings should be considered. Further advice in this regard should be obtained from the appointed project arborist.

All remaining heavy metal concentrations were below the ecological SAC. All heavy metal concentrations were below the human health SAC.

### **10.2.3 Hydrocarbons**

Carcinogenic PAHs were identified in the shallow fill soils in BH3 and BH8, and within deeper fill soils in TP15, at concentrations above the human health SAC. BH3 and TP15 were located within the central portion of the site, to the north-west of the nurses' accommodation, and BH8 was located within the northern portion of the site, to the south-west of the main hospital building, as shown on Figure 4 attached in the appendices.

The source of the carcinogenic PAHs was considered likely to be associated with impacted fill imported to the site, and to a lesser extent, surficial leaks/spills. The results of leachate analysis indicated low potential for the PAHs to migrate (leach) into the underlying soils and groundwater. On this basis, the impacts were considered to likely be confined to the fill soils.

BH3 and TP15 were located within an unsealed portion of the site, to the west of the main driveway. It is noted that the elevated carcinogenic PAH concentrations in TP15 were recorded at a depth greater than 0.5mBGL, however given the proximity to BH3 which encountered elevated PAH concentrations in shallow fill (at a depth of approximately 0.3mBGL), there is potential for elevated PAH concentrations to be encountered in shallow fill soils. As these areas were unsealed, and elevated carcinogenic PAH concentrations were recorded within shallow fill soils, there is potential for a complete SPR linkage to exist once the soils are disturbed (i.e. excavation, erosion). It is noted that the surficial soil samples collected from BH3 and TP15 recorded low carcinogenic PAH concentrations (below the human health SAC), indicating the elevated carcinogenic PAHs concentrations recorded in the underlying fill do not present an immediate risk to human health, provided they remain undisturbed.

BH8 was located within the main driveway area and was sealed with a thin (20mm thickness) AC pavement. However, the pavement was considered to be in moderate to poor condition with cracked sections and unrepaired potholes. Due to the moderate to poor condition of the AC pavement and the fact that elevated carcinogenic PAH concentrations were recorded in the shallow fill immediately underlying the AC pavement, JKE consider there is potential for a complete SPR linkage to be realised.

Remediation may be required to address the potential risks to human health by carcinogenic PAHs in fill soils. This will need to be further evaluated following the detailed investigation as statistical analysis and/or site-specific risk assessment may establish that remediation is not necessary. The detected concentrations do not pose an unacceptable risk to ecological receptors.

All remaining BTEX/TRH and PAH concentrations were below the human health SAC. All BTEX/TRH and PAH concentrations were below the ecological SAC.

#### **10.2.4 Other CoPC in Soil**

All remaining CoPC in soil were below the relevant SAC.

### **10.3 Decision Statements**

The decision statements are addressed below:

*Did the site inspection, or does the historical information identify potential contamination sources/AEC at the site?*

Yes, as discussed in Section 10.1.

*Are any results above the SAC?*

Yes, as discussed in Section 8.4.

*Do potential risks associated with contamination exist, and if so, what are they?*

Yes. The surficial FCF/ACM in the vicinity of BH4 and the carcinogenic PAHs within fill soils in BH3, BH8 and TP15 were assessed to pose a potential risk to human health.

*Is remediation required?*

Yes. Based on the existing data, remediation is required to address the potential risks to human health posed by asbestos in the form of FCF/ACM. Remediation may also be required in relation to carcinogenic PAHs in fill soils.

*Is the site characterisation sufficient to provide adequate confidence in the above decisions?*

Further investigation is required to better assess the potential risks posed to human health and ecological receptors, and to inform the preparation of a Remediation Action Plan (RAP).

*Is the site suitable for the proposed development, or can the site be made suitable subject to further characterisation and/or remediation?*

JKE is of the opinion that the site can be made suitable for the proposed development via remediation. A detailed (stage 2) site investigation (DSI) is required to better assess the risks associated with the potential contamination sources /AEC and the identified CoPC, and to inform the preparation of a RAP.

## 10.4 Data Gaps

An assessment of data gaps is provided in the following table:

Table 10-1: Data Gap Assessment

Data Gap	Assessment
Groundwater flow direction and contaminant condition not assessed	Based on the site history and the results reported, the potential for groundwater contamination to pose a risk to the receptors is considered to be low. Additional work to address this data gap is not recommended at this stage.
Soil sampling density below minimum guideline density	Sampling was limited to approximately 30% of the minimum sampling density recommended in the EPA Sampling Design Guidelines 2022, and approximately 20% of the minimum sampling density recommended in DGN 030. The investigation identified fill containing demolition waste including FCF/ACM, and elevated concentrations of PAHs. Recommendations for additional soil sampling are included in the report to address this data gap.
Building footprints not assessed.	The nominated sampling locations were positioned outside of the building footprints. The fill and soil conditions beneath the building footprints are currently unknown. JKE note that the proposed development details are unknown and the buildings may be retained. In the event that the existing buildings are not retained, further investigation beneath the building footprints is recommended following demolition. The requirements for

Data Gap	Assessment
	<p>assessing risks in the building footprints must be considered as part of the DSI process.</p>
<p>Asbestos quantification undertaken using boreholes.</p>	<p>Asbestos quantification was undertaken from boreholes (150mm nominal diameter) for some locations. Though acceptable, the WA DoH (2021) guidance recommends the use of test pits where possible. The WA DoH (2021) guidance also recommends that where a site is known to be impacted by asbestos, quantification sampling should be conducted at twice the recommended minimum sampling density.</p> <p>Additional sampling is recommended to quantify the extent of asbestos impacts at the site. Test pits should be used where possible for the additional asbestos quantification sampling.</p>
<p>PAH source within natural soils not confirmed.</p>	<p>Detectable concentrations of PAHs were recorded within several samples collected from the natural silty clay and sandy silty clay soils across the site. The concentrations recorded in the natural soils did not pose an unacceptable risk to receptors, though may compromise classification of the soils as VENM. Low PAH concentrations may be naturally occurring in soils, though may also be attributable to atmospheric/surficial impacts where natural soils are exposed at the surface, and/or from overlying fill where natural soils were sampled near the fill/natural soil interface.</p> <p>Additional investigation is required to assess the lateral and vertical distribution of PAHs within the natural soil. The further investigation is primarily required for waste classification purposes. JKE recommend that the additional investigation is undertaken using push-tube sampling techniques where practicable.</p>

## 10.5 Potential Remediation & Management Options

Further investigation of the soil contamination conditions is required. The below discussion is based on the available data at the time of reporting. The further investigation(s) will inform the feasibility of the below remediation/management options. Any remediation/management strategy will need to be outlined in a RAP.

Based on the findings of this investigation, the primary concerns identified in relation to soil were the presence of asbestos and elevated concentrations of carcinogenic PAHs within fill soils. The surficial FCF/ACM impacts can be managed in the short term by 'emu-picking', followed by a clearance inspection and certificate by a SafeWork NSW licensed asbestos assessor (LAA), and then suitable site/asbestos management.

In the context of remediation, asbestos-impacted soils and/or PAH-impacted soils may be remediated by:

- Consolidation of impacted soils in a dedicated containment cell, or capped in-situ, and managed long-term in accordance with an Environmental Management Plan (EMP); or
- Excavated and disposed off-site at an appropriately licensed landfill facility.

JKE note that widespread concentrations of copper above the ecological SAC were also identified within the fill and natural soils and bedrock. These exceedances should be considered during proposed earthworks (cut/fill) so that the soils containing elevated concentrations of copper are not placed within landscaped or





---

unpaved areas. Consideration should be given to the importation of validated appropriate growing medium for landscaped areas. The detected concentrations of copper do not pose a risk to human health.



## 11 CONCLUSIONS AND RECOMMENDATIONS

The investigation included a review of historical information and soil sampling from 12 locations. The site was historically used for residential and agricultural (grazing) purposes until the late 1930s, and has been used for a hospital since.

The investigation encountered fill and/or clay soils to depths of approximately, underlain by andesite bedrock. The maximum depth of fill encountered was 1.1m. Groundwater was not encountered during the investigation. The fill typically comprised of silty and/or sandy clay and silty sand, with inclusions of gravel and boulders, volcanic breccia, metal fragments and root fibres. FCF/ACM was observed in surficial fill in BH4.

The investigation identified fill soils impacted by asbestos and carcinogenic PAHs at concentrations that were above the adopted SAC. Elevated copper concentrations above the SAC were also identified in the majority of the analysed fill, natural soil and rock samples though were considered to be representative of the regional conditions.

Based on the findings of the investigation, JKE is of the opinion that the site can be made suitable for the proposed development via remediation. The following is recommended:

- A surface walkover and 'emu-picking' of all visible FCF/ACM from the site surface should be undertaken and an asbestos clearance certificate obtained from an LAA;
- Interim management of the site is to occur under an AMP, until remediation occurs;
- The earthworks and any re-use of material is to adequately consider the presence of copper in the soil in relation to waste classification and potential ecological risks, as discussed in Section 10 of this report;
- Undertake a DSI to better assess the risks associated with the AEC/potential sources of contamination and inform preparation of a RAP. The DSI should address the data gaps identified in Section 10.4 of this report. A SAQP should be prepared for the DSI prior to commencement of the investigation;
- A RAP is to be prepared to address the contamination issues identified at the site; and
- The site is to be managed, remediated and validated in accordance with the RAP and AMP.

At this stage, JKE consider there is no requirement to notify the NSW EPA under the NSW EPA Guidelines on the Duty to Report Contamination under Section 60 of the CLM Act 1997 (2015)<sup>22</sup>. The duty to report should be reconsidered following completion of each stage of additional work recommended above.

JKE consider that the report objectives outlined in Section 1.2 have been addressed.

---

<sup>22</sup> NSW EPA, (2015). *Guidelines on the Duty to Report Contamination under Section 60 of the CLM Act 1997* (referred to as Duty to Report Contamination)



---

## 12 LIMITATIONS

The report limitations are outlined below:

- JKE accepts no responsibility for any unidentified contamination issues at the site. Any unexpected problems/subsurface features that may be encountered during development works should be inspected by an environmental consultant as soon as possible;
- Previous use of this site may have involved excavation for the foundations of buildings, services, and similar facilities. In addition, unrecorded excavation and burial of material may have occurred on the site. Backfilling of excavations could have been undertaken with potentially contaminated material that may be discovered in discrete, isolated locations across the site during construction work;
- This report has been prepared based on site conditions which existed at the time of the investigation; scope of work and limitation outlined in the JKE proposal; and terms of contract between JKE and the client (as applicable);
- The conclusions presented in this report are based on investigation of conditions at specific locations, chosen to be as representative as possible under the given circumstances, visual observations of the site and immediate surrounds and documents reviewed as described in the report;
- Subsurface soil and rock conditions encountered between investigation locations may be found to be different from those expected. Groundwater conditions may also vary, especially after climatic changes;
- The investigation and preparation of this report have been undertaken in accordance with accepted practice for environmental consultants, with reference to applicable environmental regulatory authority and industry standards, guidelines and the assessment criteria outlined in the report;
- Where information has been provided by third parties, JKE has not undertaken any verification process, except where specifically stated in the report;
- JKE has not undertaken any assessment of off-site areas that may be potential contamination sources or may have been impacted by site contamination, except where specifically stated in the report;
- JKE accept no responsibility for potentially asbestos containing materials that may exist at the site. These materials may be associated with demolition of pre-1990 constructed buildings or fill material at the site;
- JKE have not and will not make any determination regarding finances associated with the site;
- Additional investigation work may be required in the event of changes to the proposed development or land use. JKE should be contacted immediately in such circumstances;
- Material considered to be suitable from a geotechnical point of view may be unsatisfactory from a soil contamination viewpoint, and vice versa; and
- This report has been prepared for the particular project described and no responsibility is accepted for the use of any part of this report in any other context or for any other purpose.



---

## Important Information About This Report

These notes have been prepared by JKE to assist with the assessment and interpretation of this report.

### **The Report is based on a Unique Set of Project Specific Factors**

This report has been prepared in response to specific project requirements as stated in the JKE proposal document which may have been limited by instructions from the client. This report should be reviewed, and if necessary, revised if any of the following occur:

- The proposed land use is altered;
- The defined subject site is increased or sub-divided;
- The proposed development details including size, configuration, location, orientation of the structures or landscaped areas are modified;
- The proposed development levels are altered, eg addition of basement levels; or
- Ownership of the site changes.

JKE will not accept any responsibility whatsoever for situations where one or more of the above factors have changed since completion of the investigation. If the subject site is sold, ownership of the investigation report should be transferred by JKE to the new site owners who will be informed of the conditions and limitations under which the investigation was undertaken. No person should apply an investigation for any purpose other than that originally intended without first conferring with the consultant.

### **Changes in Subsurface Conditions**

Subsurface conditions are influenced by natural geological and hydrogeological process and human activities. Groundwater conditions are likely to vary over time with changes in climatic conditions and human activities within the catchment (e.g. water extraction for irrigation or industrial uses, subsurface waste water disposal, construction related dewatering). Soil and groundwater contaminant concentrations may also vary over time through contaminant migration, natural attenuation of organic contaminants, ongoing contaminating activities and placement or removal of fill material. The conclusions of an investigation report may have been affected by the above factors if a significant period of time has elapsed prior to commencement of the proposed development.

### **This Report is based on Professional Interpretations of Factual Data**

Site investigations identify actual subsurface conditions at the actual sampling locations at the time of the investigation. Data obtained from the sampling and subsequent laboratory analyses, available site history information and published regional information is interpreted by geologists, engineers or environmental scientists and opinions are drawn about the overall subsurface conditions, the nature and extent of contamination, the likely impact on the proposed development and appropriate remediation measures.

Actual conditions may differ from those inferred, because no professional, no matter how qualified, and no subsurface exploration program, no matter how comprehensive, can reveal what is hidden by earth, rock and time. The actual interface between materials may be far more gradual or abrupt than an investigation indicates. Actual conditions in areas not sampled may differ from predictions. Nothing can be done to prevent the unanticipated, but steps can be taken to help minimise the impact. For this reason, site owners should retain the services of their consultants throughout the development stage of the project, to identify variances, conduct additional tests which may be needed, and to recommend solutions to problems encountered on site.

### **Investigation Limitations**

Although information provided by a site investigation can reduce exposure to the risk of the presence of contamination, no environmental site investigation can eliminate the risk. Even a rigorous professional investigation may not detect all contamination on a site. Contaminants may be present in areas that were not surveyed or sampled, or may migrate to areas which showed no signs of contamination when sampled. Contaminant analysis cannot possibly cover every type of contaminant which may occur; only the most likely contaminants are screened.



---

### **Misinterpretation of Site Investigations by Design Professionals**

Costly problems can occur when other design professionals develop plans based on misinterpretation of an investigation report. To minimise problems associated with misinterpretations, the environmental consultant should be retained to work with appropriate professionals to explain relevant findings and to review the adequacy of plans and specifications relevant to contamination issues.

### **Logs Should not be Separated from the Investigation Report**

Borehole and test pit logs are prepared by environmental scientists, engineers or geologists based upon interpretation of field conditions and laboratory evaluation of field samples. Logs are normally provided in our reports and these should not be re-drawn for inclusion in site remediation or other design drawings, as subtle but significant drafting errors or omissions may occur in the transfer process. Photographic reproduction can eliminate this problem, however contractors can still misinterpret the logs during bid preparation if separated from the text of the investigation. If this occurs, delays, disputes and unanticipated costs may result. In all cases it is necessary to refer to the rest of the report to obtain a proper understanding of the investigation. Please note that logs with the 'Environmental Log' header are not suitable for geotechnical purposes as they have not been peer reviewed by a Senior Geotechnical Engineer.

To reduce the likelihood of borehole and test pit log misinterpretation, the complete investigation should be available to persons or organisations involved in the project, such as contractors, for their use. Denial of such access and disclaiming responsibility for the accuracy of subsurface information does not insulate an owner from the attendant liability. It is critical that the site owner provides all available site information to persons and organisations such as contractors.

### **Read Responsibility Clauses Closely**

Because an environmental site investigation is based extensively on judgement and opinion, it is necessarily less exact than other disciplines. This situation has resulted in wholly unwarranted claims being lodged against consultants. To help prevent this problem, model clauses have been developed for use in written transmittals. These are definitive clauses designed to indicate consultant responsibility. Their use helps all parties involved recognise individual responsibilities and formulate appropriate action. Some of these definitive clauses are likely to appear in the environmental site investigation, and you are encouraged to read them closely. Your consultant will be pleased to give full and frank answers to any questions.



---

## Appendix A: Report Figures



SOURCE: <http://www.wherereis.com/>




AERIAL IMAGE SOURCE: [MAPS.AU.NEARMAP.COM](https://maps.au.nearmap.com)


Title:		<b>SITE LOCATION PLAN</b>	
Location:		169-189 LOFTUS STREET, TEMORA, NSW	
Project No:	E35822PR	Figure No:	1
<b>JKEnvironments</b>			



This plan should be read in conjunction with the Environmental report.



**LEGEND**  
 - - - - - APPROXIMATE SITE BOUNDARY



Title: <b>SITE FEATURES PLAN</b>	
Location: 169-189 LOFTUS STREET, TEMORA, NSW	
Project No: E35822PR	Figure No: 2
<b>JKEnvironments</b>	








**LEGEND**


	APPROXIMATE SITE BOUNDARY
	BH(Fill Depth)
	TP(Fill Depth)
	BOREHOLE LOCATION, NUMBER AND DEPTH OF FILL (m)
	TEST PIT LOCATION, NUMBER AND DEPTH OF FILL (m)



Title: <b>SAMPLE LOCATION PLAN</b>	
Location: 169-189 LOFTUS STREET, TEMORA, NSW	
Project No: E35822PR	Figure No: 3
<b>JKEnvironments</b>	




PLOT DATE: 18/05/2023 1:43:06 PM DWG FILE: K:\5C EIS JOBS\35007\5E35822PR TEMORA\CAD\E35822PR.DWG



**LEGEND**

- APPROXIMATE SITE BOUNDARY
  - BH(Fill Depth) BOREHOLE LOCATION, NUMBER AND DEPTH OF FILL (m)
  - ⊕ BH/MW(Fill Depth) BOREHOLE AND GROUNDWATER MONITORING WELL LOCATION, NUMBER AND DEPTH OF FILL (m)
- | SAMPLE ID   | DEPTH (metres) | SOIL/SURFACE SAMPLE EXCEEDANCE                             |
|---|----------------|--|
| CHEMICAL  | CONCENTRATION  |  |
| <span style="background-color: yellow; width: 15px; height: 10px; display: inline-block;"></span> |                | SOIL/SURFACE CONTAMINATION ABOVE SAC FOR HUMAN HEALTH RISK |
| <span style="background-color: green; width: 15px; height: 10px; display: inline-block;"></span>  |                | SOIL/SURFACE CONTAMINATION ABOVE SAC FOR ECOLOGICAL RISK   |



Title: <b>SAC EXCEEDANCE PLAN</b>	
Location: 169-189 LOFTUS STREET, TEMORA, NSW	
Project No: E35822PR	Figure No: 4
<b>JKEnvironments</b>	





---

## **Appendix B: Site Information and Site History**



---

## Selected Site Photographs



Photograph 1: Main hospital building



Photograph 2: Nurses' accommodation



Photograph 3: Maintenance building and Day centre building



Photograph 4: Plant Room



Photograph 5: Maintenance building



Photograph 6: Fire extinguishers in Maintenance building



Photograph 7: Boilers in Boiler room



Photograph 8: Incinerator in Boiler room



Photograph 9: Generator



Photograph 10: Electrical substation



Photograph 11: Exposed fill soils at surface




Photograph 12: Evidence of cut/fill




Photograph 13: TP14 excavation



Photograph 14: TP15 Excavation



Photograph 15: BH4-FCF1



Photograph 16: BH4 - FCF2





---

## **Lotsearch Environmental Risk and Planning Report**



# LOTSEARCH

LOTSEARCH ENVIRO PROFESSIONAL

**Date: 28 Mar 2023 15:58:33**

**Reference: LS041987 EP**

**Address: Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666**

**Disclaimer:**

The purpose of this report is to provide an overview of some of the site history, environmental risk and planning information available, affecting an individual address or geographical area in which the property is located. It is not a substitute for an on-site inspection or review of other available reports and records. It is not intended to be, and should not be taken to be, a rating or assessment of the desirability or market value of the property or its features. You should obtain independent advice before you make any decision based on the information within the report. The detailed terms applicable to use of this report are set out at the end of this report.

## Dataset Listing

Datasets contained within this report, detailing their source and data currency:

Dataset Name	Custodian	Supply Date	Currency Date	Update Frequency	Dataset Buffer (m)	No. Features On-site	No. Features within 100m	No. Features within Buffer
Cadastre Boundaries	NSW Department of Customer Service - Spatial Services	14/02/2023	14/02/2023	Quarterly	-	-	-	-
Topographic Data	NSW Department of Customer Service - Spatial Services	22/08/2022	22/08/2022	Annually	-	-	-	-
List of NSW contaminated sites notified to EPA	Environment Protection Authority	24/03/2023	10/03/2023	Monthly	1000m	0	0	1
Contaminated Land Records of Notice	Environment Protection Authority	27/02/2023	27/02/2023	Monthly	1000m	0	0	1
Former Gasworks	Environment Protection Authority	06/12/2022	14/07/2021	Quarterly	1000m	0	0	0
National Waste Management Facilities Database	Geoscience Australia	26/05/2022	07/03/2017	Annually	1000m	0	0	0
National Liquid Fuel Facilities	Geoscience Australia	23/08/2022	13/07/2012	Annually	1000m	0	0	5
EPA PFAS Investigation Program	Environment Protection Authority	13/02/2023	23/09/2022	Monthly	2000m	0	0	0
Defence PFAS Investigation & Management Program - Investigation Sites	Department of Defence	14/02/2023	14/02/2023	Monthly	2000m	0	0	0
Defence PFAS Investigation & Management Program - Management Sites	Department of Defence	14/02/2023	14/02/2023	Monthly	2000m	0	0	0
Airservices Australia National PFAS Management Program	Airservices Australia	13/02/2023	13/02/2023	Monthly	2000m	0	0	0
Defence 3 Year Regional Contamination Investigation Program	Department of Defence	02/09/2022	02/09/2022	Quarterly	2000m	0	0	0
EPA Other Sites with Contamination Issues	Environment Protection Authority	16/02/2022	13/12/2018	Annually	1000m	0	0	0
Licensed Activities under the POEO Act 1997	Environment Protection Authority	27/02/2023	27/02/2023	Monthly	1000m	0	0	0
Delicensed POEO Activities still regulated by the EPA	Environment Protection Authority	27/02/2023	27/02/2023	Monthly	1000m	0	0	1
Former POEO Licensed Activities now revoked or surrendered	Environment Protection Authority	27/02/2023	27/02/2023	Monthly	1000m	0	0	3
UBD Business Directories (Premise & Intersection Matches)	Hardie Grant			Not required	150m	0	8	8
UBD Business Directories (Road & Area Matches)	Hardie Grant			Not required	150m	-	111	112
UBD Business Directory Dry Cleaners & Motor Garages/Service Stations (Premise & Intersection Matches)	Hardie Grant			Not required	500m	0	0	1
UBD Business Directory Dry Cleaners & Motor Garages/Service Stations (Road & Area Matches)	Hardie Grant			Not required	500m	-	4	10
Points of Interest	NSW Department of Customer Service - Spatial Services	19/10/2022	19/10/2022	Quarterly	1000m	1	7	50
Tanks (Areas)	NSW Department of Customer Service - Spatial Services	19/10/2022	19/10/2022	Quarterly	1000m	0	0	0
Tanks (Points)	NSW Department of Customer Service - Spatial Services	19/10/2022	19/10/2022	Quarterly	1000m	0	2	2
Major Easements	NSW Department of Customer Service - Spatial Services	16/02/2023	16/02/2023	Quarterly	1000m	0	0	4
State Forest	Forestry Corporation of NSW	16/08/2022	14/08/2022	Annually	1000m	0	0	0
NSW National Parks and Wildlife Service Reserves	NSW Office of Environment & Heritage	16/02/2023	31/12/2022	Annually	1000m	0	0	0
Hydrogeology Map of Australia	Commonwealth of Australia (Geoscience Australia)	29/08/2022	19/08/2019	As required	1000m	1	1	1
Temporary Water Restriction (Botany Sands Groundwater Source) Order 2018	NSW Department of Planning, Industry and Environment	28/03/2022	23/02/2018	Annually	1000m	0	0	0
National Groundwater Information System (NGIS) Boreholes	Bureau of Meteorology; Water NSW	14/02/2023	14/02/2023	Annually	2000m	0	0	1

Dataset Name	Custodian	Supply Date	Currency Date	Update Frequency	Dataset Buffer (m)	No. Features On-site	No. Features within 100m	No. Features within Buffer
NSW Seamless Geology Single Layer: Rock Units	Department of Regional NSW	17/02/2022	01/05/2021	Annually	1000m	1	2	2
NSW Seamless Geology – Single Layer: Trendlines	Department of Regional NSW	17/02/2022	01/05/2021	Annually	1000m	0	0	0
NSW Seamless Geology – Single Layer: Geological Boundaries and Faults	Department of Regional NSW	17/02/2022	01/05/2021	Annually	1000m	0	0	0
Naturally Occurring Asbestos Potential	NSW Dept. of Industry, Resources & Energy	04/12/2015	24/09/2015	Unknown	1000m	0	0	0
Atlas of Australian Soils	Australian Bureau of Agriculture and Resource Economics and Sciences (ABARES)	19/05/2017	17/02/2011	As required	1000m	1	1	1
Soil Landscapes of Central and Eastern NSW	NSW Department of Planning, Industry and Environment	18/08/2022	27/07/2020	Annually	1000m	2	2	3
Environmental Planning Instrument Acid Sulfate Soils	NSW Department of Planning, Industry and Environment	28/02/2023	02/12/2022	Monthly	500m	0	-	-
Atlas of Australian Acid Sulfate Soils	CSIRO	19/01/2017	21/02/2013	As required	1000m	1	1	1
Dryland Salinity - National Assessment	National Land and Water Resources Audit	18/07/2014	12/05/2013	None planned	1000m	0	0	0
Mining Subsidence Districts	NSW Department of Customer Service - Subsidence Advisory NSW	14/02/2023	14/02/2023	Quarterly	1000m	0	0	0
Current Mining Titles	NSW Department of Industry	13/02/2023	13/02/2023	Monthly	1000m	1	1	2
Mining Title Applications	NSW Department of Industry	13/02/2023	13/02/2023	Monthly	1000m	0	0	0
Historic Mining Titles	NSW Department of Industry	13/02/2023	13/02/2023	Monthly	1000m	9	9	10
Environmental Planning Instrument SEPP State Significant Precincts	NSW Department of Planning, Industry and Environment	15/11/2021	07/12/2018	Monthly	1000m	0	0	0
Environmental Planning Instrument Land Zoning	NSW Department of Planning, Industry and Environment	15/12/2022	02/12/2022	Monthly	1000m	1	4	21
Commonwealth Heritage List	Australian Government Department of the Agriculture, Water and the Environment	03/06/2022	13/04/2022	Annually	1000m	0	0	1
National Heritage List	Australian Government Department of the Agriculture, Water and the Environment	03/06/2022	13/04/2022	Annually	1000m	0	0	0
State Heritage Register - Curtilages	NSW Department of Planning, Industry and Environment	18/10/2022	01/07/2022	Quarterly	1000m	0	0	0
Environmental Planning Instrument Local Heritage	NSW Department of Planning, Industry and Environment	28/02/2023	17/02/2023	Monthly	1000m	1	1	64
Bush Fire Prone Land	NSW Rural Fire Service	27/03/2023	25/10/2022	Weekly	1000m	0	0	0
Ramsar Wetlands of Australia	Australian Government Department of Agriculture, Water and the Environment	28/03/2022	19/03/2020	Annually	1000m	0	0	0
Groundwater Dependent Ecosystems	Bureau of Meteorology	28/10/2022	26/10/2022	Annually	1000m	0	0	0
Inflow Dependent Ecosystems Likelihood	Bureau of Meteorology	28/10/2022	26/10/2022	Annually	1000m	0	0	0
NSW BioNet Species Sightings	NSW Office of Environment & Heritage	28/03/2023	28/03/2023	Weekly	10000m	-	-	-

# Site Diagram


Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



<b>Legend</b> Site Boundary Internal Parcel Boundaries	<b>Total Area:</b> 31967m <sup>2</sup> <b>Total Perimeter:</b> 973m	<b>Scale:</b> 
	Disclaimers: Measurements are approximate only and may have been simplified or smaller lengths removed for readability. Parcels that make up a small percentage of the total site area have not been labelled for increased legibility.	Data Sources: Aerial Imagery: © NSW Department of Finance, Services & Innovation
		Date: 28 March 2023

# Contaminated Land

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



## Contaminated Land

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

### List of NSW contaminated sites notified to EPA

Records from the NSW EPA Contaminated Land list within the dataset buffer:

Map Id	Site	Address	Suburb	Activity	Management Class	Status	Location Confidence	Dist	Direction
13615	Woolworths Caltex Temora	98-100 Hoskins Street	TEMORA	Service Station	Regulation under CLM Act not required	Current EPA List	Premise Match	879m	West

The values within the EPA site management class in the table above, are given more detailed explanations in the table below:

EPA site management class	Explanation
Contamination being managed via the planning process (EP&A Act)	The EPA has completed an assessment of the contamination and decided that the contamination is significant enough to warrant regulation. The contamination of this site is managed by the consent authority under the Environmental Planning and Assessment Act 1979 (EP&A Act) planning approval process, with EPA involvement as necessary to ensure significant contamination is adequately addressed. The consent authority is typically a local council or the Department of Planning and Environment.
Contamination currently regulated under CLM Act	The EPA has completed an assessment of the contamination and decided that the contamination is significant enough to warrant regulation under the Contaminated Land Management Act 1997 (CLM Act). Management of the contamination is regulated by the EPA under the CLM Act. Regulatory notices are available on the EPA's Contaminated Land Public Record of Notices.
Contamination currently regulated under POEO Act	The EPA has completed an assessment of the contamination and decided that the contamination is significant enough to warrant regulation. Management of the contamination is regulated under the Protection of the Environment Operations Act 1997 (POEO Act). The EPA's regulatory actions under the POEO Act are available on the POEO public register.
Contamination formerly regulated under the CLM Act	The EPA has determined that the contamination is no longer significant enough to warrant regulation under the Contaminated Land Management Act 1997 (CLM Act). The contamination was addressed under the CLM Act.
Contamination formerly regulated under the POEO Act	The EPA has determined that the contamination is no longer significant enough to warrant regulation. The contamination was addressed under the Protection of the Environment Operations Act 1997 (POEO Act).
Contamination was addressed via the planning process (EP&A Act)	The EPA has determined that the contamination is no longer significant enough to warrant regulation. The contamination was addressed by the appropriate consent authority via the planning process under the Environmental Planning and Assessment Act 1979 (EP&A Act).
Ongoing maintenance required to manage residual contamination (CLM Act)	The EPA has determined that ongoing maintenance, under the Contaminated Land Management Act 1997 (CLM Act), is required to manage the residual contamination. Regulatory notices under the CLM Act are available on the EPA's Contaminated Land Public Record of Notices.
Regulation being finalised	The EPA has completed an assessment of the contamination and decided that the contamination is significant enough to warrant regulation under the Contaminated Land Management Act 1997. A regulatory approach is being finalised.
Regulation under the CLM Act not required	The EPA has completed an assessment of the contamination and decided that regulation under the Contaminated Land Management Act 1997 is not required.
Under assessment	The contamination is being assessed by the EPA to determine whether regulation is required. The EPA may require further information to complete the assessment. For example, the completion of management actions regulated under the planning process or Protection of the Environment Operations Act 1997. Alternatively, the EPA may require information via a notice issued under s77 of the Contaminated Land Management Act 1997 or issue a Preliminary Investigation Order.

NSW EPA Contaminated Land List Data Source: Environment Protection Authority  
© State of New South Wales through the Environment Protection Authority

## Contaminated Land

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

### Contaminated Land: Records of Notice

Record of Notices within the dataset buffer:

Map Id	Name	Address	Suburb	Notices	Area No	Location Confidence	Distance	Direction
408	Woolworths Caltex Temora	98-100 Hoskins Street	Temora	2 former	3445	Premise Match	879m	West

Contaminated Land Records of Notice Data Source: Environment Protection Authority  
© State of New South Wales through the Environment Protection Authority  
Terms of use and disclaimer for Contaminated Land: Record of Notices, please visit  
<http://www.epa.nsw.gov.au/clm/clmdisclaimer.htm>

### Former Gasworks

Former Gasworks within the dataset buffer:

Map Id	Location	Council	Further Info	Location Confidence	Distance	Direction
N/A	No records in buffer					

Former Gasworks Data Source: Environment Protection Authority  
© State of New South Wales through the Environment Protection Authority



# Waste Management & Liquid Fuel Facilities

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



## Waste Management & Liquid Fuel Facilities

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

### National Waste Management Site Database

Sites on the National Waste Management Site Database within the dataset buffer:

Site Id	Owner	Name	Address	Suburb	Class	Landfill	Reprocess	Transfer	Comments	Loc Conf	Dist	Direction
N/A	No records in buffer											

Waste Management Facilities Data Source: Geoscience Australia

Creative Commons 3.0 © Commonwealth of Australia <http://creativecommons.org/licenses/by/3.0/au/deed.en>

### National Liquid Fuel Facilities

National Liquid Fuel Facilities within the dataset buffer:

Map Id	Owner	Name	Address	Suburb	Class	Operational Status	Operator	Revision Date	Loc Conf	Dist	Direction
4498	Caltex	Caltex Temora	111 Hoskins Street	Temora	Petrol Station	Operational		25/07/2011	Premise Match	787m	West
4386	BP	BP Temora	Lot 1 Victoria Street	Temora	Petrol Station	Operational		25/07/2011	Premise Match	812m	South West
3362	BP	Temora Fuel Distributors	9 Ironbark Street	Temora	Fuel Depot	Operational	Temora Fuel Distributors	04/10/2012	Premise Match	849m	South East
4387	BP	Temora Fuel Distributors	9 Ironbark Street	Temora	Petrol Station	Operational		25/07/2011	Premise Match	849m	South East
4499	Caltex	Woolworths Caltex Temora	98 Hoskins Street	Temora	Petrol Station	Operational		25/07/2011	Premise Match	879m	West

National Liquid Fuel Facilities Data Source: Geoscience Australia

Creative Commons 3.0 © Commonwealth of Australia <http://creativecommons.org/licenses/by/3.0/au/deed.en>

# PFAS Investigation & Management Programs

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

## EPA PFAS Investigation Program

Sites that are part of the EPA PFAS investigation program, within the dataset buffer:

Map ID	Site	Address	Loc Conf	Dist	Dir
N/A	No records in buffer				

EPA PFAS Investigation Program: Environment Protection Authority  
© State of New South Wales through the Environment Protection Authority

## Defence PFAS Investigation Program

Sites being investigated by the Department of Defence for PFAS contamination within the dataset buffer:

Map ID	Base Name	Address	Loc Conf	Dist	Dir
N/A	No records in buffer				

Defence PFAS Investigation Program Data Custodian: Department of Defence, Australian Government

## Defence PFAS Management Program

Sites being managed by the Department of Defence for PFAS contamination within the dataset buffer:

Map ID	Base Name	Address	Loc Conf	Dist	Dir
N/A	No records in buffer				

Defence PFAS Management Program Data Custodian: Department of Defence, Australian Government

## Airservices Australia National PFAS Management Program

Sites being investigated or managed by Airservices Australia for PFAS contamination within the dataset buffer:

Map ID	Site Name	Impacts	Loc Conf	Dist	Dir
N/A	No records in buffer				

Airservices Australia National PFAS Management Program Data Custodian: Airservices Australia

## Defence Sites

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

### Defence 3 Year Regional Contamination Investigation Program

Sites which have been assessed as part of the Defence 3 Year Regional Contamination Investigation Program within the dataset buffer:

Property ID	Base Name	Address	Known Contamination	Loc Conf	Dist	Dir
N/A	No records in buffer					

Defence 3 Year Regional Contamination Investigation Program, Data Custodian: Department of Defence, Australian Government

## EPA Other Sites with Contamination Issues

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

## EPA Other Sites with Contamination Issues

This dataset contains other sites identified on the EPA website as having contamination issues. This dataset currently includes:

- James Hardie asbestos manufacturing and waste disposal sites
- Radiological investigation sites in Hunter's Hill
- Pasmenco Lead Abatement Strategy Area

Sites within the dataset buffer:

Site Id	Site Name	Site Address	Dataset	Comments	Location Confidence	Distance	Direction
N/A	No records in buffer						

EPA Other Sites with Contamination Issues: Environment Protection Authority  
© State of New South Wales through the Environment Protection Authority

## EPA Activities

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

## Licensed Activities under the POEO Act 1997

Licensed activities under the Protection of the Environment Operations Act 1997, within the dataset buffer:


EPL	Organisation	Name	Address	Suburb	Activity	Loc Conf	Distance	Direction
N/A	No records in buffer							

POEO Licence Data Source: Environment Protection Authority

© State of New South Wales through the Environment Protection Authority

# Delicensed & Former Licensed EPA Activities

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



## EPA Activities

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

### Delicensed Activities still regulated by the EPA

Delicensed activities still regulated by the EPA, within the dataset buffer:

Licence No	Organisation	Name	Address	Suburb	Activity	Loc Conf	Distance	Direction
1053	HANSON CONSTRUCTION MATERIALS PTY LTD	HANSON CONSTRUCTION MATERIALS PTY LTD	3 INDUSTRIAL AVENUE	TEMORA	Concrete works	Premise Match	697m	South East

Delicensed Activities Data Source: Environment Protection Authority  
© State of New South Wales through the Environment Protection Authority

### Former Licensed Activities under the POEO Act 1997, now revoked or surrendered

Former Licensed activities under the Protection of the Environment Operations Act 1997, now revoked or surrendered, within the dataset buffer:

Licence No	Organisation	Location	Status	Issued Date	Activity	Loc Conf	Distance	Direction
4653	LUHRMANN ENVIRONMENT MANAGEMENT PTY LTD	WATERWAYS THROUGHOUT NSW	Surrendered	06/09/2000	Other Activities / Non Scheduled Activity - Application of Herbicides	Network of Features	807m	North East
4838	Robert Orchard	Various Waterways throughout New South Wales - SYDNEY NSW 2000	Surrendered	07/09/2000	Other Activities / Non Scheduled Activity - Application of Herbicides	Network of Features	807m	North East
6630	SYDNEY WEED & PEST MANAGEMENT PTY LTD	WATERWAYS THROUGHOUT NSW - PROSPECT, NSW, 2148	Surrendered	09/11/2000	Other Activities / Non Scheduled Activity - Application of Herbicides	Network of Features	807m	North East

Former Licensed Activities Data Source: Environment Protection Authority  
© State of New South Wales through the Environment Protection Authority



# Historical Business Directories

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



<b>Legend</b> <ul style="list-style-type: none"> <li><span style="color: magenta;">▭</span> Site Boundary</li> <li><span style="color: blue;">●</span> Business directory records mapped to a specific premise</li> <li><span style="border: 2px solid black; border-radius: 50%; padding: 2px;"> </span> Buffer 150m</li> <li><span style="color: green;">■</span> Business directory records mapped to a road intersection</li> <li><span style="border: 1px solid grey; padding: 2px;"> </span> Property Boundary</li> <li><span style="color: orange;">▲</span> Business directory records mapped to a road corridor</li> <li><span style="background-color: #d3d3d3; border: 1px solid black; padding: 2px;"> </span> Business directory records mapped to a general area</li> </ul>		Scale: 	Coordinate System: GDA 1994 MGA Zone 56  Date: 28 March 2023
Data Sources: Reproduced with permission of UBD and Hardie Grant Media Pty Ltd DD 01/08/2018 Property Boundaries © NSW Department Finance, Services & Innovation 2023			

## Historical Business Directories

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

### Business Directory Records 1950-1991 Premise or Road Intersection Matches

Universal Business Directory records from years 1991, 1982, 1970, 1961 & 1950, mapped to a premise or road intersection within the dataset buffer:

Map Id	Business Activity	Premise	Ref No.	Year	Location Confidence	Distance to Property Boundary or Road Intersection	Direction
1	MEDICAL PRACTITIONERS.	Mead M, 172 Loftus St., Temora. 2666	213120	1991	Premise Match	31m	South
	MEDICAL PRACTITIONERS	Mead, M., 172 Loftus St., Temora 2666	162591	1982	Premise Match	31m	South
2	ASSOCIATIONS &/OR SOCIETIES	Temora High School P. & C. Association., Anzac St., Temora 2666	220946	1991	Premise Match	87m	West
	SCHOOLS &/OR COLLEGES - PRIVATE &/OR PUBLIC	Temora High School., Anzac St., Temora. 2666	213271	1991	Premise Match	87m	West
	ASSOCIATIONS, SOCIETIES, CLUBS &/OR SPORTING BODIES	Temora High School P. & C. Association, Anzac St., Temora 2666	162360	1982	Premise Match	87m	West
	SCHOOLS &/OR COLLEGES - PRIVATE &/OR PUBLIC	Temora High School, Anzac St., Temora 2666	162732	1982	Premise Match	87m	West
	SCHOOLS & COLLEGES-PRIVATE & PUBLIC	High School, Anzac St. Temora 2666	588646	1970	Premise Match	87m	West
	ASSOCIATIONS, SOCIETIES, CLUBS & SPORTING BODIES	Temora High School Parents & Citizens Association Anzac St. Temora 2666	588118	1970	Premise Match	87m	West

Reproduced with permission of UBD and Hardie Grant Media Pty Ltd DD 01/08/2018

## Business Directory Records 1950-1991 Road or Area Matches

Universal Business Directory records from years 1991, 1982, 1970, 1961 & 1950, mapped to a road or an area, within the dataset buffer. Records are mapped to the road when a building number is not supplied, cannot be found, or the road has been renumbered since the directory was published:

Map Id	Business Activity	Premise	Ref No.	Year	Location Confidence	Distance to Road Corridor or Area
3	ASSOCIATIONS &/OR SOCIETIES	Temora Amateur Swimming Club., Loftus St., Temora 2666	220930	1991	Road Match	0m
	ASSOCIATIONS &/OR SOCIETIES	Temora Bowling & Recreation Club., Loftus St., Temora 2666	220932	1991	Road Match	0m
	ASSOCIATIONS &/OR SOCIETIES	Temora Dist Hospital Board., Loftus St., Temora 2666	220938	1991	Road Match	0m
	HOSPITALS &/OR NURSING HOMES.	Temora District Hospital., Loftus St., Temora. 2666	213064	1991	Road Match	0m
	KINDERGARTENS &/OR CHILD MINDING CENTRES.	Temora Pre-School Kindergarten., Loftus St., Temora. 2666	213096	1991	Road Match	0m
	LOCAL BODIES	Temora Shire Council., Loftus St., Temora. 2666	213114	1991	Road Match	0m
	AIR CONDITIONING SALES &/OR SERVICE	Gilchrist's Service Centre, 86 Loftus St., Temora 2666	162305	1982	Road Match	0m
	ELECTRICAL REPAIR SERVICES	Gilchrist's Service Centre, 86 Loftus St., Temora 2666	162475	1982	Road Match	0m
	RADIO &/OR TELEVISION SALES &/OR SERVICE &/OR HIRERS	Gilchrist's Service Centre, 86 Loftus St., Temora 2666	162705	1982	Road Match	0m
	HOTELS - LICENSED	Grand Hotel, Loftus St., Temora 2666	162542	1982	Road Match	0m
	SADDLERS	Hors'n Around Saddlery, 96 Loftus St., Temora 2666	162728	1982	Road Match	0m
	BATHS - SWIMMING	Municipal Swimming Pool. Loftus St., Temora 2666	162394	1982	Road Match	0m
	NATUROPATHS	Naturopath. 94 Loftus St., Temora 2666	162670	1982	Road Match	0m
	ASSOCIATIONS, SOCIETIES, CLUBS &/OR SPORTING BODIES	Temora Amateur Swimming Club, Loftus St., Temora 2666	162346	1982	Road Match	0m
	CRANES - MOBILE & TRAVEL TOWER - PROPRIETORS &/OR HIRERS	Temora Auto Wreckers, 72 Loftus St., Temora 2666	162458	1982	Road Match	0m
	MOTOR ACCESSORIES &/OR SPARE PARTS -RETAIL	Temora Auto Wreckers, 72 Loftus St., Temora 2666	162618	1982	Road Match	0m
	MOTOR TOWING SERVICES.	Temora Auto Wreckers, 72 Loftus St., Temora 2666	162664	1982	Road Match	0m
	MOTOR WRECKERS	Temora Auto Wreckers, 72 Loftus St., Temora 2666	162668	1982	Road Match	0m
	SCRAP METAL MERCHANTS	Temora Auto Wreckers, 72 Loftus St., Temora 2666	162737	1982	Road Match	0m
	SECONDHAND DEALERS	Temora Auto Wreckers, 72 Loftus St., Temora 2666	162741	1982	Road Match	0m
	ASSOCIATIONS, SOCIETIES, CLUBS &/OR SPORTING BODIES	Temora Bowling & Recreation Club. Loftus St., Temora 2666	162348	1982	Road Match	0m
	ASSOCIATIONS, SOCIETIES, CLUBS &/OR SPORTING BODIES	Temora Dist Hospital Board, Loftus St., Temora 2666	162354	1982	Road Match	0m
	HOSPITALS &/OR HEALTH CENTRES	Temora District Hospital, Loftus St., Temora 2666	162541	1982	Road Match	0m
	SCHOOLS - KINDERGARTEN, DAY NURSERY	Temora Pre-School Kindergarten. Loftus St., Temora 2666	162736	1982	Road Match	0m
	ASSOCIATIONS, SOCIETIES, CLUBS &/OR SPORTING BODIES	Women's Friendship Club. Loftus St., Temora 2666	162376	1982	Road Match	0m
	BEAUTY SALONS & LADIES' HAIRDRESSERS	Aromet Salon, 96 Loftus St. Temora 2666	588162	1970	Road Match	0m

Map Id	Business Activity	Premise	Ref No.	Year	Location Confidence	Distance to Road Corridor or Area
3	AUCTIONEERS-GENERAL	Australian Estates Co. Agencies Pty. Ltd., 94 Loftus St. Temora 2666	588132	1970	Road Match	0m
	INSURANCE AGENTS	Australian Estates Co. Agencies Pty. Ltd., 94 Loftus St. Temora 2666	588380	1970	Road Match	0m
	STATION & FARM SUPPLIES	Australian Estates Co. Agencies Pty. Ltd., 94 Loftus St. Temora 2666	588680	1970	Road Match	0m
	STOCK, STATION & REAL ESTATE AGENTS	Australian Estates Co. Agencies Pty. Ltd., 94 Loftus St. Temora 2666	588699	1970	Road Match	0m
	WOOL BROKERS	Australian Estates Co. Agencies Pty. Ltd., 94 Loftus St. Temora 2666	588787	1970	Road Match	0m
	AUCTIONEERS-GENERAL	Davoren, W. J., 88 Loftus St. Temora 2666	588135	1970	Road Match	0m
	INSURANCE AGENTS	Davoren, W. J., 88 Loftus St. Temora 2666	588385	1970	Road Match	0m
	STOCK, STATION & REAL ESTATE AGENTS	Davoren, W. J., 88 Loftus St. Temora 2666	588702	1970	Road Match	0m
	WOOL, SKIN & HIDE BUYERS	Deep, A. A. & Co., 76 Loftus St. Temora 2666	588793	1970	Road Match	0m
	HOTELS-LICENSED	Grand Hotel, Loftus St. Temora 2666	588371	1970	Road Match	0m
	WOOL, SKIN & HIDE BUYERS	Green, T. W. & Co. Pty. Ltd., 66 Loftus St. Temora 2666	588794	1970	Road Match	0m
	BATHS-SWIMMING	Municipal Swimming Pool, Loftus St. Temora 2666	588157	1970	Road Match	0m
	TAXI &/OR HIRE CAR SERVICES	Taxi Rank, Loftus St. Temora 2666	588716	1970	Road Match	0m
	ASSOCIATIONS, SOCIETIES, CLUBS & SPORTING BODIES	Temora Amateur Swimming Club, Loftus St. Temora 2666	588104	1970	Road Match	0m
	CRANES-MOBILE-PROP. OR HIRERS	Temora Auto Wreckers, 72 Loftus St. Temora 2666	588250	1970	Road Match	0m
	MOTOR ACCESSORIES & SPARE PARTS DEALERS	Temora Auto Wreckers, 72 Loftus St. Temora 2666	588489	1970	Road Match	0m
	MOTOR TOWING SERVICES	Temora Auto Wreckers, 72 Loftus St. Temora 2666	588554	1970	Road Match	0m
	MOTOR WRECKERS	Temora Auto Wreckers, 72 Loftus St. Temora 2666	588558	1970	Road Match	0m
	SECOND-HAND DEALERS	Temora Auto Wreckers, 72 Loftus St. Temora 2666	588657	1970	Road Match	0m
	ASSOCIATIONS, SOCIETIES, CLUBS & SPORTING BODIES	Temora Bowling & Recreation Club, Loftus St. Temora 2666	588105	1970	Road Match	0m
	ASSOCIATIONS, SOCIETIES, CLUBS & SPORTING BODIES	Temora District Hospital Board, Loftus St. Temora 2666	588112	1970	Road Match	0m
	HOSPITALS & HEALTH CENTRES	Temora District Hospital, Loftus St. Temora 2666	588369	1970	Road Match	0m
	LOCAL BODIES	Temora Municipal Council, Loftus St. Temora 2666	588442	1970	Road Match	0m
	BOOT & SHOE REPAIRERS	White, K., 92 Loftus St. Temora 2666	588167	1970	Road Match	0m
	DRY CLEANERS, PRESSERS & DYERS	C.K. Dry Cleaners and Pressers, 92 Loftus St., Temora	225730	1961	Road Match	0m
	ENGINEERS-STRUCTURAL	Cleverdon Bros., 72 Loftus St., Temora	225752	1961	Road Match	0m
	HARDWARE DEALERS & IRONMONGERS	Clevedon's Loftus Street, Temora	225838	1961	Road Match	0m
	AGRICULTURAL MACHINERY DEALERS	Cleverdon Bros., 72 Loftus St., Temora	225556	1961	Road Match	0m
	AGRICULTURAL MACHINERY REPAIRERS	Cleverdon Bros., 72 Loftus St., Temora	225576	1961	Road Match	0m
	ENGINEERS-CONSTRUCTIONAL	Cleverdon Bros., 72 Loftus St., Temora	225744	1961	Road Match	0m
	INSURANCE AGENTS	Cleverdon Bros., 72 Loftus St., Temora	225861	1961	Road Match	0m
	WELDERS-ELECTRIC & OXY	Cleverdon Bros., 72 Loftus St., Temora	226166	1961	Road Match	0m
	AUCTIONEERS-GENERAL	Davoren, W. J., 88 Loftus St., Temora	225606	1961	Road Match	0m
	INSURANCE AGENTS	Davoren, W. J., 88 Loftus St., Temora	225863	1961	Road Match	0m
	STOCK, STATION & REAL ESTATE AGENTS	Davoren, W. J., 88 Loftus St., Temora	226124	1961	Road Match	0m


Map Id	Business Activity	Premise	Ref No.	Year	Location Confidence	Distance to Road Corridor or Area
3	WOOL, SKIN & HIDE BUYERS	Deeps, A. A. and Co., Loftus St, Temora	226185	1961	Road Match	0m
	BEAUTY SALONS & LADIES' HAIRDRESSERS	Edwards, G., Loftus St., Temora	225630	1961	Road Match	0m
	HOTELS-LICENSED	Grand Hotel, Loftus St., Temora	225848	1961	Road Match	0m
	WOOL, SKIN & HIDE BUYERS	Green, T. W. Pty. Ltd., 66 Loftus St., Temora	226186	1961	Road Match	0m
	MOTOR TRIMMERS	Rodgers, Jack, Off Loftus St., Temora	226026	1961	Road Match	0m
	UPHOLSTERERS	Rodgers, Jack, Off Loftus St., Temora	226159	1961	Road Match	0m
	LOCAL BODIES	Temora Municipal Council, Loftus St., Temora	225911	1961	Road Match	0m
	HOTELS-LICENSED	Terminus Hotel, Loftus St., Temora	225855	1961	Road Match	0m
	MOTOR WRECKER	Tom Walsh Loftus Street, Temora	226020	1961	Road Match	0m
	MOTOR ACCESSORIES & SPARE PARTS DEALERS	Walsh, T., Loftus St., Temora	225964	1961	Road Match	0m
	MOTOR WRECKERS	Walsh, T., Loftus St., Temora	226028	1961	Road Match	0m
	SECOND-HAND DEALERS	Walsh, T., Loftus St., Temora	226094	1961	Road Match	0m
	BEAUTY SALONS & LADIES HAIRDRESSERS	Allen, Mrs., Loftus St., Temora	165108	1950	Road Match	0m
	DRY CLEANERS, PRESSERS & DYERS	C.K. Dry Cleaners, Loftus St., Temora	165179	1950	Road Match	0m
	WELDERS-ELECTRIC & OXY	Cieverdon and Douglas, Loftus St Temora	165416	1950	Road Match	0m
	MOTOR CAR & TRUCK DEALERS	Cieverdon and Douglas, Loftus St., Temora	165296	1950	Road Match	0m
	MOTOR GARAGES & ENGINEERS	Cieverdon and Douglas, Loftus St., Temora	165309	1950	Road Match	0m
	MOTOR PAINTERS &/OR PANEL BEATERS	Cieverdon and Douglas, Loftus St., Temora	165322	1950	Road Match	0m
	MOTORCYCLE DEALERS & SERVICEMEN	Cieverdon and Douglas, Loftus St., Temora	165304	1950	Road Match	0m
	INSURANCE AGENTS	Cieverdon and Douglas, Loftus St., Temora	165246	1950	Road Match	0m
	MOTOR ACCESSORIES DEALERS	Cieverdon and Douglas, Loftus St., Temora	165292	1950	Road Match	0m
	INSURANCE AGENTS	Davoren, W. J. (Agent, M.L.C.), Loftus St., Temora	165247	1950	Road Match	0m
	REAL ESTATE AGENTS	Davoren, W. J., Loftus St., Temora	165365	1950	Road Match	0m
	STOCK & STATION AGENTS	Davoren, W. J., Loftus St., Temora	165389	1950	Road Match	0m
	AUCTIONEERS-,GENERAL	Davuren, W. J., Loftus St., Temora	165086	1950	Road Match	0m
	SKIN & HIDE MERCHANTS	Deeps, A. A., Loftus St., Temora	165378	1950	Road Match	0m
	WOOL MERCHANTS	Deeps, A. A., Loftus St., Temora	165421	1950	Road Match	0m
	SHEARING CONTRACTORS	Goode, J. J., Loftus St., Temora	165377	1950	Road Match	0m
	HOTELS-LICENSED	Grand Hotel, Loftus St., Temora	165236	1950	Road Match	0m
	SKIN & HIDE MERCHANTS	Green, T. W. Pty. Ltd., Loftus St., Temora	165379	1950	Road Match	0m
	WOOL MERCHANTS	Green, T. W. Pty. Ltd., Loftus St., Temora	165422	1950	Road Match	0m
	MILLINERY-RETAIL	Kelly, Nom Loftus St., Temora	165289	1950	Road Match	0m
	FLORISTS-RETAIL	Kelly, Nora, Loftus St., Temora	165190	1950	Road Match	0m
	CARRIERS & CARTAGE CONTRACTORS	M.W.S. Transport Service, Loftus St., Temora	165143	1950	Road Match	0m
	PRODUCE MERCHANTS-WHOLESALE	M.W.S. Transport Service, Loftus St., Temora	165357	1950	Road Match	0m

Map Id	Business Activity	Premise	Ref No.	Year	Location Confidence	Distance to Road Corridor or Area
3	ENGINEERS-GENERAL &/OR MANUFACTURING	Masiin, R. J. Loftus St., Temora	165186	1950	Road Match	0m
	MOTOR CARBURETTOR SPECIALISTS	Maslin, R. G. Loftus St., Temora	165303	1950	Road Match	0m
	DRY CLEANERS, PRESSERS & DYERS	O.K. Dry Cleaners, Loftus St, Temora	165180	1950	Road Match	0m
	AGRICULTURAL MACHINERY DEALERS	Temora Wheatgrowers Union Co-op, Society Ltd., Loftus St., Temora	165081	1950	Road Match	0m
	AUCTIONEERS-,GENERAL	Temora Wheatgrowers Union Co-op. Society Ltd., Loftus St., Temora	165090	1950	Road Match	0m
	REAL ESTATE AGENTS	Temora Wheatgrowers Union Co-op. Society Ltd., Loftus St., Temora	165369	1950	Road Match	0m
	STOCK & STATION AGENTS	Temora Wheatgrowers Union Co-op. Society Ltd., Loftus St., Temora	165393	1950	Road Match	0m
	HOTELS-LICENSED	Terminus Hotel (S. P. Wurth, Propr.), Loftus St., Temora	165241	1950	Road Match	0m
4	ASSOCIATIONS &/OR SOCIETIES	Temora Tech. College Advisory Committee., Gloucester St., Temora 2666	220956	1991	Road Match	0m
	SCHOOLS &/OR COLLEGES - PRIVATE &/OR PUBLIC	Temora Technical College., Gloucester St., Temora. 2666	213273	1991	Road Match	0m
	ASSOCIATIONS, SOCIETIES, CLUBS &/OR SPORTING BODIES	Temora Tech. College Advisory Committee. Gloucester St., Temora 2666	162369	1982	Road Match	0m
	SCHOOLS &/OR COLLEGES - PRIVATE &/OR PUBLIC	Temora Technical College. Gloucester St., Temora 2666	162734	1982	Road Match	0m
	ASSOCIATIONS, SOCIETIES, CLUBS & SPORTING BODIES	Temora Tech. College Advisory Committee, Gloucester St. Temora 2666	588126	1970	Road Match	0m
	SCHOOLS & COLLEGES-TECHNICAL	Temora Technical College, Gloucester St. Temora 2666	588651	1970	Road Match	0m
5	MILK VENDORS	Salzke, C. E. Gallipoli St., Temora	165288	1950	Road Match	84m
6	QUARRY PROPRIETORS	Will Bros., George St., Temora	226083	1961	Road Match	108m

Reproduced with permission of UBD and Hardie Grant Media Pty Ltd DD 01/08/2018

# Dry Cleaners, Motor Garages & Service Stations

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



Legend	
	Site Boundary
	Buffer 500m
	Property Boundary
	Business directory records mapped to a specific premise
	Business directory records mapped to a road intersection
	Business directory records mapped to a road corridor
	Business directory records mapped to a general area

Scale: 0 100 200 300 400 Meters	Coordinate System: GDA 1994 MGA Zone 56
	Date: 28 March 2023
Data Sources: Reproduced with permission of UBD and Hardie Grant Media Pty Ltd DD 01/08/2018 Property Boundaries © NSW Department Finance, Services & Innovation 2023	

## Historical Business Directories

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

### Dry Cleaners, Motor Garages & Service Stations Premise or Road Intersection Matches

Dry Cleaners, Motor Garages & Service Stations from UBD Business Directories, mapped to a premise or road intersection, within the dataset buffer.

Map Id	Business Activity	Premise	Ref No.	Year	Location Confidence	Distance to Property Boundary or Road Intersection	Direction
1	MOTOR SERVICE STATIONS-PETROL, OIL, Etc.	Franke, F. H. & V., 181 Victoria St. Temora 2666	588550	1970	Premise Match	411m	South East

Reproduced with permission of UBD and Hardie Grant Media Pty Ltd DD 01/08/2018



## Dry Cleaners, Motor Garages & Service Stations Road or Area Matches

Dry Cleaners, Motor Garages & Service Stations from UBD Business Directories, mapped to a road or an area, within the dataset buffer. Records are mapped to the road when a building number is not supplied, cannot be found, or the road has been renumbered since the directory was published.

Map Id	Business Activity	Premise	Ref No.	Year	Location Confidence	Distance to Road Corridor or Area
2	DRY CLEANERS, PRESSERS & DYERS	C.K. Dry Cleaners and Pressers, 92 Loftus St., Temora	225730	1961	Road Match	0m
	DRY CLEANERS, PRESSERS & DYERS	C.K. Dry Cleaners, Loftus St., Temora	165179	1950	Road Match	0m
	MOTOR GARAGES & ENGINEERS	Cieverdon and Douglas, Loftus St., Temora	165309	1950	Road Match	0m
	DRY CLEANERS, PRESSERS & DYERS	O.K. Dry Cleaners, Loftus St, Temora	165180	1950	Road Match	0m
3	MOTOR GARAGES & SERVICE STATIONS.	BP Temora Service Station., Victoria St., Temora. 2666	213170	1991	Road Match	354m
	MOTOR GARAGES & SERVICE STATIONS.	BP Temora Service Station., Victoria Street, Temora. 2666	213168	1991	Road Match	354m
	MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS	Temora Filling Station, Victoria St., Temora 2666	162653	1982	Road Match	354m
	MOTOR SERVICE STATIONS-PETROL, OIL, Etc.	Temora Filling Station, Victoria St. Temora 2666	588551	1970	Road Match	354m
	MOTOR GARAGES & ENGINEERS	Meagher, John & Co. Pty. Ltd. Victoria St., Temora	165306	1950	Road Match	354m
	MOTOR GARAGES & ENGINEERS	Meagher, John and Co. Pty. Ltd., Victoria St., Temora	165314	1950	Road Match	354m

Reproduced with permission of UBD and Hardie Grant Media Pty Ltd DD 01/08/2018

# Aerial Imagery 2022

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666




# Aerial Imagery 2017

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



### Legend

- Site Boundary
- Buffer 150m



Data Source Aerial Imagery: © 2023 Google Inc, used with permission. Google and the Google logo are registered trademarks of Google Inc.

Coordinate System: GDA 1994 MGA Zone 56


Date: 27 March 2023

# Aerial Imagery 2011

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



Scale:




Data Source Aerial Imagery: © 2023 Google Inc, used with permission. Google and the Google logo are registered trademarks of Google Inc.

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 27 March 2023

# Aerial Imagery 2005

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666




Data Source Aerial Imagery: © 2023 Google Inc, used with permission. Google and the Google logo are registered trademarks of Google Inc.

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 27 March 2023

# Aerial Imagery 1997

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666




Data Source Aerial Imagery:  
© NSW Department of Customer Service

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 04 April 2023

# Aerial Imagery 1986

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



Data Source Aerial Imagery:  
© NSW Department of Customer Service

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 29 March 2023

# Aerial Imagery 1978


Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666





# Aerial Imagery 1961

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666




Data Source Aerial Imagery:  
© NSW Department of Customer Service

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 29 March 2023

# Aerial Imagery 1945

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666




Data Source Aerial Imagery:  
© NSW Department of Customer Service

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 27 March 2023


# Topographic Map 2015

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



# Historical Map 2000

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



# Topographic Features

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



# Topographic Features

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

## Points of Interest

What Points of Interest exist within the dataset buffer?

Map Id	Feature Type	Label	Distance	Direction
287229	Integrated Health Service	TEMORA HOSPITAL	0m	On-site
415876	Retirement Village	THE WHIDDON GROUP TEMORA	36m	West
402561	Picnic Area	BBQ	45m	South West
287246	Nursing Home	THE WHIDDON GROUP TEMORA GREENSTONE	50m	South West
287236	Park	GLOUCESTER PARK	83m	West
402560	Child Care Centre	TEMORA PRESCHOOL	98m	South West
414859	Community Home	THE WHIDDON GROUP-TEMORA	100m	North East
287228	TAFE College	TEMORA TAFE COLLEGE	184m	North
399402	High School	TEMORA HIGH SCHOOL	184m	West
294577	Place Of Worship	LUTHERAN CHURCH	281m	South West
393700	Sports Field	BOWLING GREENS	394m	West
414184	Club	TEMORA BOWLING AND REC CLUB	412m	South West
419397	Park	LIONS PARK	455m	South West
287235	Swimming Pool	Swimming Pool	458m	West
414301	Retirement Village	SOUTHERN CROSS VILLAGE TEMORA	466m	South West
287237	Park	HILLVIEW PARK	500m	North West
287263	Sports Field	FATHER HERMAN OVAL	506m	South West
419399	Monument	WAR MEMORIAL	520m	South West
294578	Sports Centre	TEMORA RECREATION CENTRE	521m	West
419393	Sports Court	CRICKET NETS	539m	South East
287227	Park	CALLAGHAN PARK	547m	South West
419401	Park	PLAYGROUND	555m	West
419400	Picnic Area	BBQ	560m	West
294579	Place Of Worship	SEVENTH DAY ADVENTIST CHURCH	611m	West
421211	Retirement Village	DR PARRY MEMORIAL HOMES	615m	North West
398839	Primary School	TEMORA PUBLIC SCHOOL	618m	West
371182	Sports Field	OVAL	636m	South East
399710	Combined Primary-Secondary School	ST ANNES CENTRAL SCHOOL	658m	South West
354245	Community Facility	TEMORA MEMORIAL TOWN HALL	664m	South West
287264	Place Of Worship	CATHOLIC CHURCH	670m	South West
287226	Park	NIXON PARK	671m	South East

Map Id	Feature Type	Label	Distance	Direction
287218	Fire Station	TEMORA FIRE STATION	703m	South West
349503	Place Of Worship	UNITING CHURCH	709m	West
287247	Police Station	TEMORA POLICE STATION	726m	South West
349506	Place Of Worship	ST ANDREWS PRESBYTERIAN CHURCH	731m	South West
287231	Local Government Chambers	TEMORA SHIRE COUNCIL	733m	South West
287216	Place Of Worship	ST PAULS ANGLICAN CHURCH	735m	South West
287248	Court House	TEMORA COURT HOUSE	745m	South West
287224	Sports Field	THE OVAL	768m	South
371183	Sports Field	OVAL	769m	South East
419392	Sports Court	NETBALL	771m	South East
287238	Park	PINNEY PARK	779m	South
392501	Park	PALEFACE PARK	789m	South West
287217	Post Office	TEMORA POST OFFICE	812m	South West
287230	Ambulance Station	TEMORA AMBULANCE STATION	813m	West
348747	Town	TEMORA	834m	South West
402611	Sports Court	NETBALL COURTS	837m	South
349510	Park	GOLDEN GATE RESERVE	892m	South
349501	Park	BRADLEY PARK	931m	North West
287222	Dog Track	TEMORA GREYHOUND TRACK	979m	South

Topographic Data Source: © Land and Property Information (2015)

Creative Commons 3.0 © Commonwealth of Australia <http://creativecommons.org/licenses/by/3.0/au/deed.en>

# Topographic Features

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

## Tanks (Areas)

What are the Tank Areas located within the dataset buffer?

Note. The large majority of tank features provided by LPI are derived from aerial imagery & are therefore primarily above ground tanks.

Map Id	Tank Type	Status	Name	Feature Currency	Distance	Direction
N/A	No records in buffer					

## Tanks (Points)

What are the Tank Points located within the dataset buffer?

Note. The large majority of tank features provided by LPI are derived from aerial imagery & are therefore primarily above ground tanks.

Map Id	Tank Type	Status	Name	Feature Currency	Distance	Direction
181242	Water	Operational		01/01/2017	24m	East
181240	Water	Operational		01/01/2017	25m	East

Tanks Data Source: © Land and Property Information (2015)

Creative Commons 3.0 © Commonwealth of Australia <http://creativecommons.org/licenses/by/3.0/au/deed.en>

## Major Easements

What Major Easements exist within the dataset buffer?

Note. Easements provided by LPI are not at the detail of local governments. They are limited to major easements such as Right of Carriageway, Electrical Lines (66kVa etc.), Easement to drain water & Significant subterranean pipelines (gas, water etc.).

Map Id	Easement Class	Easement Type	Easement Width	Distance	Direction
120111009	Primary	Undefined		316m	North
120114897	Primary	Undefined		323m	North East
120109396	Primary	Undefined		631m	North West
120111005	Primary	Undefined		920m	North

Easements Data Source: © Land and Property Information (2015)

Creative Commons 3.0 © Commonwealth of Australia <http://creativecommons.org/licenses/by/3.0/au/deed.en>



# Topographic Features

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

## State Forest

What State Forest exist within the dataset buffer?

State Forest Number	State Forest Name	Distance	Direction
N/A	No records in buffer		

State Forest Data Source: © NSW Department of Finance, Services & Innovation (2018)  
Creative Commons 3.0 © Commonwealth of Australia <http://creativecommons.org/licenses/by/3.0/au/deed.en>

## National Parks and Wildlife Service Reserves


What NPWS Reserves exist within the dataset buffer?

Reserve Number	Reserve Type	Reserve Name	Gazetted Date	Distance	Direction
N/A	No records in buffer				

NPWS Data Source: © NSW Department of Finance, Services & Innovation (2018)  
Creative Commons 3.0 © Commonwealth of Australia <http://creativecommons.org/licenses/by/3.0/au/deed.en>

# Elevation Contours (m AHD)

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



## Hydrogeology & Groundwater

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

### Hydrogeology

Description of aquifers within the dataset buffer:

Description	Distance	Direction
Fractured or fissured, extensive aquifers of low to moderate productivity	0m	On-site

Hydrogeology Map of Australia : Commonwealth of Australia (Geoscience Australia)  
Creative Commons 3.0 © Commonwealth of Australia <http://creativecommons.org/licenses/by/3.0/au/deed.en>

### Temporary Water Restriction (Botany Sands Groundwater Source) Order 2018


Temporary water restrictions relating to the Botany Sands aquifer within the dataset buffer:

Prohibition Area No.	Prohibition	Distance	Direction
N/A	No records in buffer		

Temporary Water Restriction (Botany Sands Groundwater Source) Order 2018 Data Source : NSW Department of Primary Industries

# Groundwater Boreholes

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



# Hydrogeology & Groundwater

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

## Groundwater Boreholes

Boreholes within the dataset buffer:

NGIS Bore ID	NSW Bore ID	Bore Type	Status	Drill Date	Bore Depth (m)	Reference Elevation	Height Datum	Salinity (mg/L)	Yield (L/s)	SWL (mbgl)	Distance	Direction
10026695	GW015089		Unknown	01/02/1957	54.90		AHD				335m	West

Borehole Data Source: Bureau of Meteorology; Water NSW. Creative Commons 3.0 © Commonwealth of Australia <http://creativecommons.org/licenses/by/3.0/au/deed.en>

# Hydrogeology & Groundwater


Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

## Driller's Logs

Drill log data relevant to the boreholes within the dataset buffer:

NGIS Bore ID	Drillers Log	Distance	Direction
10026695	0.00m-12.19m Clay Red Sticky 12.19m-15.24m Clay Red 15.24m-22.86m Clay Red Hard 22.86m-29.87m Clay Silty 29.87m-32.00m Sandstone Decomposed 32.00m-37.19m Clay Red Sticky 37.19m-41.15m Clay Yellow 41.15m-46.94m Shale Dark Broken Water Supply 46.94m-51.82m Slate Dark Soft 51.82m-54.86m Slate Yellow Hard Some Sand 51.82m-54.86m Veins	335m	West

Drill Log Data Source: Bureau of Meteorology; Water NSW. Creative Commons 3.0 © Commonwealth of Australia <http://creativecommons.org/licenses/by/3.0/au/deed.en>



# Geology

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

## Geological Units

What are the Geological Units within the dataset buffer?

Unit Code	Unit Name	Description	Unit Stratigraphy	Age	Dominant Lithology	Distance
Suet	Temora Volcanics	Andesite, trachyandesite, latite, basaltic trachyandesite, basalt, trachybasalt; vesicular amygdaloidal pillow lava with hyaloclastite, breccia and interpillow material; lapilli tuff; volcanoclastic siltstone, sandstone, polymictic pebble conglomerate.	/Ungrouped Eastern Lachlan Silurian units//Temora Volcanics//	Silurian (base) to Silurian (top)	Andesite	0m
Q_c	Colluvium	Poorly sorted, weakly cemented to unconsolidated colluvial lenses of polymictic conglomerate with medium- to very coarse-grained sand matrix; interspersed with unconsolidated clayey and silty red-brown (aeolian) sand layers, modified by pedogenesis.	/Colluvium////	Quaternary (base) to Now (top)	Clastic sediment	39m

## Linear Geological Structures

What are the Dyke, Sill, Fracture, Lineament and Vein trendlines within the dataset buffer?

Map ID	Feature Description	Map Sheet Name	Distance
No Features			

What are the Faults, Shear zones or Schist zones, Intrusive boundaries & Marker beds within the dataset buffer?

Map ID	Boundary Type	Description	Map Sheet Name	Distance
No Features				

Geological Data Source: Statewide Seamless Geology v2.1, Department of Regional NSW  
 Creative Commons 4.0 © Commonwealth of Australia <http://creativecommons.org/licenses/by/4.0/au/deed.en>



# Naturally Occurring Asbestos Potential

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

## Naturally Occurring Asbestos Potential


Naturally Occurring Asbestos Potential within the dataset buffer:

Potential	Sym	Strat Name	Group	Formation	Scale	Min Age	Max Age	Rock Type	Dom Lith	Description	Dist	Dir
No records in buffer												


Naturally Occurring Asbestos Potential Data Source: © State of New South Wales through NSW Department of Industry, Resources & Energy

# Atlas of Australian Soils

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



<b>Legend</b>		<b>Australian Soil Classification Orders</b>					
Site Boundary	Anthrosol	Dermosol	Kandosol	Podosol	Tenosol	No Data	
Buffer 1000m	Calcarosol	Ferrosol	Kurosol	Rudosol	Vertosol		
Property Boundary	Chromosol	Hydrosol	Organosol	Sodosol	Lake		



Data Sources: Property Boundaries & Topographic Data:  
© Department Finance, Services & Innovation 2023

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 28 March 2023

## Soils

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

### Atlas of Australian Soils

Soil mapping units and Australian Soil Classification orders within the dataset buffer:


Map Unit Code	Soil Order	Map Unit Description	Distance	Direction
Ob7	Chromosol	Gently undulating with long broad slopes and characterized by occasional stone-strewn hilly ridges: chief soils are hard alkaline and neutral red soils (Dr2.23 and Dr2.22) often with a surface scatter of stones and gravel. Associated are some (Dy) and (Gn2.1) soils. Data are limited.	0m	On-site

Atlas of Australian Soils Data Source: CSIRO

Creative Commons 4.0 © Commonwealth of Australia <http://creativecommons.org/licenses/by/4.0/au/deed.en>

# Soil Landscapes of Central and Eastern NSW

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



## Soils

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

### Soil Landscapes of Central and Eastern NSW

Soil Landscapes of Central and Eastern NSW within the dataset buffer:

Soil Code	Name	Distance	Direction
<a href="#">SI5511te</a>	Temora	0m	On-site
<a href="#">SI5511ry</a>	Reynolds	0m	On-site
<a href="#">SI5511tea</a>	Temora variant a	967m	North East

Soil Landscapes of Central and Eastern NSW: NSW Department of Planning, Industry and Environment  
Creative Commons 4.0 © Commonwealth of Australia <http://creativecommons.org/licenses/by/4.0/au/deed.en>

## Acid Sulfate Soils

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

### Environmental Planning Instrument - Acid Sulfate Soils

What is the on-site Acid Sulfate Soil Plan Class that presents the largest environmental risk?

Soil Class	Description	EPI Name
N/A		

If the on-site Soil Class is 5, what other soil classes exist within 500m?

Soil Class	Description	EPI Name	Distance	Direction
N/A				

NSW Crown Copyright - Planning and Environment  
Creative Commons 4.0 © Commonwealth of Australia <https://creativecommons.org/licenses/by/4.0/>

# Atlas of Australian Acid Sulfate Soils

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



<b>Legend</b>			
Site Boundary	<b>Probability of occurrence of Acid Sulfate Soils</b>		
Buffer 1000m	A. High (>70%)	C. Extremely Low (1-5%)	No Data
Property Boundary	B. Low (6-70%)	D. No Chance (0%)	
<b>Scale:</b> 0 100 200 400 600 Meters	<b>Data Sources:</b> Property Boundaries & Topographic Data. © Department Finance, Services & Innovation 2023	<b>Coordinate System:</b> GDA 1994 MGA Zone 56	<b>Date:</b> 28March 2023

## Acid Sulfate Soils

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

### Atlas of Australian Acid Sulfate Soils

Atlas of Australian Acid Sulfate Soil categories within the dataset buffer:

Class	Description	Distance	Direction
C	Extremely low probability of occurrence. 1-5% chance of occurrence with occurrences in small localised areas.	0m	On-site

Atlas of Australian Acid Sulfate Soils Data Source: CSIRO

Creative Commons 3.0 © Commonwealth of Australia <http://creativecommons.org/licenses/by/3.0/au/deed.en>



# Dryland Salinity

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

## Dryland Salinity - National Assessment

Is there Dryland Salinity - National Assessment data onsite?

**No**

Is there Dryland Salinity - National Assessment data within the dataset buffer?

**No**

What Dryland Salinity assessments are given?

Assessment 2000	Assessment 2020	Assessment 2050	Distance	Direction
N/A	N/A	N/A		

Dryland Salinity Data Source : National Land and Water Resources Audit

The Commonwealth and all suppliers of source data used to derive the maps of "Australia, Forecast Areas Containing Land of High Hazard or Risk of Dryland Salinity from 2000 to 2050" do not warrant the accuracy or completeness of information in this product. Any person using or relying upon such information does so on the basis that the Commonwealth and data suppliers shall bear no responsibility or liability whatsoever for any errors, faults, defects or omissions in the information. Any persons using this information do so at their own risk.

In many cases where a high risk is indicated, less than 100% of the area will have a high hazard or risk.

# Mining

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

## Mining Subsidence Districts


Mining Subsidence Districts within the dataset buffer:

District	Distance	Direction
There are no Mining Subsidence Districts within the report buffer		

Mining Subsidence District Data Source: © Land and Property Information (2016)  
Creative Commons 3.0 © Commonwealth of Australia <http://creativecommons.org/licenses/by/3.0/au/deed.en>

# Mining & Exploration Titles

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



# Mining

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

## Current Mining & Exploration Titles

Current Mining & Exploration Titles within the dataset buffer:

Title Ref	Holder	Grant Date	Expiry Date	Last Renewed	Operation	Resource	Minerals	Dist	Dir
EL9258	EX9 PTY LTD	06/08/2021	06/08/2024	20210806	EXPLORING	MINERALS	Group 1, Group 10	0m	On-site
EL6901	CAPE CLEAR (LACHLAN) PTY LTD	08/10/2007	08/10/2023	20210726	EXPLORING	MINERALS	Group 1	514m	South East

Current Mining & Exploration Titles Data Source: © State of New South Wales through NSW Department of Industry

## Current Mining & Exploration Title Applications

Current Mining & Exploration Title Applications within the dataset buffer:

Application Ref	Applicant	Application Date	Operation	Resource	Minerals	Dist	Dir
N/A	No records in buffer						

Current Mining & Exploration Title Applications Data Source: © State of New South Wales through NSW Department of Industry

# Mining

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

## Historical Mining & Exploration Titles

Historical Mining & Exploration Titles within the dataset buffer:

Title Ref	Holder	Start Date	End Date	Resource	Minerals	Dist	Dir
EL6889	NEW SOUTHERN MINING PTY LTD	20071004	20090630	MINERALS	Au	0m	On-site
EL7459	CENTIUS GOLD LIMITED	20100226	20120226	MINERALS		0m	On-site
EL8713	ABUNDANT METALS PTY LTD	20180305	30000101	MINERALS		0m	On-site
EL4522	CRA EXPLORATION PTY LIMITED	19930617	19950616	MINERALS	Au Cu	0m	On-site
EL5256	GOLD MINES OF AUSTRALIA (NSW) PTY LTD	19970317	19990316	MINERALS	Au Cu	0m	On-site
EL3601	NEWCREST MINING (W.A) LIMITED	19900701	19910101	MINERALS	Au	0m	On-site
EL1654	ZENITH EXPLORATIONS PTY LIMITED	19810601	19820601	MINERALS	Au	0m	On-site
EL2196	PARAGON GOLD PTY LIMITED	19840301	19890301	MINERALS	Au Ag	0m	On-site
EL6011	BIG ISLAND MINING LIMITED	20021022	20070212	MINERALS	Au Cu	0m	On-site
EL5929	TEMPLAR RESOURCES LIMITED	20020402	20060401	MINERALS	Diamond	961m	North

Historical Mining & Exploration Titles Data Source: © State of New South Wales through NSW Department of Industry

# State Environmental Planning Policy

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

## State Significant Precincts

What SEPP State Significant Precincts exist within the dataset buffer?

Map Id	Precinct	EPI Name	Published Date	Commenced Date	Currency Date	Amendment	Distance	Direction
N/A	No records in buffer							

State Environment Planning Policy Data Source: NSW Crown Copyright - Planning & Environment  
Creative Commons 4.0 © Commonwealth of Australia <https://creativecommons.org/licenses/by/4.0/>

# EPI Planning Zones

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



# Environmental Planning Instrument

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

## Land Zoning

What EPI Land Zones exist within the dataset buffer?


Zone	Description	Purpose	EPI Name	Published Date	Commenced Date	Currency Date	Amendment	Distance	Direction
SP2	Infrastructure	Hospital	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		0m	On-site
R1	General Residential		Temora Local Environmental Plan 2010	22/04/2016	22/04/2016	01/12/2021	Amendment No 2	0m	West
RE1	Public Recreation		Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		20m	West
SP2	Infrastructure	Seniors Housing	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		20m	North East
R5	Large Lot Residential		Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		215m	North East
IN1	General Industrial		Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		309m	South East
RE2	Private Recreation		Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		343m	West
RE1	Public Recreation		Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		423m	West
RE1	Public Recreation		Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		426m	North West
RU1	Primary Production		Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		455m	East
RE1	Public Recreation		Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		505m	South East
RE1	Public Recreation		Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		635m	South
RE1	Public Recreation		Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		659m	South
RE1	Public Recreation		Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		762m	South West
B2	Local Centre		Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		762m	South West
RE2	Private Recreation		Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		803m	South
RE1	Public Recreation		Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		804m	South
RE1	Public Recreation		Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		817m	North West
RE1	Public Recreation		Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		867m	North West
B4	Mixed Use		Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		938m	West
RE2	Private Recreation		Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	01/12/2021		987m	South West

Environmental Planning Instrument Data Source: NSW Crown Copyright - Planning & Environment Creative Commons 4.0 © Commonwealth of Australia <https://creativecommons.org/licenses/by/4.0/>




# Heritage Items

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666



## Legend

- Site Boundary
- Commonwealth Heritage List
- State Heritage Items
- Buffer 1000m
- National Heritage List
- EPI Heritage Items
- Property Boundary



Data Sources: Property Boundaries & Topographic Data:  
 © Department Finance, Services & Innovation 2023  
 Heritage - NSW Crown Copyright - Planning & Environment

Coordinate System:  
 GDA 1994 MGA Zone 56

Date: 28 March 2023

## Heritage

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

### Commonwealth Heritage List

What are the Commonwealth Heritage List Items located within the dataset buffer?

Place Id	Name	Address	Place File No	Class	Status	Register Date	Distance	Direction
106129	Temora Post Office	173 Hoskins St, Temora NSW	1/06/319/0005	Historic	Listed place	08/11/2011	774m	South West

Heritage Data Source: Australian Government Department of the Environment and Energy - Heritage Branch  
Creative Commons 3.0 © Commonwealth of Australia <https://creativecommons.org/licenses/by/3.0/au/deed.en>

### National Heritage List

What are the National Heritage List Items located within the dataset buffer?

Note. Please click on Place Id to activate a hyperlink to online website.

Place Id	Name	Address	Place File No	Class	Status	Register Date	Distance	Direction
N/A	No records in buffer							

Heritage Data Source: Australian Government Department of the Environment and Energy - Heritage Branch  
Creative Commons 3.0 © Commonwealth of Australia <https://creativecommons.org/licenses/by/3.0/au/deed.en>

### State Heritage Register - Curtilages

What are the State Heritage Register Items located within the dataset buffer?

Map Id	Name	Address	LGA	Listing Date	Listing No	Plan No	Distance	Direction
N/A	No records in buffer							

Heritage Data Source: NSW Crown Copyright - Office of Environment & Heritage  
Creative Commons 4.0 © Commonwealth of Australia <https://creativecommons.org/licenses/by/4.0/>

### Environmental Planning Instrument - Heritage

What are the EPI Heritage Items located within the dataset buffer?

Map Id	Name	Classification	Significance	EPI Name	Published Date	Commenced Date	Currency Date	Distance	Direction
I108	Temora & District Hospital	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	0m	On-site
I17	House (Thurles) - Anzac/George St	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	128m	West
I80	House - Goode-Loftus St	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	128m	South West

Map Id	Name	Classification	Significance	EPI Name	Published Date	Commenced Date	Currency Date	Distance	Direction
I128	House Meagher Residence	Item - General	Local	Temora Local Environmental Plan 2010	21/02/2020	21/02/2020	21/02/2020	136m	South
I93	House - Carson St	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	217m	South
I82	House - Matthews - Redmund St	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	234m	South
I13	House (Craigendoran) - Asquith St	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	246m	West
I103	Lutheran Church	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	273m	South West
I12	House (Booralga) - Polaris St	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	284m	North West
I79	House - Anderson - Kitchener Rd	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	306m	North West
I158	Former Methodist Church Manse	Item - General	Local	Temora Local Environmental Plan 2010	21/02/2020	21/02/2020	21/02/2020	343m	North West
I52	Temora War Memorials - Callaghan Park	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	478m	South West
I3	Catholic Presbytery	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	575m	South West
I102	7th Day Adventist	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	596m	West
I155	St Brigid's Convent	Item - General	Local	Temora Local Environmental Plan 2010	21/02/2020	21/02/2020	21/02/2020	631m	South West
I2	Roman Catholic Church	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	632m	South West
I11	Temora Public School (original building)	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	632m	West
I5	St. Joseph's Hall	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	632m	South West
B	Civic Conservation Area	Conservation Area - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	632m	South West
I4	St. Anne's Original School Building	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	634m	South West
I94	House (Formerly Surgery - Parry) - DeBoos St	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	654m	South West
I10	Temora Fire Station	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	660m	South West
I95	House (Rotunda) - Block - DeBoos St	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	660m	West
I75	Uniting Church	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	673m	West
I132	Narraburra Shire Offices - Senior Citizens Centre	Item - General	Local	Temora Local Environmental Plan 2010	21/02/2020	21/02/2020	21/02/2020	712m	West
I91	House (Carlton House) - DeBoos St	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	712m	West
I109	Temora Council Chambers	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	712m	South West

Map Id	Name	Classification	Significance	EPI Name	Published Date	Commenced Date	Currency Date	Distance	Direction
I6	St. Andrew's Presbyterian Church & Hall	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	713m	South West
I55	Anglican Church (Temora)	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	714m	South West
I90	House (Police Lock Up Keepers) - DeBoos St	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	718m	South West
I89	House (Police Station) - DeBoos St	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	721m	South West
I8	Court House (Temora)	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	728m	South West
I14	House (Mortlake) - Victoria St	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	743m	South West
I9	Masonic Hall & Temple	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	759m	South West
I126	House Armagh	Item - General	Local	Temora Local Environmental Plan 2010	21/02/2020	21/02/2020	21/02/2020	766m	South West
I15	House (Terenge) - Victoria St	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	767m	South West
I139	Commercial Bank of Australia building	Item - General	Local	Temora Local Environmental Plan 2010	21/02/2020	21/02/2020	21/02/2020	769m	South West
A	Central Conservation Area	Conservation Area - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	769m	South West
I31	Main St Variety (Strand Theatre)	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	769m	South West
I30	ANZ Bank	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	769m	South West
I140	Rural Bank building	Item - General	Local	Temora Local Environmental Plan 2010	21/02/2020	21/02/2020	21/02/2020	769m	South West
I32	Sutton's Motors Building	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	769m	South West
I136	Paleface Park - Queensland Hotel Site	Item - General	Local	Temora Local Environmental Plan 2010	21/02/2020	21/02/2020	21/02/2020	769m	South West
I29	Temora Post Office	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	770m	South West
I28	Creaghe Lisle (CBC Bank)	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	772m	South West
I124	Patchwork Inn B & B	Item - General	Local	Temora Local Environmental Plan 2010	21/02/2020	21/02/2020	21/02/2020	774m	South West
I26	Target (Thom's Store)	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	777m	South West
I34	Temora Ambulance Station	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	777m	West
I112	Commonwealth Bank	Item - General	Local	Temora Local Environmental Plan 2010	21/02/2020	21/02/2020	21/02/2020	784m	South West
I22	Westminster Hotel	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	819m	South West
I19	Auswild Complex	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	850m	South West

Map Id	Name	Classification	Significance	EPI Name	Published Date	Commenced Date	Currency Date	Distance	Direction
I33	Railway Hotel	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	850m	West
I27	Temora House	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	850m	South West
I25	Westpac Bank (Temora)	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	850m	South West
I24	Temora Hotel	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	853m	South West
I23	Miller & James	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	856m	South West
I143	Melzer House	Item - General	Local	Temora Local Environmental Plan 2010	21/02/2020	21/02/2020	21/02/2020	858m	West
I125	Royal Hotel	Item - General	Local	Temora Local Environmental Plan 2010	21/02/2020	21/02/2020	21/02/2020	865m	South West
I21	John Meagher Building	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	869m	South West
I141	Brick Shed	Item - General	Local	Temora Local Environmental Plan 2010	21/02/2020	21/02/2020	21/02/2020	893m	South West
I101	Kingdom Hall	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	896m	West
I142	McGuirks Tyre Service	Item - General	Local	Temora Local Environmental Plan 2010	21/02/2020	21/02/2020	21/02/2020	908m	West
I20	Shamrock Hotel	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	940m	South West
I100	Salvation Army	Item - General	Local	Temora Local Environmental Plan 2010	11/06/2010	11/06/2010	21/02/2020	943m	South West

Heritage Data Source: NSW Crown Copyright - Planning & Environment

Creative Commons 4.0 © Commonwealth of Australia <https://creativecommons.org/licenses/by/4.0/>

## Natural Hazards

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

### Bush Fire Prone Land

What are the nearest Bush Fire Prone Land Categories that exist within the dataset buffer?

Bush Fire Prone Land Category	Distance	Direction
No records in buffer		

NSW Bush Fire Prone Land - © NSW Rural Fire Service under Creative Commons 4.0 International Licence

## Ecological Constraints

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

### Ramsar Wetlands

What Ramsar Wetland areas exist within the dataset buffer?

Map Id	Ramsar Name	Wetland Name	Designation Date	Source	Distance	Direction
N/A	No records in buffer					

Ramsar Wetlands Data Source: © Commonwealth of Australia - Department of Agriculture, Water and the Environment

## Ecological Constraints

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

### Groundwater Dependent Ecosystems Atlas

Type	GDE Potential	Geomorphology	Ecosystem Type	Aquifer Geology	Distance	Direction
N/A	No records in buffer					

Groundwater Dependent Ecosystems Atlas Data Source: The Bureau of Meteorology  
Creative Commons 3.0 © Commonwealth of Australia <http://creativecommons.org/licenses/by/3.0/au/deed.en>



## Ecological Constraints

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

### Inflow Dependent Ecosystems Likelihood

Type	IDE Likelihood	Geomorphology	Ecosystem Type	Aquifer Geology	Distance	Direction
N/A	No records in buffer					

Inflow Dependent Ecosystems Likelihood Data Source: The Bureau of Meteorology

Creative Commons 3.0 © Commonwealth of Australia <http://creativecommons.org/licenses/by/3.0/au/deed.en>

## Ecological Constraints

Temora Hospital, 169-189 Loftus Street, Temora, NSW 2666

### NSW BioNet Atlas

Species on the NSW BioNet Atlas that have a NSW or federal conservation status, a NSW sensitivity status, or are listed under a migratory species agreement, and are within 10km of the site?

Kingdom	Class	Scientific	Common	NSW Conservation Status	NSW Sensitivity Class	Federal Conservation Status	Migratory Species Agreements
Animalia	Aves	Anseranas semipalmata	Magpie Goose	Vulnerable	Not Sensitive	Not Listed	
Animalia	Aves	Artamus cyanopterus cyanopterus	Dusky Woodswallow	Vulnerable	Not Sensitive	Not Listed	
Animalia	Aves	Circus assimilis	Spotted Harrier	Vulnerable	Not Sensitive	Not Listed	
Animalia	Aves	Climacteris picumnus victoriae	Brown Treecreeper (eastern subspecies)	Vulnerable	Not Sensitive	Not Listed	
Animalia	Aves	Daphoenositta chrysoptera	Varied Sittella	Vulnerable	Not Sensitive	Not Listed	
Animalia	Aves	Epthianura albifrons	White-fronted Chat	Vulnerable	Not Sensitive	Not Listed	
Animalia	Aves	Gallinago hardwickii	Latham's Snipe	Not Listed	Not Sensitive	Not Listed	ROKAMBA;JAMBA
Animalia	Aves	Hieraaetus morphnoides	Little Eagle	Vulnerable	Not Sensitive	Not Listed	
Animalia	Aves	Lathamus discolor	Swift Parrot	Endangered	Not Sensitive	Critically Endangered	
Animalia	Aves	Melanodryas cucullata cucullata	Hooded Robin (south-eastern form)	Vulnerable	Not Sensitive	Not Listed	
Animalia	Aves	Ninox connivens	Barking Owl	Vulnerable	Category 3	Not Listed	
Animalia	Aves	Petroica phoenicea	Flame Robin	Vulnerable	Not Sensitive	Not Listed	
Animalia	Aves	Polytelis swainsonii	Superb Parrot	Vulnerable	Category 3	Vulnerable	
Animalia	Aves	Pomatostomus temporalis temporalis	Grey-crowned Babbler (eastern subspecies)	Vulnerable	Not Sensitive	Not Listed	
Animalia	Aves	Stagonopleura guttata	Diamond Firetail	Vulnerable	Not Sensitive	Not Listed	
Animalia	Aves	Stictonetta naevosa	Freckled Duck	Vulnerable	Not Sensitive	Not Listed	
Plantae	Flora	Lepidium aschersonii	Spiny Peppergrass	Vulnerable	Not Sensitive	Vulnerable	

Data does not include NSW category 1 sensitive species.

NSW BioNet: © State of NSW and Office of Environment and Heritage

## Location Confidences

Where Lotsearch has had to georeference features from supplied addresses, a location confidence has been assigned to the data record. This indicates a confidence to the positional accuracy of the feature. Where applicable, a code is given under the field heading "LC" or "LocConf". These codes lookup to the following location confidences:

LC Code	Location Confidence
Premise Match	Georeferenced to the site location / premise or part of site
Area Match	Georeferenced to an approximate or general area
Road Match	Georeferenced to a road or rail corridor
Road Intersection	Georeferenced to a road intersection
Buffered Point	A point feature buffered to x metres
Adjacent Match	Land adjacent to a georeferenced feature
Network of Features	Georeferenced to a network of features
Suburb Match	Georeferenced to a suburb boundary
As Supplied	Spatial data supplied by provider

## USE OF REPORT - APPLICABLE TERMS

The following terms apply to any person (End User) who is given the Report by the person who purchased the Report from Lotsearch Pty Ltd (ABN: 89 600 168 018) (Lotsearch) or who otherwise has access to the Report (Terms). The contract terms that apply between Lotsearch and the purchaser of the Report are specified in the order form pursuant to which the Report was ordered and the terms set out below are of no effect as between Lotsearch and the purchaser of the Report.

1. End User acknowledges and agrees that:
  - (a) the Report is compiled from or using content (**Third Party Content**) which is comprised of:
    - (i) content provided to Lotsearch by third party content suppliers with whom Lotsearch has contractual arrangements or content which is freely available or methodologies licensed to Lotsearch by third parties with whom Lotsearch has contractual arrangements (**Third Party Content Suppliers**); and
    - (ii) content which is derived from content described in paragraph (i);
  - (b) Neither Lotsearch nor Third Party Content Suppliers takes any responsibility for or give any warranty in relation to the accuracy or completeness of any Third Party Content included in the Report including any contaminated land assessment or other assessment included as part of a Report;
  - (c) the Third Party Content Suppliers do not constitute an exhaustive set of all repositories or sources of information available in relation to the property which is the subject of the Report (**Property**) and accordingly neither Lotsearch nor Third Party Content Suppliers gives any warranty in relation to the accuracy or completeness of the Third Party Content incorporated into the report including any contaminated land assessment or other assessment included as part of a Report;
  - (d) Reports are generated at a point in time (as specified by the date/time stamp appearing on the Report) and accordingly the Report is based on the information available at that point in time and Lotsearch is not obliged to undertake any additional reporting to take into consideration any information that may become available between the point in time specified by the date/time stamp and the date on which the Report was provided by Lotsearch to the purchaser of the Report;
  - (e) Reports must be used or reproduced in their entirety and End User must not reproduce or make available to other persons only parts of the Report;
  - (f) Lotsearch has not undertaken any physical inspection of the property;
  - (g) neither Lotsearch nor Third Party Content Suppliers warrants that all land uses or features whether past or current are identified in the Report;
  - (h) the Report does not include any information relating to the actual state or condition of the Property;
  - (i) the Report should not be used or taken to indicate or exclude actual fitness or unfitness of Land or Property for any particular purpose
  - (j) the Report should not be relied upon for determining saleability or value or making any other decisions in relation to the Property and in particular should not be taken to be a rating or assessment of the desirability or market value of the property or its features; and
  - (k) the End User should undertake its own inspections of the Land or Property to satisfy itself that there are no defects or failures
2. The End User may not make the Report or any copies or extracts of the report or any part of it available to any other person. If End User wishes to provide the Report to any other person or make extracts or copies of the Report, it must contact the purchaser of the Report before doing so to ensure the proposed use is consistent with the contract terms between Lotsearch and the purchaser.
3. Neither Lotsearch (nor any of its officers, employees or agents) nor any of its Third Party Content Suppliers will have any liability to End User or any person to whom End User provides the Report and End User must not represent that Lotsearch or any of its Third Party Content Suppliers accepts liability to any such person or make any other representation to any such person on behalf of Lotsearch or any Third Party Content Supplier.
4. The End User hereby to the maximum extent permitted by law:
  - (a) acknowledges that the Lotsearch (nor any of its officers, employees or agents), nor any of its Third Party Content Supplier have any liability to it under or in connection with the

- Report or these Terms;
- (b) waives any right it may have to claim against Third Party Content Supplier in connection with the Report, or the negotiation of, entry into, performance of, or termination of these Terms; and
  - (c) releases each Third Party Content Supplier from any claim it may have otherwise had in connection with the Report, or the negotiation of, entry into, performance of, or termination of these Terms.
5. The End User acknowledges that any Third Party Supplier shall be entitled to plead the benefits conferred on it under clause 4, despite not being a party to these terms.
  6. End User must not remove any copyright notices, trade marks, digital rights management information, other embedded information, disclaimers or limitations from the Report or authorise any person to do so.
  7. End User acknowledges and agrees that Lotsearch and Third Party Content Suppliers retain ownership of all copyright, patent, design right (registered or unregistered), trade marks (registered or unregistered), database right or other data right, moral right or know how or any other intellectual property right in any Report or any other item, information or data included in or provided as part of a Report.
  8. To the extent permitted by law and subject to paragraph 9, all implied terms, representations and warranties whether statutory or otherwise relating to the subject matter of these Terms other than as expressly set out in these Terms are excluded.
  9. Subject to paragraph 6, Lotsearch excludes liability to End User for loss or damage of any kind, however caused, due to Lotsearch's negligence, breach of contract, breach of any law, in equity, under indemnities or otherwise, arising out of all acts, omissions and events whenever occurring.
  10. Lotsearch acknowledges that if, under applicable State, Territory or Commonwealth law, End User is a consumer certain rights may be conferred on End User which cannot be excluded, restricted or modified. If so, and if that law applies to Lotsearch, then, Lotsearch's liability is limited to the greater of an amount equal to the cost of resupplying the Report and the maximum extent permitted under applicable laws.
  11. Subject to paragraph 9, neither Lotsearch nor the End User is liable to the other for:
    - (a) any indirect, incidental, consequential, special or exemplary damages arising out of or in relation to the Report or these Terms; or
    - (b) any loss of profit, loss of revenue, loss of interest, loss of data, loss of goodwill or loss of business opportunities, business interruption arising directly or indirectly out of or in relation to the Report or these Terms,
 irrespective of how that liability arises including in contract or tort, liability under indemnity or for any other common law, equitable or statutory cause of action or otherwise.
  12. These Terms are subject to New South Wales law.



---

## Land Title Records



ABN: 36 092 724 251  
Ph: 02 9099 7400  
(Ph: 0412 199 304)

Level 14, 135 King Street, Sydney  
Sydney 2000  
GPO Box 4103 Sydney NSW 2001  
DX 967 Sydney

Report

NSW LRS

Sydney

Re: - Temora Hospital 169 to 189 Loftus Street, Temora

Description: - Lot 2 D.P. 572392

<u>Date of Acquisition and term held</u>	<u>Registered Proprietor(s) &amp; Occupations where available</u>	<u>Reference to Title at Acquisition and sale</u>
16.03.1899 (1899 to 1926)	Emily Hamlyn Dibbs (Married Woman)	Volume 913 Folio 23
11.02.1926 (1926 to 1936)	Saville Darcy Morton (Farmer)	Volume 913 Folio 23
24.09.1930 (1930 to 2019)	The Temora and District Hospital	Volume 913 Folio 23 Then Volume 4799 Folio 48 Volume 12452 Folios 7 & 8 Volume 12572 Folio 114 Now 2/572392
13.09.2019 (2019 to Date)	# Health Administration Corporation	2/572392

# Denotes Current Registered Proprietors

Easements and Leases: - NIL

Yours Sincerely  
Mark Groll  
11 April 2023

Cadastral Records Enquiry Report : Lot 2 DP 572392



Ref : Temora Hospital

Parish : BUNDAWARRAH  
County : BLAND



2  
DP 182469

TEMORA  
SHIRE  
COUNCIL



GLOUCESTER ST

1095

DP 750587

GEORGE ST

ANZAC ST

DP 387115

DP 946074

DP 971960

DP 45453

DP 946074

DP 1110193\*

DP 664428

DP 306317

DP 590281

DP 834

79351

DP 572392

DP 191813

LOFTUS ST

MEAGHER ST

105672843

DP 36866

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871

DP 27871






WARNING: ORCADING OR FOLDING WILL LEAD TO REJECTION

<p><b>Council Clerk's Certificate.</b></p> <p>I hereby certify that—</p> <p>(a) the requirements of the Local Government Act, 1919 have been complied with by the applicant in relation to the proposed plan, and</p> <p>(b) the requirements of section 212 of the Metropolitan Water, Sewerage, and Drainage Act, 1924, as amended, 1928, or as amended, have been complied with by the applicant in relation to the proposed plan.</p> <p>Subdivision No. <u>467A</u></p> <p>Date <u>26 August 1974</u></p> <p>(Signature) <i>[Signature]</i>                  Council Clerk</p> <p>This part of certificate to be deleted where the application is only for a consolidation or the opening of a new road or where the land to be subdivided is wholly within the area of operation of the Metropolitan Water Sewerage and Drainage Board and the Major District Water Board.</p> <p>Signatures, seals and statements of intention to dedicate public roads or to create public reserves, drainage reserves, easements or restrictions as to user.</p>	<p><b>Surveyor's Certificate</b></p> <p>(VINCENT JAMES HUMPHREYS)</p> <p>of COOTAMUNDRA</p> <p>a surveyor registered under the Surveyors Act, 1925, as amended hereby certify that the survey represented in this plan is correct and has been made in accordance with the Survey Practice Regulations, 1923, and was completed on <u>17-8-1974</u></p> <p>Signature <i>[Signature]</i>                  Surveyor registered under Surveyors Act, 1925, as amended. Class List of Address "A-15"</p>	<p><b>PLAN</b></p> <p>OF SUBDIVISION OF <del>LOT 1 AND 2 D.P. 568979</del></p> <p>LOTS 1 AND 2 D.P. 568979</p> <p>Registered: <u>1-10-1974</u></p> <p>C.A. No. <u>467A</u> OF <u>26-B-1974</u></p> <p>Title System: <u>TORRENS</u></p> <p>Purpose: <u>SUBDIVISION</u></p> <p>Ref. Map: <u>TEMORA SH2</u></p> <p>Last Plan: <u>D.P. 568979</u></p> <p>Mun./Shire: <u>TEMORA</u> Locality: <u>TEMORA</u></p> <p>City: <u>TEMORA</u></p> <p>Parish: <u>SUNDAWARRAH</u> County: <u>BLAND</u></p> <p>Reduction Ratio <u>1:2000</u> Lengths are in metres.</p>
<p style="font-size: small;">M. P. D. SURVEYOR'S REFERENCE: 219/1</p>		
<p style="font-size: small;">Plan Drawing only to appear in this space.</p>		

D. P. 572 392

in Common Seal of the Temora District Council was hereunto affixed pursuant to a resolution of the Council on 27th August, 1974 and recorded in the Minute Book of the Council at which such resolution was passed in the presence of

*[Signature]* Mayor  
*[Signature]* Chief Executive Officer



I, Jack Hayward Watson, Registrar General for New South Wales, certify that this negative is a photograph made as a permanent record of a document in my custody this 2nd day of October, 1974.

*[Signature]*

# CERTIFICATE OF TITLE



12452007

NEW SOUTH WALES

PROPERTY ACT, 1900

Vol. **12452** Fol. **7**

Crown Grant Vol. 913 Fol.23

Prior Title Vol.4799 Fol.48



Edition issued 31-5-1974.

**CANCELLED**


I certify that the person described in the First Schedule is the registered proprietor of the undermentioned estate in the land within described subject nevertheless to such exceptions encumbrances and interests as are shown in the Second Schedule.

*Jawaton*  
Registrar General.



## PLAN SHOWING LOCATION OF LAND

LENGTHS ARE IN METRES



### ESTATE AND LAND REFERRED TO

Estate in Fee Simple in Lot 3 in Deposited Plan 568979 at Temora in the Municipality of Temora Parish of Bundawarra and County of Bland. EXCEPTING THEREOUT the minerals reserved by the Crown Grant.

### FIRST SCHEDULE

THE TEMORA AND DISTRICT HOSPITAL.

### SECOND SCHEDULE

1. Reservations and conditions, if any, contained in the Crown Grant above referred to.

NOTE: ENTRIES RULED THROUGH AND AUTHENTICATED BY THE SEAL OF THE REGISTRAR GENERAL ARE CANCELLED.

PERSONS ARE CAUTIONED AGAINST ALTERING OR ADDING TO THIS CERTIFICATE OR ANY NOTIFICATION HEREIN

WARNING: THIS DOCUMENT MUST NOT BE REMOVED FROM THE LAND TITLES OFFICE.

(Page 1) Vol. 12452 Fol. 7


DP52239  
 8/1/07  
 [Signature]

FIRST SCHEDULE (continued)

REGISTERED PROPRIETOR

INSTRUMENT  
 NATURE      NUMBER      DATE      ENTERED      Signature of Registrar General

4/10 This deed is cancelled as to the whole  
 New Certificates of Title have issued on 15-12-1974  
 for lots in Deposited Plan No. 572392 as follows:  
 Lots 1-2 Vol. 12572 Fol. 113-114 respectively.

*Joubertson* 

REGISTRAR GENERAL

SECOND SCHEDULE (continued)

INSTRUMENT      PARTICULARS      ENTERED      Signature of Registrar General      CANCELLATION  
 NATURE      NUMBER      DATE

NOTE: ENTRIES RULED THROUGH AND AUTHENTICATED BY THE SEAL OF THE REGISTRAR GENERAL ARE CANCELLED







# CIFICATE OF TITLE



12572-114

NEW SOUTH WALES

REAL PROPERTY ACT, 1900

Vol. **12572** Fol. **114**

Edition issued 14-10-1974

Crown Grant Vol. 913 Fol. 23

Prior Titles Vol. 12452 Fols. 7 & 8



12572 Fol. 114

(Page 1) Vol.

I certify that the person described in the First Schedule is the registered proprietor of the undermentioned estate in the land with the described subject, nevertheless to such exceptions encumbrances and interests as are shown in the Second Schedule.

*Jawatson*  
Registrar General




SEE AUTO FOLIO



## PLAN SHOWING LOCATION OF LAND

LENGTHS ARE IN METRES



### ESTATE AND LAND REFERRED TO

Estate in Fee Simple in Lot 2 in Deposited Plan 572392 at Temora in the Municipality of Temora, Parish of Bundawarra and County of Bland. EXCEPTING THEREOUT the minerals reserved by the Crown Grants.

### FIRST SCHEDULE

THE TEMORA AND DISTRICT HOSPITAL.

### SECOND SCHEDULE

GRM

1. Reservations and conditions, if any, contained in the Crown Grant above referred to.

PERSONS ARE CAUTIONED AGAINST ALTERING OR ADDING TO THIS CERTIFICATE OR ANY NOTIFICATION HEREON

WARNING: THIS DOCUMENT MUST NOT BE REMOVED FROM THE LAND TITLES OFFICE.





SEARCH DATE

11/4/2023 9:09AM

FOLIO: 2/572392

First Title(s): SEE PRIOR TITLE(S)

Prior Title(s): VOL 12572 FOL 114

Recorded	Number	Type of Instrument	C.T. Issue
28/3/1988		TITLE AUTOMATION PROJECT	LOT RECORDED FOLIO NOT CREATED
8/8/1988		CONVERTED TO COMPUTER FOLIO	FOLIO CREATED CT NOT ISSUED
13/9/2019	AP410680	REQUEST	
13/9/2019	AP535301	DEPARTMENTAL DEALING	EDITION 1

\*\*\* END OF SEARCH \*\*\*





Form: IIR  
 Release: 4.3

**REQUEST**  
 New South Wales  
 Real Property Act 1900

**AP410680K**

**PRIVACY NOTE:** Section 31B of the Real Property Act 1900 (RP Act) authorises the Registrar General to correct the information required by this form for the establishment and maintenance of the Real Property Act Register. Section 96B RP Act requires that the Register is made available to any person for search upon payment of a fee, if any.

All Statutory Declarations and evidence that are lodged in support of land dealings will be treated as publicly accessible and will be disclosed to persons upon request.

(A) STAMP DUTY	If applicable. Revenue NSW use only		<div style="border: 1px solid black; padding: 5px; display: inline-block;"> <b>RELOADED</b>                  30 AUG 2019             </div>
(B) TORRENS TITLE	See Annexure X		
(C) REGISTERED DEALING	Number	Torrens Title	TIME: 1.05
(D) LODGED BY	Document Collection Box <b>47 V</b>	Name, Address or DX, Telephone, and Customer Account Number if any LLPN 123012 E H.M. Allen & Co. DX 437 Sydney Ph 9232 3652 Reference: <u>NSW HEALTH MCMD62</u>	CODE  <b>R</b>
(E) APPLICANT	Health Administration Corporation ABN 45 100 538 161		
(F) NATURE OF REQUEST	Issue of Certificates of Title		


(G) TEXT OF REQUEST


The Health Administration Corporation has acquired the subject land pursuant to the Land Acquisition (Just Terms Compensation) Act 1991 and the Health Administration Act 1982. A copy of the acquisition notice from NSW Government Gazette No. 73 dated 12th July 2019 (n2019-2054) is attached at Annexure "Y". It is requested that the titles for the acquired land be issued in the name of the Health Administration Corporation.


DATE \_\_\_\_\_

(H) I certify that I am an eligible witness and that an authorised officer of the applicant signed this dealing in my presence. [See note\* below].

Certified correct for the purposes of the Real Property Act 1900 by the authorised officer named below.

Signature of witness:   
 Name of witness: Shane Kenyon  
 Address of witness: 73 Miller Street, North Sydney, NSW

Signature of authorised officer:   
 Authorised officer's name: Bryson Wilson  
 Authority of officer: Delegate  
 Signing on behalf of: Health Administration Corporation

(I) This section is to be completed where a notice of sale is required and the relevant data has been forwarded through eNOS. The applicant \_\_\_\_\_ certifies that the eNOS data relevant to this dealing has been submitted and stored under eNOS ID No. 1866761 Full name: Shane Kenyon Signature: 

\* s117 RP Act requires that you must have known the signatory for more than 12 months or have sighted identifying documentation.  
 ALL HANDWRITING MUST BE IN BLOCK CAPITALS Page 1 of 58 1708

EXTRA  
 @ 2x FEES RAISED.

Annexure: X to Request

Parties:

Health Administration Corporation

Text:

(B) TORRENS TITLE

Being

Lot	Section	Plan	Plan No	Vol/Folio	Auto Consol
7	33	DP	257	246/249	
9	Z	DP	3041		
10	Z	DP	3041		
11	Z	DP	3041		
12	Z	DP	3041		
3		DP	41412	11085/230	
218		DP	41481	4590/2	
1		DP	129140	4864/158	being whole Auto Consol 4864-158
1	69	DP	758757	4864/158	
1		DP	129211	4822/173	
2		DP	129211	4216/31	
3		DP	129211	4251/8	
4		DP	129211	4126/140	
5		DP	129211	4242/137	
1		DP	132967	12479/2	being whole Auto Consol 12479-2
2	64	DP	758757	12479/2	
3	64	DP	758757	12479/2	
4	64	DP	758757	12479/2	
5	64	DP	758757	12479/2	
6	64	DP	758757	12479/2	
10		DP	301282		
1		DP	319733		
2		DP	319733		
1		DP	542301	11329/153	
1		DP	556329	11948/13	
1		DP	572392	12572/113	
2		DP	572392	12572/114	
2		DP	604639		
9		DP	667767		
2		DP	748864		

Lot	Section	Plan	Plan No	Vol/Folio	Auto Consol
147		DP	756426	8458/70	
148		DP	756426	8458/70	being whole Auto Consol 8458-70
149		DP	756426	8458/70	
150		DP	756426	8458/70	
151		DP	756426	8458/70	
153		DP	756426	1149/228	
154		DP	756426	1153/11	
2	29	DP	758009		
3	29	DP	758009		
10	9	DP	758621		
5	1	DP	758713	14688/209	*
1	64	DP	758757	12479/1	
1	3	DP	759066	4619/18	
10	51	DP	759144	6757/143	
2		DP	815888		
1		DP	818278		
2		DP	818278		
2		DP	1038477		
9132		DP	1041292		
2		DP	1043580		
11		DP	1055714		
1		DP	1070392		
2		DP	1070392		
21		DP	1077622		
1		DP	1144609	4761/216	
2		DP	1167182		
100		DP	1167917		
22		DP	1173233		
16		DP	1180488	5642/28	
18		DP	1184334		
19		DP	1184334		
451		DP	1248604		

\* now being title 5/1137023

# ANNEXURE "Y"

## **HEALTH ADMINISTRATION ACT 1982**

### **LAND ACQUISITION (JUST TERMS COMPENSATION) ACT 1991**

### **NOTICE OF ACQUISITION OF LAND BY COMPULSORY PROCESS**

### **FOR THE PURPOSES OF THE HEALTH ADMINISTRATION ACT 1982**

Pursuant to section 10 of the *Health Administration Act 1982* and section 19(1) of the *Land Acquisition (Just Terms Compensation) Act 1991*, the Health Administration Corporation by its delegate declares, with the approval of the Governor, that the land described in Schedule 1 below is by this notice acquired by compulsory process for the purposes of the *Health Administration Act 1982*.

SIGNED at North Sydney this 4th day of July 2019.

B.Wilson  
Manager, Assets  
NSW Ministry of Health  
a duly authorised delegate of the  
Health Administration Corporation

#### **SCHEDULE 1**

##### Land

All those pieces or parcels of land described in Annexure "A" ("the Land") excluding the interests in the Land listed in Schedule 2 ("Excluded Interests").

#### **SCHEDULE 2**

##### Excluded Interests

All other existing interests, easements, leases, unregistered leases, covenants, caveats, rights, charges, restrictions, licences coupled with an interest, native title rights and interests, profits a prendre, mortgages and contracts in, over or in connection with the Land.

Lismore Base Hospital Hunter Street, Lismore 2480	1	DP 350710	THE LISMORE BASE HOSPITAL	1/DP350710
Lismore Base Hospital Hunter Street, Lismore 2480	1	DP 350717	THE LISMORE BASE HOSPITAL	1/DP350717
Lismore Base Hospital Hunter Street, Lismore 2480	1	DP 511444	THE LISMORE BASE HOSPITAL	1/DP511444
Lismore Base Hospital Hunter Street, Lismore 2480	22	DP 589890	NORTHERN NSW LOCAL HEALTH DISTRICT	22/DP589890
Lismore Base Hospital Hunter Street, Lismore 2480	267	DP 755718	NORTHERN NSW LOCAL HEALTH DISTRICT	267/DP755718
Lismore Base Hospital Hunter Street, Lismore 2480	1	DP 820625	NORTH COAST AREA HEALTH SERVICE	1/DP820625
Lismore Base Hospital Hunter Street, Lismore 2480	10	DP 1109862	NORTH COAST AREA HEALTH SERVICE	10/DP1109862
Medical Centre, 29 Uralba Street, Lismore 2480	1	DP 120560	THE HEALTH ADMINISTRATION CORPORATION	1/DP120560
Cootamundra Ambulance Station, 83 Parker Street, Cootamundra 2590	A	DP 349286	NEW SOUTH WALES AMBULANCE TRANSPORT SERVICE BOARD	A/DP349286
Nimbin Community Health Centre, 31 Cullen Street, Nimbin 2480	1	DP 1096006	NORTH COAST AREA HEALTH SERVICE	1/DP1096006
Temora District Hospital, Kitchener Road, Temora 2666	1	DP 572392	THE TEMORA AND DISTRICT HOSPITAL	1/DP572392
Temora District Hospital, Kitchener Road, Temora 2666	2	DP 572392	THE TEMORA AND DISTRICT HOSPITAL	2/DP572392
Temora District Hospital, Kitchener Road, Temora 2666	2	DP 748864	THE TEMORA DISTRICT HOSPITAL	2/DP748864
Gundagai District Hospital, William, Torr Street, Gundagai 2722	22	DP 1173233	MURRUMBIDGEE LOCAL HEALTH DISTRICT	22/DP1173233
Cootamundra Hospital, Mackay Street, Dickson Street, Cootamundra 2590	100	DP 1167917	THE HEALTH ADMINISTRATION CORPORATION	100/DP1167917
Lockhart District Hospital, Hebden Street, Lockhart 2656	1	DP 319733	MURRUMBIDGEE LOCAL HEALTH DISTRICT	1/DP319733
Lockhart District Hospital, Hebden Street, Lockhart 2656	2	DP 319733	MURRUMBIDGEE LOCAL HEALTH DISTRICT	2/DP319733



FOLIO: 2/572392

-----

SEARCH DATE	TIME	EDITION NO	DATE
-----	----	-----	----
11/4/2023	9:04 AM	1	13/9/2019

LAND

-----

LOT 2 IN DEPOSITED PLAN 572392  
AT TEMORA  
LOCAL GOVERNMENT AREA TEMORA  
PARISH OF BUNDAWARRAH COUNTY OF BLAND  
TITLE DIAGRAM DP572392

FIRST SCHEDULE

-----

HEALTH ADMINISTRATION CORPORATION (R AP410680)

SECOND SCHEDULE (1 NOTIFICATION)

-----

1 LAND EXCLUDES MINERALS AND IS SUBJECT TO RESERVATIONS AND  
CONDITIONS IN FAVOUR OF THE CROWN - SEE CROWN GRANT(S)

NOTATIONS

-----

UNREGISTERED DEALINGS: NIL

\*\*\* END OF SEARCH \*\*\*



---

## Local Council Records

**Regulator File Reference:**

Environmental Planning & Assessment Amendment (Fire Safety & Building Certification) Regulation 2017.  
 Issued under the Environmental Planning & Assessment Regulation 2000, Part 9, Division 5.

## 1. Type of statement

an annual fire safety statement |  Supplementary Statement

## 2. Building the subject of this statement

Flat/Street no. **N/A** Street name **Loftus Street**  
 Suburb or town **Temora** State **NSW** Postcode **2666**  
 Description of the building or part of the building Property# **Temora Hospital**  
 Temora Hospital, Nearest cross street- Gloucester. GPS 34°26'34.45"S / 147°32'36.25"E  
 This statement applies to:  Whole building  Part building.....

## 3. Description of building or part of building the subject of this statement

Stories above ground in the building **1** Stories below ground in the building **0**  
 If statement relates to part of the building, describe that part and its location  
 n/a  
 Usage of the building or part subject to this statement  
 District Hospital / Healthcare BCA Class 9a

## 4. Name & address of the building owner

Building Owner  
 NSW Health – Murrumbidgee Local Health District  
 Address for all correspondence  
 Murrumbidgee LHD Asset Management PO Box 159 Wagga Wagga NSW 2650

## 5. Fire safety measures

List of essential fire safety measures specified in the Fire Safety Schedule for the building

	Date assessed	CFSP*	Minimum standard of performance
Fire Detection & alarm system	March 2020	SH	AS1670 AS1851
System monitoring	March 2020	SH	BCA E 2.2a7
OWS	March 2020	SH	BCA E2.2a AS 1851
Exit & emergency lights	March 2020	SH	AS 2293.2
Fire resistant doors	March 2020	SH	AS1905 AS 1851
Smoke doors	March 2020	SH	BCA C 3.4
Hydrants	March 2020	SH	Ord 70 AS 1851
Fire hose reels	March 2020	SH	Ord 70 AS 1851
Fire Extinguishers & blankets	March 2020	SH	AS 2444 AS 1851
Access for emergency vehicles	March 2020	SH	BCA C 2.4
Operational & warning signs	March 2020	SH	BCA D 2.23
Path of travel	March 2020	SH	Prt 9 div7 c186 epa

## 6. Details of competent fire safety practitioners (CFSP's)

Each CFSP who endorsed a fire safety measure referred to in Section 5 of this form

Each CFSP who inspected the building in accordance with cl.175(b) of the regulation (shaded row)

Initials	Given name/s	Family name	Phone	email	Signature
SH	Stephen	Halligan	(02) 59433033	Stephen.halligan@health.nsw.gov.au	
SH	Stephen	Halligan	(02) 59433033	Stephen.halligan@health.nsw.gov.au	

## 7. Annual fire safety statement declaration

I, **Stephen Halligan, Asset Management, Fire & Security Advisor**

Being the nominee of the owner (*Murrumbidgee Local Health District*) for this purpose, certify that:

- (a) each essential fire safety measure listed above has been assessed by a competent fire safety practitioner and was found, when it was assessed, to be capable of performing:
  - (i) In the case of an essential fire safety measure applicable by virtue of a fire safety schedule, to a standard not less than that set by the schedule; or
  - (ii) In the case of an essential fire safety measure applicable otherwise than by virtue of the fire safety schedule to a standard no less than that to which the measure was originally designed and implemented; and
- (b) The building was inspected by a competent fire safety practitioner and was found, when it was inspected, to be in a condition that did not disclose any grounds for prosecution under EP&AR2000 Division 7; and
- (c) the information contained in this statement is true and accurate to the best of my knowledge and belief

<b>Stephen Halligan</b>		16-3-2020
-------------------------	--	-----------

## 8. Supplementary fire safety statement declaration

*Not applicable for Annual fire safety statements*

## 9. Owner's authorisation

NSW Health Murrumbidgee Local Health District has nominated their Fire and Security Advisor, to audit these NSW Health Facilities based upon AS4655-2005 procedures. See the attached letter of appointment being the letter of authority by the NSW Health.

## 10. Contact details of person issuing this statement


Given name	Family Name	Phone	Cellular	email
Stephen	Halligan	(02) 59433033	0477-388-846	Stephen.halligan@health.nsw.gov.au



## 11. Fire safety schedule

The Fire Safety measures in Sect.5 reflect the Fire Safety Schedule of record

	<b>Fire safety measure</b>	<b>Minimum standard of performance</b>
1	Fire Detection & alarm system	AS1670 AS1851
2	System monitoring	BCA E 2.2a7
3	OWS	BCA E2.2a AS 1851
4	Exit & emergency lights	AS 2293.2
5	Fire resistant doors	AS1905 AS 1851
6	Smoke doors	BCA C 3.4
7	Hydrants	Ord 70 AS 1851
8	Fire hose reels	Ord 70 AS 1851
9	Fire Extinguishers & blankets	AS 2444 AS 1851
10	Access for emergency vehicles	BCA C 2.4
11	Operational & warning signs	BCA D 2.23
12	Path of travel	Prt 9 div7 c186 epa



- BLOCK WALL DETAILS-NOTES**
- REINFORCED CONCRETE BLOCK WALLS SHALL COMPLY WITH THE FOLLOWING:
1. ALL PERPENDS SHALL BE FULLY FILLED WITH MORTAR (1:1:6).
  2. PROVIDE TEMPORARY PROPPING TO WALLS WHERE REQUIRED FOR STABILITY DURING CONSTRUCTION.
  3. ALL MORTAR DAGS SHALL BE REMOVED BEFORE FILLING CORES WITH GROUT. PROVIDE CLEAN OUT HOLES (OR CLEAN OUT BLOCKS) AT THE BASE OF ALL WALLS AND EACH FOUR BREAK.
  4. STARTER BARS SHALL BE ACCURATELY POSITIONED BY TEMPLATES OR SIMILAR MEANS.
  5. VERTICAL WALL BARS SHALL BE TIED TO STARTER BARS THROUGH INSPECTION OPENINGS AT THE BASE OF THE WALL AND ALSO ACCURATELY FIXED IN POSITION AT THE TOP BY AN APPROPRIATE METHOD.
  6. REINFORCEMENT SHALL BE ACCURATELY PLACED AND FIRMLY HELD IN POSITION TO A TOLERANCE OF ± 10 mm.
  7. FILL ALL CORES WITH GROUT OF  $f_c \geq 20$  MPa AND SLUMP 220, 10 mm MAXIMUM AGGREGATE SIZE.
  8. CORE GROUT IS TO BE COMPACTED TO ENSURE COMPLETE FILLING OF ALL CORES.
  9. BLOCK CHARACTERISTIC COMPRESSIVE STRENGTH  $f_{ck}$  TO BE 15 MPa MINIMUM.

The Government Architect's Office is a division of the Government Architect's Office. It is responsible for the design and construction of public buildings and infrastructure. The drawings are prepared in accordance with the relevant standards and specifications. The Government Architect's Office is not responsible for the accuracy of the information provided in this document.

NOTE: WATERPROOF THE LIFT PIT BASE AND ALL REINFORCED CONCRETE WALLS (TO GROUND FLOOR LEVEL) WITH A WATERPROOFING PRODUCT EQUAL TO 'EVERDEE CALTITE SYSTEM BY CEMENTAID' IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATION AND RECOMMENDATIONS.

NOTE: LIFT PIT BASE SLAB AND MASS CONCRETE BELOW CAN BE POURED IN ONE POUR.

STRUCTURAL / CIVIL ENGINEERING  
GOVERNMENT ARCHITECT OFFICE

DESIGNED: [Signature]  
CHECKED: [Signature]

STRUCTURAL  
GOVERNMENT ARCHITECT OFFICE

DESIGNED: [Signature]  
CHECKED: [Signature]

ARCHITECTURAL  
GOVERNMENT ARCHITECT OFFICE

DESIGNED: [Signature]  
CHECKED: [Signature]

MECHANICAL  
GOVERNMENT ARCHITECT OFFICE

DESIGNED: [Signature]  
CHECKED: [Signature]

HYDRAULIC  
GOVERNMENT ARCHITECT OFFICE

DESIGNED: [Signature]  
CHECKED: [Signature]



<b>CONSTRUCT LIFT SHAFT - TEMORA HOSPITAL</b>		1201333/2
AS SHOWN	DATE	SHEET NO
25/09/2012		S03
TENDER DOCUMENT SECTIONS AND DETAIL - SHEET 1		

Kris.D.

Industry

**NW Bland & Sons Pty Ltd**

**From:** "Peter Hughes" <Peter.Hughes@services.nsw.gov.au>  
**To:** <nwblandandsons@bigpond.com>  
**Sent:** Friday, 22 February 2013 9:42 AM  
**Subject:** Temora hospital - Structural changes  
Hi Rob

See hereunder principal design engineer concurrence with Xeros Piccolo suggested changes to the design'

Please proceed with the Xeros Piccalo changes

Peter Hughes  
Project Manager  
NSW Public Works  
Riverina Region  
M 0407 757 638

>>> Nick Harb 21/02/2013 3:21 >>>  
Hi Peter,

Based on the information provided by Xeros Piccolo Consulting Engineers, the following comments are provided:

1. The mass concrete blinding layer underneath the base slab can be deleted.
2. The thickness of the lift base slab can be reduced to a minimum of 350mm thick with local thickening of 150mm under the sump pit.
3. In theory the bond beam as per sketch provided with 4-N12 bars and N12 ties is approved.
4. Fixing/installation of the "UNISTRUT" shall be carried out in accordance with manufacturer's recommendations and details.

Regards

Nick

>>> Peter Hughes 20/02/13 14:54 >>>  
Thanks Nick

Contractor had a local structural engineer on site today and he has come up with suggestions that you will find attached for GF and subsequent 1st and 2nd floor connections

We have agreed to move the lift 350mm east this will require now infil floor panel due to the contractor having cut out the floors already

Footing pads have to be cut, this has also been considered by local engineer by casting lift base

22/02/2013

then temp propping GF until lift walls are cast that will provide adequate support for the pier pads and floor over.

Due to rock in the base of the foundation, the local engineer has deemed that there is adequate bearing on the substrate and therefore suggested that the blinding layer be deleted and the based of the pit slab be reduced to 350mm thick

Also attached on the detail is the proposed casting method of lift inserts using bond beam with legs tied to unistrut sections and connected to horizontal and vertical block wall reinforcement

Can you review and confirm your agreement with the suggested changes or otherwise

Peter Hughes  
Project Manager  
NSW Public Works  
Riverina Region  
M 0407 757 638

>>> Nick Harb 20/02/2013 2:34 >>>  
Peter,

Expose steel minimum 150mm, drill 150 deep into existing slab and epoxy in N12-300 max.

This should apply only to the ground floor slab. Details for the first and second floor slabs should remain as documented.

Regards

>>> Peter Hughes <[PETER.HUGHES@SERVICES.NSW.GOV.AU](mailto:PETER.HUGHES@SERVICES.NSW.GOV.AU)> 20/02/13 12:05 >>>  
Nick

We think we can move lift shaft which will gat away from beam.  
Reinforcement for existing slab is only bottom placed, can we drill and chem set reo bars into edge of slab instead of exposing steel in slab  
Peter Hughes

\*\*\*\*\*

This email message, including any attached files, is confidential and intended solely for the use of the individual or entity to whom it is addressed.

The Department of Finance and Services prohibits the right to publish, copy, distribute or disclose any information contained in this email, or its attachments, by any party other than the intended recipient.  
If you have received this email in error please notify the sender and delete it from your system.

No employee or agent is authorised to conclude any binding agreement on behalf of the Department of Finance and Services by email.

The views or opinions presented in this email are solely those of the author and do not necessarily represent those of the Department, except where the sender expressly, and with authority, states them to be the views of the Department of Finance and Services.


The Department of Finance and Services accepts no liability for any loss or damage arising from the use of this email and recommends that the recipient check this email and any attached files for the presence of viruses.

\*\*\*\*\*



PROJECT: TEMORA HOSPITAL	JOB NO:	DATE: 20 2 13
	DESIGNED BY: <i>PA</i>	SHEET: 1 of 1

1. BASE SLAB REDUCE TO 250mm FROM 500  
SAME REQ TO BE FOUNDED ON ROCK  
OR MASS CONCRETE ON ROCK.

2. SLAB JOIN TO LIFT WALL



3. BOND BEAM  
LIFT SUPPORT WALL



4. POUR BASE  
SLAB FIRST  
AND PROP OFF AS  
REQUIRED

KJD:NMS:D/01/01

**NOTICE TO THE APPLICANT OF DETERMINATION OF  
DEVELOPMENT CONSENT**

issued under Section 81 (1)(a) of the *Environmental Planning & Assessment Act, 1979*,

---

<b>DEVELOPMENT CONSENT No:</b>	1213/012D
Applicant:	PETER HUGHES (TEMORA & DISTRICT HOSPITAL)
Applicant's Address:	PO BOX 2129 WAGGA WAGGA NSW 2650
Land to be Developed:	LOT 2; DP 572392; 19 GLOUCESTER STREET, TEMORA
Proposed Development:	CONSTRUCT LIFT SHAFT AND INSTALL A 1500 X 2500MM LIFT CAR
BCA Building Classification:	9 (a)

---

<b>DETERMINATION DATE:</b>	<b>16<sup>TH</sup> AUGUST, 2012</b>
Determination:	Consent granted subject to the conditions described below.
Consent to operate from:	17 <sup>TH</sup> AUGUST, 2012
Consent to lapse on:	16 <sup>TH</sup> AUGUST, 2017

---

**Certification**

The work referred to in this certificate and completed in accordance with the attached, certified plans, specifications and conditions of approval (identified by the above Development Consent will comply with the requirements of the regulations referred to in Section 81 (1) (a) of the Act.

**NOTE:** This certification remains valid for the duration of the Development Consent.

---

**Details of Conditions:**

Undertake development in accordance with plans, specifications and supporting documentation lodged, except where varied in the below conditions of consent. No departure from the approved plans and specifications shall be made unless the prior approval of Council has been obtained in writing.

All aspects of this development shall comply with the Environmental Planning and Assessment Act 1979 and all relevant Acts and Regulations thereunder, together with all Council planning and development policies. In particular all construction and associated building works shall comply with the Building Code of Australia and any applicable Australian Standards thereunder.

**Conditions of Consent:**

- 1 The builder must at all times maintain on the job, a legible copy of the plans and specifications bearing the stamp and building permit of Council.
- 2 A notice bearing the lot number and the builders name and license number shall be prominently displayed at the front of the land from the time the development application is submitted to Council until the building is complete, or until the occupation certificate is issued.

**Building Code of Australia**

- 3 The proposed development has been assessed under the provisions of the Building Code of Australia as:

Class	-	9(a)
Rise in Storeys	-	3
Type of Construction	-	B

- 4 All building work must be carried out in accordance with the provisions of the Building Code of Australia and any applicable Australian Standards.

**Construction Certificates**

- 5 The construction work shall be certified under section 109R of the Environmental Planning and Assessment Act.



---

### **Long Service Levy**

- 6 For works costing more than \$25,000, a Long Service Leave Levy shall be paid. For further information please contact the Long Service Levy Payments Corporation on their helpline 131441 prior to certification of Building Works (Crown).

In order to ensure the structural adequacy of the lift shaft and the existing structures nearby, additional details in regard to the following matters shall be submitted to and approved by the Certifier prior to the issue of a Crown Building works certificate

- a. Structural drawings prepared and signed by a suitably qualified engineer certifying compliance with the relevant clauses of the BCA and Australian Standards.

### **Access For People With Disabilities**

- 7 The building work and associated lift installation must be designed and constructed to provide access and facilities for people with a disability in accordance with the Building Code of Australia. The Certifying Authority must ensure that evidence of compliance with this condition from an appropriately qualified person is provided and that the requirements are referenced in the construction drawings to be certified.

### **Fire Services/Certification**

- 8 The owner of the building shall certify to Council every year that the essential services installed in the building for the purposes of fire safety have been inspected and at the time of inspection are capable of operating to the required minimum standard.

### **General**

- 9 All excavation/demolition works involving the removal and disposal of any asbestos must only be undertaken by contractors who hold a current WorkCover Asbestos or "Demolition Licence" and a current WorkCover "Class 2" (Restricted) Asbestos Licence must be carried out in accordance with NOHSC: "Code of Practice for the Safe Removal of Asbestos".

---

### **Reasons for Conditions/Refusal**

The above conditions have been imposed in the public interest, to reduce any potential environmental impact and to ensure that the proposed development complies with the provisions of the Environmental Planning and Assessment Act, 1979 and the Regulations, any environmental planning instruments applying to the subject land and Council's Codes and Policies.

### **Right of Review**

Under Section 82A of the Environmental Planning and Assessment Act 1979, the applicant has the right to request the Council to review its determinations within 12 months of the consent being granted.

The fee payable to have Council undertake this review is set out in Section 257 of the Environmental Planning and Assessment Act Regulations 2000.

### **Right of Appeal**

Section 97 of the Environmental Planning and Assessment Act confers on the applicant who is not satisfied with the determination of the consent authority a right of appeal to the Land and Environment Court is exercisable within 12 months of receipt of this notice.

### **Applicant's Responsibilities**

Any person who contravenes this notice of determination of the abovementioned application shall be guilty of a breach of the Environmental Planning Assessment Act, 1979, and shall be liable to a monetary penalty and for a restraining order which may be imposed by the Land Environment Court.

---

**SIGNED**

on behalf of the consent authority

Signature:

Name:

KJ Dunstan  
**DIRECTOR – Environmental Services**  
**BPB Accreditation No: 1115**

Date:

20<sup>th</sup> August, 2012



**Temora Hospital  
Supply, Installation &  
Construction of  
Lift Shaft and Lift Car**

**Project Brief**

**May 2012**

TEMORA SHIRE COUNCIL  
DEVELOPMENT APPLICATION No. 1213/0120  
Approved subject to compliance with the E.P. & A.  
Act 1979 (as amended), The Temora Shire E.P.  
Building Code of Australia (NSW Provisions)  
and conditions set by Council  
17/5/2012  
Date  
Director of Health & Building  
for and on behalf of Temora Shire Council



## 1.1 General

Southern Local Health District are planning to construct and install new lift at Temora Hospital Site to replace the existing lift that is now considered beyond their economical life.

The option below will be pursued at the following site: **TEMORA DISTRICT HOSPITAL**

## 1.2 Scope of works

### Ground Floor Level

- Lift to be constructed in alcove area of GF directly under room 228 1<sup>st</sup> Floor.
- Openings constructed in walls of room 135 to allow access to the internal hallway.

### First Floor Level

- Cut and remove concrete floor to allow the construction of lift shaft.
- Fill all openings in external walls and match existing finishes.
- Fill door opening to the ensuite
- Extend opening to allow increased access to hallway.
- Remove and reposition double doors to maintain secure area.
- Remove and replace counter so that office staff are separated from the lift area.
- Install window in the external wall of room 231.
- Install doorway into ensuite room 229. This will allow Room 231 to be returned as a hospital bed from a store room.

### Second Floor

- Install lift shaft to the Second Floor.
- Install an opening for the lift in the external walls of Room 323 and 324.
- Remove internal walls as necessary between Rooms 323 and 324.
- Install new wall to suit lift opening between Room 324 and 323.

Option 1 would deliver access to all three levels of the hospital without losing any beds or services. Construction would be disruptive to the hospital operations (noise, hoardings etc).



# TEMORA DISTRICT HOSPITAL - NEW LIFT CORNER GLOUCESTER AND LOFTUS STREETS, TEMORA

## DRAWING LIST ARCHITECTURAL



LOCATION



SITE



AERIAL PHOTOGRAPH


DA01	COVER SHEET	NTS
DA02	OVERALL SITE PLAN	1:500
DA03	SITE PLAN	1:200
	ADMINISTRATION PLANS	1:100
	NEW ADDITIONS TO EXISTING SHEDS-PLANS	1:100
	ADMINISTRATION ELEVATIONS & SECTIONS	1:100
	NEW ADDITIONS TO EXISTING SHEDS-ELEVATIONS & SECTIONS	1:100

NTS
1:500
1:200
1:100
1:100
1:100
1:100


<p>1 The Government Architect's Office, a division of the Department of Finance &amp; Services (the Department) shall not be liable or responsible for any loss or damage arising out of the conversion of any electronic document, data or program to any other format or medium, or arising out of any modification or changes that occur in the handling or use of the electronic document, data or program.</p> <p>2 The recipient or user of any electronic document, data or program is solely responsible for ascertaining its accuracy and its suitability for their purposes.</p> <p>3 The Department uses virus scanning software to prevent file and system virus attacks but gives no warranty. The recipient or user is solely responsible for their own virus protection.</p>	<p><b>LEGEND</b></p> <p>AC ALL CONDUITING AF AIR CONDITIONING AG AIR-GRADE AL ALUMINUM ANGLE AM ALUMINUM AN ANGLE AO ANGLE AP AIR PORT AR AR AS AS AT AT AU AU AV AV AW AW AX AX AY AY AZ AZ BA BALL BB BALL BC BALL BD BALL BE BALL BF BALL BG BALL BH BALL BI BALL BJ BALL BK BALL BL BALL BM BALL BN BALL BO BALL BP BALL BQ BALL BR BALL BS BALL BT BALL BU BALL BV BALL BW BALL BX BALL BY BALL BZ BALL CA CABLE CB CABLE CC CABLE CD CABLE CE CABLE CF CABLE CG CABLE CH CABLE CI CABLE CJ CABLE CK CABLE CL CABLE CM CABLE CN CABLE CO CABLE CP CABLE CQ CABLE CR CABLE CS CABLE CT CABLE CU CABLE CV CABLE CW CABLE CX CABLE CY CABLE CZ CABLE DA DRAINAGE DB DRAINAGE DC DRAINAGE DD DRAINAGE DE DRAINAGE DF DRAINAGE DG DRAINAGE DH DRAINAGE DI DRAINAGE DJ DRAINAGE DK DRAINAGE DL DRAINAGE DM DRAINAGE DN DRAINAGE DO DRAINAGE DP DRAINAGE DQ DRAINAGE DR DRAINAGE DS DRAINAGE DT DRAINAGE DU DRAINAGE DV DRAINAGE DW DRAINAGE DX DRAINAGE DY DRAINAGE DZ DRAINAGE EA ELECTRICAL EB ELECTRICAL EC ELECTRICAL ED ELECTRICAL EE ELECTRICAL EF ELECTRICAL EG ELECTRICAL EH ELECTRICAL EI ELECTRICAL EJ ELECTRICAL EK ELECTRICAL EL ELECTRICAL EM ELECTRICAL EN ELECTRICAL EO ELECTRICAL EP ELECTRICAL EQ ELECTRICAL ER ELECTRICAL ES ELECTRICAL ET ELECTRICAL EU ELECTRICAL EV ELECTRICAL EW ELECTRICAL EX ELECTRICAL EY ELECTRICAL EZ ELECTRICAL FA FLOORING FB FLOORING FC FLOORING FD FLOORING FE FLOORING FF FLOORING FG FLOORING FH FLOORING FI FLOORING FJ FLOORING FK FLOORING FL FLOORING FM FLOORING FN FLOORING FO FLOORING FP FLOORING FQ FLOORING FR FLOORING FS FLOORING FT FLOORING FU FLOORING FV FLOORING FW FLOORING FX FLOORING FY FLOORING FZ FLOORING GA GARDENING GB GARDENING GC GARDENING GD GARDENING GE GARDENING GF GARDENING GG GARDENING GH GARDENING GI GARDENING GJ GARDENING GK GARDENING GL GARDENING GM GARDENING GN GARDENING GO GARDENING GP GARDENING GQ GARDENING GR GARDENING GS GARDENING GT GARDENING GU GARDENING GV GARDENING GW GARDENING GX GARDENING GY GARDENING GZ GARDENING HA HEATING HB HEATING HC HEATING HD HEATING HE HEATING HF HEATING HG HEATING HH HEATING HI HEATING HJ HEATING HK HEATING HL HEATING HM HEATING HN HEATING HO HEATING HP HEATING HQ HEATING HR HEATING HS HEATING HT HEATING HU HEATING HV HEATING HW HEATING HX HEATING HY HEATING HZ HEATING IA INSULATION IB INSULATION IC INSULATION ID INSULATION IE INSULATION IF INSULATION IG INSULATION IH INSULATION II INSULATION IJ INSULATION IK INSULATION IL INSULATION IM INSULATION IN INSULATION IO INSULATION IP INSULATION IQ INSULATION IR INSULATION IS INSULATION IT INSULATION IU INSULATION IV INSULATION IW INSULATION IX INSULATION IY INSULATION IZ INSULATION JA JOINTS JB JOINTS JC JOINTS JD JOINTS JE JOINTS JF JOINTS JG JOINTS JH JOINTS JI JOINTS JJ JOINTS JK JOINTS JL JOINTS JM JOINTS JN JOINTS JO JOINTS JP JOINTS JQ JOINTS JR JOINTS JS JOINTS JT JOINTS JU JOINTS JV JOINTS JW JOINTS JX JOINTS JY JOINTS JZ JOINTS KA KITCHEN KB KITCHEN KC KITCHEN KD KITCHEN KE KITCHEN KF KITCHEN KG KITCHEN KH KITCHEN KI KITCHEN KJ KITCHEN KK KITCHEN KL KITCHEN KM KITCHEN KN KITCHEN KO KITCHEN KP KITCHEN KQ KITCHEN KR KITCHEN KS KITCHEN KT KITCHEN KU KITCHEN KV KITCHEN KW KITCHEN KX KITCHEN KY KITCHEN KZ KITCHEN LA LANDSCAPE LB LANDSCAPE LC LANDSCAPE LD LANDSCAPE LE LANDSCAPE LF LANDSCAPE LG LANDSCAPE LH LANDSCAPE LI LANDSCAPE LJ LANDSCAPE LK LANDSCAPE LL LANDSCAPE LM LANDSCAPE LN LANDSCAPE LO LANDSCAPE LP LANDSCAPE LQ LANDSCAPE LR LANDSCAPE LS LANDSCAPE LT LANDSCAPE LU LANDSCAPE LV LANDSCAPE LW LANDSCAPE LX LANDSCAPE LY LANDSCAPE LZ LANDSCAPE MA MASONRY MB MASONRY MC MASONRY MD MASONRY ME MASONRY MF MASONRY MG MASONRY MH MASONRY MI MASONRY MJ MASONRY MK MASONRY ML MASONRY MM MASONRY MN MASONRY MO MASONRY MP MASONRY MQ MASONRY MR MASONRY MS MASONRY MT MASONRY MU MASONRY MV MASONRY MW MASONRY MX MASONRY MY MASONRY MZ MASONRY NA NAILING NB NAILING NC NAILING ND NAILING NE NAILING NF NAILING NG NAILING NH NAILING NI NAILING NJ NAILING NK NAILING NL NAILING NM NAILING NO NAILING NP NAILING NQ NAILING NR NAILING NS NAILING NT NAILING NU NAILING NV NAILING NW NAILING NX NAILING NY NAILING NZ NAILING OA OIL OB OIL OC OIL OD OIL OE OIL OF OIL OG OIL OH OIL OI OIL OJ OIL OK OIL OL OIL OM OIL ON OIL OO OIL OP OIL OQ OIL OR OIL OS OIL OT OIL OU OIL OV OIL OW OIL OX OIL OY OIL OZ OIL PA PAVEMENT PB PAVEMENT PC PAVEMENT PD PAVEMENT PE PAVEMENT PF PAVEMENT PG PAVEMENT PH PAVEMENT PI PAVEMENT PJ PAVEMENT PK PAVEMENT PL PAVEMENT PM PAVEMENT PN PAVEMENT PO PAVEMENT PP PAVEMENT PQ PAVEMENT PR PAVEMENT PS PAVEMENT PT PAVEMENT PU PAVEMENT PV PAVEMENT PW PAVEMENT PX PAVEMENT PY PAVEMENT PZ PAVEMENT QA QUANTITIES QB QUANTITIES QC QUANTITIES QD QUANTITIES QE QUANTITIES QF QUANTITIES QG QUANTITIES QH QUANTITIES QI QUANTITIES QJ QUANTITIES QK QUANTITIES QL QUANTITIES QM QUANTITIES QN QUANTITIES QO QUANTITIES QP QUANTITIES QQ QUANTITIES QR QUANTITIES QS QUANTITIES QT QUANTITIES QU QUANTITIES QV QUANTITIES QW QUANTITIES QX QUANTITIES QY QUANTITIES QZ QUANTITIES RA RAINWATER RB RAINWATER RC RAINWATER RD RAINWATER RE RAINWATER RF RAINWATER RG RAINWATER RH RAINWATER RI RAINWATER RJ RAINWATER RK RAINWATER RL RAINWATER RM RAINWATER RN RAINWATER RO RAINWATER RP RAINWATER RQ RAINWATER RR RAINWATER RS RAINWATER RT RAINWATER RU RAINWATER RV RAINWATER RW RAINWATER RX RAINWATER RY RAINWATER RZ RAINWATER SA STRUCTURE SB STRUCTURE SC STRUCTURE SD STRUCTURE SE STRUCTURE SF STRUCTURE SG STRUCTURE SH STRUCTURE SI STRUCTURE SJ STRUCTURE SK STRUCTURE SL STRUCTURE SM STRUCTURE SN STRUCTURE SO STRUCTURE SP STRUCTURE SQ STRUCTURE SR STRUCTURE SS STRUCTURE ST STRUCTURE SU STRUCTURE SV STRUCTURE SW STRUCTURE SX STRUCTURE SY STRUCTURE SZ STRUCTURE TA TILING TB TILING TC TILING TD TILING TE TILING TF TILING TG TILING TH TILING TI TILING TJ TILING TK TILING TL TILING TM TILING TN TILING TO TILING TP TILING TQ TILING TR TILING TS TILING TT TILING TU TILING TV TILING TW TILING TX TILING TY TILING TZ TILING UA UNFINISHED UB UNFINISHED UC UNFINISHED UD UNFINISHED UE UNFINISHED UF UNFINISHED UG UNFINISHED UH UNFINISHED UI UNFINISHED UJ UNFINISHED UK UNFINISHED UL UNFINISHED UM UNFINISHED UN UNFINISHED UO UNFINISHED UP UNFINISHED UQ UNFINISHED UR UNFINISHED US UNFINISHED UT UNFINISHED UU UNFINISHED UV UNFINISHED UW UNFINISHED UX UNFINISHED UY UNFINISHED UZ UNFINISHED VA VENTILATION VB VENTILATION VC VENTILATION VD VENTILATION VE VENTILATION VF VENTILATION VG VENTILATION VH VENTILATION VI VENTILATION VJ VENTILATION VK VENTILATION VL VENTILATION VM VENTILATION VN VENTILATION VO VENTILATION VP VENTILATION VQ VENTILATION VR VENTILATION VS VENTILATION VT VENTILATION VU VENTILATION VV VENTILATION VW VENTILATION VX VENTILATION VY VENTILATION VZ VENTILATION WA WATER WB WATER WC WATER WD WATER WE WATER WF WATER WG WATER WH WATER WI WATER WJ WATER WK WATER WL WATER WM WATER WN WATER WO WATER WP WATER WQ WATER WR WATER WS WATER WT WATER WU WATER WV WATER WW WATER WX WATER WY WATER WZ WATER XA EXTERIOR XB EXTERIOR XC EXTERIOR XD EXTERIOR XE EXTERIOR XF EXTERIOR XG EXTERIOR XH EXTERIOR XI EXTERIOR XJ EXTERIOR XK EXTERIOR XL EXTERIOR XM EXTERIOR XN EXTERIOR XO EXTERIOR XP EXTERIOR XQ EXTERIOR XR EXTERIOR XS EXTERIOR XT EXTERIOR XU EXTERIOR XV EXTERIOR XW EXTERIOR XX EXTERIOR XY EXTERIOR XZ EXTERIOR YA YARD YB YARD YC YARD YD YARD YE YARD YF YARD YG YARD YH YARD YI YARD YJ YARD YK YARD YL YARD YM YARD YN YARD YO YARD YP YARD YQ YARD YR YARD YS YARD YT YARD YU YARD YV YARD YW YARD YX YARD YY YARD YZ YARD ZA ZONE ZB ZONE ZC ZONE ZD ZONE ZE ZONE ZF ZONE ZG ZONE ZH ZONE ZI ZONE ZJ ZONE ZK ZONE ZL ZONE ZM ZONE ZN ZONE ZO ZONE ZP ZONE ZQ ZONE ZR ZONE ZS ZONE ZT ZONE ZU ZONE ZV ZONE ZW ZONE ZX ZONE ZY ZONE ZZ ZONE</p>	<p>REVISION</p> <table border="1"> <thead> <tr> <th>NO.</th> <th>DATE</th> <th>COMMENT</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	NO.	DATE	COMMENT																<p>STRUCTURAL GOVERNMENT ARCHITECTS' OFFICE T 8372 8200 F 8372 8209</p> <p>ELECTRICAL GOVERNMENT ARCHITECTS' OFFICE T 8372 8200 F 8372 8209</p> <p>MECHANICAL GOVERNMENT ARCHITECTS' OFFICE T 8372 8200 F 8372 8209</p> <p>HYDRAULIC GOVERNMENT ARCHITECTS' OFFICE T 8372 8200 F 8372 8209</p>	<p>ARCHITECTURAL GOVERNMENT ARCHITECTS' OFFICE T 8372 8411 F 8372 8398</p> <p>LANDSCAPE GOVERNMENT ARCHITECTS' OFFICE T 8372 8408 F 8372 8404</p> <p>QUANTITY SURVEYOR GOVERNMENT ARCHITECTS' OFFICE T 8372 8311 F 8372 8444</p> <p>PROJECT MANAGEMENT PROJECT MANAGEMENT GROUP T 8372 8558 F 8372 8556</p>	<p><b>NSW</b> GOVERNMENT</p> <p>Public Works Government Architects' Office</p> <p>PETER POLLET NEW Government Architect New Government Architect Level 11, Market Street, 224 Market Place Sydney NSW 2010 Australia Phone: (02) 9250 4477</p> <p>a division of the Department of Finance &amp; Services MICHAEL COULTS-TROTTER Director General</p>	<p>PLAN NO SCALE DESIGNED DRAWN</p> <p>1:100 @ A1 10/07/2012</p>	<p>CONTRACT NUMBER SHEET NO DATE REVISION</p> <p>DA01</p>
	NO.	DATE	COMMENT																						

PRELIM  
10/07/2012


10/07/2012 3:51:19 PM G:\Projects\NSW\TH\LEET...TEMORA\_HOSPITAL\TEMPORA\_HOSPITAL\_NEW\_LIFT\_ARCHITECTURAL\DA01-COVER.SHP




1 PART GROUND FLOOR DEMOLITION PLAN




4 PART GROUND FLOOR PLAN




2 PART FIRST FLOOR DEMOLITION PLAN



5 PART FIRST FLOOR PLAN



3 PART SECOND FLOOR DEMOLITION PLAN



6 PART SECOND FLOOR PLAN

**LEGEND**

- BRICKWORK TO MATCH EXISTING
- STUD WALL UNLESS NOTED OTHERWISE
- EXISTING WALLS TO REMAIN
- EXISTING ROOMS NOT PART OF SCOPE OF WORKS
- EXISTING WALL TO BE DEMOLISHED
- EXISTING DOOR TO BE DEMOLISHED
- NEW DOOR
- EXISTING WINDOW TO BE DEMOLISHED
- WINDOW NUMBER ROOM NUMBER
- DOOR NUMBER ROOM NUMBER
- CEILING FINISH FLOOR FINISH
- WALL TYPE INDICATOR
- DETAIL NUMBER DRAWING NUMBER
- RL 10.157 EXISTING RECEPTION LEVEL

LEGEND

SYMBOL	DESCRIPTION
AC	ACROBATIC ROOFING
AL	ALUMINUM
AS	ASBESTOS
AV	AUTOMATIC VALVE
B	BRAZED
BS	BRAZED STEEL
CD	CORROSION RESISTANT
CE	CERAMIC
CF	CONCRETE FINISH
CG	CONCRETE GIRDER
CH	CHAR
CI	CONCRETE IN PLACE
CM	CONCRETE MASS
CMU	CONCRETE MASONRY UNIT
CN	CONCRETE
CS	CONCRETE STEEL
CT	CONCRETE TIE
CU	CUPRO-NICKEL
D	DRAIN
DB	DRAIN BOWL
DC	DRAIN CONNECTION
DD	DRILL
DE	DECEASED
DF	DRAIN FLANGE
DG	DRAIN GARD
DH	DRAIN HOLE
DI	DRAIN INSULATION
DJ	DRAIN JUNCTION
DK	DRAIN KICK OUT
DL	DRAIN LEAK
DM	DRAIN MANHOLE
DN	DRAIN NOISE
DO	DRAIN OVERFLOW
DP	DRAIN PIPING
DQ	DRAIN QUANTITY
DR	DRAIN ROD
DS	DRAIN SINK
DT	DRAIN TEST
DU	DRAIN UPLIFT
DV	DRAIN VALVE
DW	DRAIN WELDER
DX	DRAIN EXTENSION
DY	DRAIN YIELD
DZ	DRAIN ZONE
E	ELECTRICAL
EA	ELECTRICAL AIR
EB	ELECTRICAL BATTERY
EC	ELECTRICAL CABLE
ED	ELECTRICAL DUCT
EE	ELECTRICAL EQUIPMENT
EF	ELECTRICAL FEEDER
EG	ELECTRICAL GROUND
EH	ELECTRICAL HOUSING
EI	ELECTRICAL IDENTIFICATION
EJ	ELECTRICAL JUNCTION
EK	ELECTRICAL KICK OUT
EL	ELECTRICAL LEAD
EM	ELECTRICAL MOUNTING
EN	ELECTRICAL NOTICE
EO	ELECTRICAL OVERCURRENT
EP	ELECTRICAL PROTECTIVE
EQ	ELECTRICAL QUANTITY
ER	ELECTRICAL RACEWAY
ES	ELECTRICAL SIGN
ET	ELECTRICAL TEST
EU	ELECTRICAL UNIT
EV	ELECTRICAL VALVE
EW	ELECTRICAL WELDER
EX	ELECTRICAL EXTENSION
EY	ELECTRICAL YIELD
EZ	ELECTRICAL ZONE
F	FLOOR FINISH
FA	FLOOR AREA
FB	FLOOR BEARING
FC	FLOOR CONNECTION
FD	FLOOR DETAIL
FE	FLOOR EQUIPMENT
FF	FLOOR FINISH
FG	FLOOR GIRDER
FH	FLOOR HOLE
FI	FLOOR IDENTIFICATION
FJ	FLOOR JUNCTION
FK	FLOOR KICK OUT
FL	FLOOR LEAD
FM	FLOOR MOUNTING
FN	FLOOR NOTICE
FO	FLOOR OVERCURRENT
FP	FLOOR PROTECTIVE
FQ	FLOOR QUANTITY
FR	FLOOR RACEWAY
FS	FLOOR SIGN
FT	FLOOR TEST
FU	FLOOR UNIT
FV	FLOOR VALVE
FW	FLOOR WELDER
FX	FLOOR EXTENSION
FY	FLOOR YIELD
FZ	FLOOR ZONE
G	GIRDER
GA	GIRDER AREA
GB	GIRDER BEARING
GC	GIRDER CONNECTION
GD	GIRDER DETAIL
GE	GIRDER EQUIPMENT
GF	GIRDER FINISH
GG	GIRDER GIRDER
GH	GIRDER HOLE
GI	GIRDER IDENTIFICATION
GJ	GIRDER JUNCTION
GK	GIRDER KICK OUT
GL	GIRDER LEAD
GM	GIRDER MOUNTING
GN	GIRDER NOTICE
GO	GIRDER OVERCURRENT
GP	GIRDER PROTECTIVE
GQ	GIRDER QUANTITY
GR	GIRDER RACEWAY
GS	GIRDER SIGN
GT	GIRDER TEST
GU	GIRDER UNIT
GV	GIRDER VALVE
GW	GIRDER WELDER
GX	GIRDER EXTENSION
GY	GIRDER YIELD
GZ	GIRDER ZONE
H	HANDICAP
HA	HANDICAP AREA
HB	HANDICAP BEARING
HC	HANDICAP CONNECTION
HD	HANDICAP DETAIL
HE	HANDICAP EQUIPMENT
HF	HANDICAP FINISH
HG	HANDICAP GIRDER
HH	HANDICAP HOLE
HI	HANDICAP IDENTIFICATION
HJ	HANDICAP JUNCTION
HK	HANDICAP KICK OUT
HL	HANDICAP LEAD
HM	HANDICAP MOUNTING
HN	HANDICAP NOTICE
HO	HANDICAP OVERCURRENT
HP	HANDICAP PROTECTIVE
HQ	HANDICAP QUANTITY
HR	HANDICAP RACEWAY
HS	HANDICAP SIGN
HT	HANDICAP TEST
HU	HANDICAP UNIT
HV	HANDICAP VALVE
HW	HANDICAP WELDER
HX	HANDICAP EXTENSION
HY	HANDICAP YIELD
HZ	HANDICAP ZONE

1 The Government Architect's Office, a division of the Department of Finance & Services (the Department) shall not be liable or responsible for any loss or damage arising out of the conversion of any electronic document, data or program to any other format or medium, or arising out of any modification or changes that occur in the handling or use of the electronic document, data or program.

2 The recipient or user of any electronic document, data or program is solely responsible for ascertaining its accuracy and its suitability for their purposes.

3 The Department uses virus scanning software to prevent file and system virus attacks but gives no warranty. The recipient or user is solely responsible for their own virus protection.

REVISION

ISS	DATE	COMMENT


STRUCTURAL GOVERNMENT ARCHITECTS OFFICE T 9372 8200 F 9372 9399	ARCHITECTURAL GOVERNMENT ARCHITECTS OFFICE T 9372 8411 F 9372 8339
ELECTRICAL GOVERNMENT ARCHITECTS OFFICE T 9372 8233 F 9372 9133	LANDSCAPE GOVERNMENT ARCHITECTS OFFICE T 9372 8428 F 9372 8434
MECHANICAL GOVERNMENT ARCHITECTS OFFICE T 9372 8233 F 9372 9133	QUANTITY SURVEYOR GOVERNMENT ARCHITECTS OFFICE T 9372 8311 F 9372 8444
HYDRAULIC GOVERNMENT ARCHITECTS OFFICE T 9372 8233 F 9372 9133	PROJECT MANAGEMENT PROJECT MANAGEMENT GROUP T 9372 8558 F 9372 8566

**NSW GOVERNMENT**  
**Public Works**  
Government Architect's Office

**TEMORA HOSPITAL**  
- NEW LIFT  
  
**DEMOLITION AND**  
**FLOOR PLANS**

PLAN NO	CONTRACT NUMBER
SCALE	SHEET NO
DESIGNED	DA02
DATE	
10/07/2012	
DRAWN	

### 3.0 LIFT SERVICE SCOPE



#### 1 GENERAL

##### 1.1 SCOPE

Supply, install, test and commission MRL (Machine Room Less) passenger lifts with electric traction drive specified in this section and to the relevant provisions of AS 1735 Part 2 (2001) or Part 1, and Part 12 (1999). The installation shall also comply with the Building Code of Australia and the Occupational Health & Safety Regulations 2001.

The MRL lift must have the drive unit installed in the lift well and accessible via a landing lobby only. The controller must be installed adjacent to a landing entrance. No access on the side or rear of the well is available.

All fittings and fixtures to be supplied and installed complete to manufacturer's current printed instructions.

Include all costs to securely store the lift equipment off site and on site prior to installation. Include all transport and moving costs to deliver the equipment to its final installed position.

Contractor to provide temporary security fencing to secure the lift equipment materials and lift installation work site areas.

Contractor to provide all site accommodation, toilet facilities, secure tool storage, crib room etc required by site personnel under this contract.

Contractor to provide weather protection on site to the lift equipment materials and installation work areas for duration of materials on site and installation process.

Contractor to provide temporary protection of finishes to lift car up to time of handover.

Contractor to remove and dispose of all debris, rubbish, packing material, waste etc associated with this contract from the site before handover.

Provide protection to lift well openings to prevent persons from falls into the lift well. Protection to be complete with a door and lock to each level as required by the program. Provide scaffolding in the well for lift installation work. Provide overhead protection for persons working in the lift well.

Provide 4 weeks prior notice to Authorised Person indicating the date of proposed shipment of the lift equipment to the Hospital site. Provide 48 hours prior notice to confirm the delivery-taking place.

##### 1.2 DESIGN AND INSTALLATION CERTIFICATION

Ensure that the design of the proposed equipment has been registered with NSW WorkCover and verified code compliance by a competent person. Provide supporting documents.

Before Practical Completion the contractor shall appoint a competent person to carry out tests on the equipment and safety devices. The Authorised Person may attend the tests. Provide test results and a certificate to confirm that the installation has been tested, complies with the Lift Code and is "safe to operate." Submit a lift registration form with relevant section completed.

Provide a copy of the fire test certificate for the landing doors.



---

### 1.3 SHOP DRAWINGS AND WORK PROGRAM

Within four weeks of Letter of Acceptance, supply shop drawings showing the following details:

- Loadings in lift well and pit.
- Car interior finishes;
- Car and landing control panels, indicators and signs.

### 1.4 INSPECTIONS

NOTICE: Give at least five working days notice so that the Authorised Person may attend the following:

- Safety Tests by the contractor's competent person.
- Supervisory inspection at the end of defect liability period.

Insufficient notice: If the Authorised Person is unable to attend a test due to insufficient notice, the test may be repeated at the Contractor's cost.

### 1.5 LIFT PERFORMANCE

PRODUCTION ITEMS: Manufactured items of equipment shall be new, of proven design, quiet in operation, in current production, manufactured by approved suppliers and type tests in accordance with AS1735.

CAPACITY: The drive motor shall be capable of carrying the rated load at the rated speed and at the specified starts per hour without overheating or malfunction.

QUALITY OF RIDE: The quality of ride shall be compatible with the passenger's comfort during acceleration and deceleration. The horizontal and vertical vibration shall be within the specified limits.

LEVELLING: The levelling of car shall be within the specified limit.

NOISE: The car shall be made of solid material construction and free of vibration. Isolation pads shall be provided for lift car platform to eliminate vibration in the car.

### 1.6 MATERIALS AND WORKMANSHIP

STAINLESS STEEL: Sheet and plate stainless steel 304 to AS1449/303 brushed satin finish.

Lifts installed near coastal region, nominated in tender schedule shall have stainless steel faceplates of Marine grade 316.

FURNITURE STEEL SHEET: TO AS1595. Surface finish: Matt for painting

PAINTING: All metal surfaces other than stainless steel shall have a protective coat of paint or grease. All damage to the prime coat shall be made good. Paint metal surfaces in lift well and pit. The painting shall include guide rail brackets and pit support structure.

LIFT PIT: Do not cut holes for fixing or other purposes in lift pit walls or floor without prior approval.

ELECTRICAL WIRINGS: All wirings must be mechanical protection by cable ducts, rigid PVC conduits or other approved protections. Flexible conduits may be used for final connection to the equipment. Refer to Clause 3.10, AS3000 Wiring Rules.

---

## **2 LIFT WELL AND PIT**

### **2.1 WELL PROTECTION AND SCAFFOLDING**

Provide protection to the lift well openings to prevent persons from falling into the lift well. Install well protection fencing complete with a door and lock at each level as soon as it is required.

Provide scaffolding for lift installation work and overhead protection for persons working in the lift well.

### **2.2 GUIDE RAILS**

Guide rails shall be T-section or other shapes approved by the statutory authorities. The rail shall have a groove and tongue at each end to permit smooth joint. Sections not specifically designed and manufactured for lift installations are not acceptable.

Provide bond blocks or inserts for guide rail brackets. Use bolts on sections of well which has been constructed without bond blocks or inserts.

### **2.3 PIT ACCESS AND CLEARANCE**

Provide a pit access ladder permanently installed inside the liftwell and complying with Clause 10.4 of AS1732.2 (2001). Movable ladder is not acceptable. Two pit stop switches shall be provided, one near the top and another at the bottom of the pit ladder.

Identify the safe crouching area in the pit and mark in yellow the outline and the words "PERSON CLEARANCE".

A sump is required and will be provided in the pit. Supply a galvanised chequer plate to cover the sump.

Provide an alarm system or other communication means in the pit and at the car top to control the confined space hazard.

---

## **3 DRIVE AND CONTROL SYSTEMS**

### **3.1 DRIVE UNIT**

**DRIVE UNIT:** The drive unit shall be located in the lift well. The motor shall be a variable voltage variable frequency drive or other approved drive.

**ACCESS FROM LIFT LOBBY ONLY:** The drive unit must be installed in the lift well with the access to the unit from the landing lobby only. No access door on the side or rear of the lift well is allowed

### **3.2 CONTROL SYSTEM**

The controller must be installed adjacent to a landing entrance and substantially flush with the lift well. In any case the thickness of the controller must not be greater than 250 mm from the landing door panel.

**COLLECTIVE OPERATION** For single lift serving two landings Provide floor buttons in the lift car and at each landing. A car or landing call when registered, shall remain registered until answered

**DIRECTIONAL COLLECTIVE OPERATION:** (For single lift serving more than two landings) Provide a single button at the terminal landings and 'up' and 'down' buttons at intermediate landings to allow registration for the direction of intended travel. The calls are answered by the lift travels in the same direction. A car or landing call shall remain registered until answered.

ELECTROMAGNETIC INTERFERENCE: The controller and other lift equipment shall not cause interference with radio, electronic, computer, medical or the like equipment. If necessary provide filters or interference suppressors.

### **3.3 LEVELLING**

ACCURACY LIMITS: The specified limit is the distance above or below the landing level within which the car is required to stop under any load condition from 0% up to 100% of rated load.

### **3.4 ASCENDING CAR OVERSPEED PROTECTION**

Provide the ascending car over speed protection as required by the Lift Code.

### **3.5 EXCLUSIVE SERVICE**

Provide on the car control panel a key switch to allow the operation of the lift from the car control panel only.

### **3.6 FIRE SERVICE**

Provide the fire service control in the lift car with a recall key switch at the main landing, in accordance with Lift Code AS1735.

### **3.7 OUT-OF-SERVICE KEY SWITCH**

Provide a key switch at the main landing to disable all landing and car calls and put the lift out of service

### **3.8 LANDING SECURITY CONTROL**

In addition to the Out-of-Service key switch, provide a key switch at each landing to permit any landing to be keyed ON or OFF. When the key switch at a landing is keyed OFF the landing button at that floor shall be inoperative. However, car call for that floor shall remain operative.

The key shall be removable in both ON and OFF positions.

The Out of Service key and the landing control key shall have the same key combination.

### **3.9 TRIP METER**

Provide a trip meter on the controller to register the number of motor starts of each lift. The trip meter shall have a minimum of six digits and cannot be reset.

---

## **4 ELECTRICAL AND TELEPHONE**

### **4.1 CIRCUIT BREAKERS AND PROTECTION**

REQUIREMENT: Provide all circuit breakers required for the operation of the lift system. Connect the sub mains to the lift circuit breaker.

Provide electronic protections for the drive unit, including:

- overload current.
- phase loss.
- phase reversal.
- stalled drive.
- Over-travel timer.

Lift circuit breaker shall be lockable in the OFF position. The locking device shall be installed on the lift switchboard. Portable locks are not acceptable.

RCD: Provide residual current devices for all lighting and power circuits.

---

Leeton and Temora Hospital Install Lift Car

---

## **4.2 TELEPHONE**

Provide a hand-free, self-dialling phone in the lift car. The phone shall be operated by a phone/Alarm button on the car control panel and shall automatically acknowledge the lift number and building location when activated.

The company's remote monitoring system may be provided in lieu of the hand-free self-dialling phone. At the end of operational maintenance period the contractor shall remove the remote monitoring system and replace it with the self-dialling phone detailed above.

**APPLICATION:** Apply and pay the application fee to the relevant authority for a separate exchange line for each lift. The Authorised Person shall provide the name and address for billing purpose, to be included in the application form. Builder will provide an exchange line to a final distribution frame adjacent to the controller at the lift lobby.

## **4.3 WIRING DIAGRAMS**

One complete set of up-to-date schematic wiring diagrams shall be provided in the control panel. The diagrams shall be new and unmarked at the time of practical completion and shall be sealed in clear plastic sheets.

---

## **5 LANDING AND CAR DOORS**

### **5.1 LANDING AND CAR DOORS**

The doors shall be horizontal sliding and power operated.

Provide landing door unlocking device on all landing doors.

**FIRE TESTING:** The landing doors shall have one hour fire rating. Provide a certificate confirming that the doors and frames have been satisfactorily tested to AS 1735 Part 2 and Part 11. Affix a metal tag with the door manufacturer and the rating on each door. Provide the Authorised Person with a copy of the test certificate.

**SIGHT GUARDS:** Provide sight guards on the leading edges of landing doors to conceal the wiring and clearance space between car and landing doors.

### **5.2 DOOR PROTECTION UNIT**

**PASSENGER-PROTECTION DEVICE:** Provide an infrared protection unit at the car door entrance. The protection shall be consists of series of beams to detect any motion between 50 mm and 1,600 mm from the sill level. When the beams are interrupted, the unit shall cause the doors to remain in the open position or reverse to the fully open position. The doors shall commence to close after the expiry of the preset period.

**DELAY CLOSING:** Where the closing of the doors is delayed for longer than a preset period, the doors shall be closed with a kinetic energy not exceeds 3.4 J and an audible alarm sounded in the car. The time for the delay shall be adjustable.

---

## **6 CONTROL BUTTONS AND INFORMATION SYSTEM**

### **6.1 FACEPLATES, BOXES AND FIXING**

**FACEPLATES:** Faceplates shall be not less than 2.5 mm thick reinforced where necessary against distortion.

**BOXES:** House buttons, indicators and key switches in pressed-steel boxes recessed in the car and landing so that the faceplates are flushed with the surfaces. Boxes containing lamps shall form light tight compartments.

---

**FIXING:** Raised countersunk crosshead screws finished to match the faceplate. Clip-on type fixings are not acceptable.

**ENGRAVING:** Floor designations, labels, and sign on the faceplates, buttons shall be machine-engraved and colour filled to standard colours.

**REQUIREMENT:** Provide the landing and car buttons, indicators and key switches required for lift operation.

## **6.2 CAR CONTROL PANELS**

**REQUIREMENT:** Provide two control panels, main and secondary control panels. Both panels shall contain the following items:

- floor buttons;
- alarm/phone button;
- door open and door close buttons; and
- telephone operation instruction.

**KEY SWITCHES:** Provide key switches for the following functions:

- Car light;
- Ventilation fan;
- Fire service; and
- Exclusive Service.

The key switches shall be located on the main control panel. The car light and ventilation fan may be automatically controlled and switched off when the lift is not in use after a certain period. The period shall be adjustable between 0 to 30 minutes.

Provide a load notice with the owner's name, building address, the lift company's emergency phone number and other information required.

## **CAR INDICATORS**

Provide an indicator in the car showing the car position and direction of travel.

## **6.3 LANDING CONTROL PANELS AND INDICATORS**

Provide at each landing, self-illuminating call buttons, key switches, a car position and direction of travel indicator.

## **6.4 ALARM BELL**

**REQUIREMENT:** Mount a bell above or below the car.

**Power source:** the bell shall of a diameter of not less than 100 mm and be supplied from the emergency power source.

## **6.5 EMERGENCY LIGHTING**

**REQUIREMENT:** Provide in each lift a fluorescent lighting fitting capable of operating as an emergency light. The emergency unit shall operate upon failure of the power supply or when car light switch is turned to the test position. The emergency light shall be positioned over the main car control panel. The emergency supply shall have a minimum capacity of four hours continuous operation.

---

## 6.6 KEY IDENTIFICATION

Provide two keys for each key combination. To each key attach a metal ring and label engraved the building name, lift number and the purpose of the key.

---

## 7 LIFT CAR

### 7.1 CAR CONSTRUCTION

The car shall be made of steel frame and enclosure with steel or other approved materials. Provide isolation pads for the car platform to minimise vibration in the lift car.

### 7.2 CAR FINISHES

**REQUIREMENT:** Materials for car floor, floor coverings, and wall and ceiling linings shall comply with the combustibility characteristics in Clause 23.17.3 of AS1735.2.

**GLAZING:** When used in lift cars, glazing shall comply with Appendix H of AS1735.2 and the relevant requirements of AS1288 and AS 2208.

If not specified in the Schedule the colours and finishes shall be determined by the Authorised Person.

### 7.3 CAR EQUIPMENT

**POWER OUTLET:** Provide a power outlet (GPO) in the lift car. The GPO shall be protected by a residual current device.

Provide a ceiling mounted fan with a minimum flow of 60 litres, approximate 1,000 rpm. The fan shall be controlled by a key switch on the car panel.

---

## 8 FACILITIES FOR DISABILITIES

### 8.1 GENERAL

The design, construction and all equipment and components shall comply with the Lift Code AS1735 Part 12 (1999) Facilities for Persons with Disabilities.

### 8.2 FACILITIES FOR DISABILITIES

**REQUIREMENT:** The facilities for disabilities shall include, but not limited to the followings:

- Two car control panels.
- A handrail in car.
- Tactile symbols for all car and landing buttons.
- Design and position of buttons and indicators.
- Visible and audible indication in the car and on the landings.

### 8.3 INDICATORS IN CAR

In the lift car provide visual and audio indication for the car position and direction of travel. The size of the visual floor designation shall be at least 50 mm high and installed at 1800 mm above the floor.

**Audio Indication:** For lifts serving up to 3 floors a tone shall sound when the lift passes and arrives at a floor.

For lifts serving more than 3 floors the indication shall be in a form of floor announcement. The sound volume shall be adjustable.

---

## 8.4 AUDIBLE CAR BUTTONS

For lift serves more than two landings, the floor buttons in the lift car shall be provided with a short tone and illumination when the button is registered. The tone may be omitted if the operation of the button can be detected by touch.

## 8.5 INDICATORS AT LANDINGS

Provide visual and audio indication on the car position and direction of travel at all landings. The size of the visual floor designation shall be at least 50 mm high and installed at 1800 mm above the floor.

Audio indication: One tone shall sound to indicate the lift is travelling in the up direction and two tones indicate the lift is travelling in the down direction. The sound volume shall be adjustable.

## 8.6 HANDRAIL

Provide a handrail on the sidewall adjacent to the side control panel. The handrail shall extend from the front to the back of the lift car.

---

# 9 TESTING

## 9.1 GENERAL

TESTS: Carry out tests to confirm that the installation complies with all the requirements in the Lift Code AS1735 and the lift is safe to operate.

EQUIPMENT: Provide all equipment, tools, test weights and materials necessary for the carrying out of the required tests.

## 9.2 SAFETY TESTS

ACCEPTANCE TESTS: Test the effectiveness and safe operation of safety devices, including but not limited to the following:

- governor and safety gear;
- machine brake;
- door locks and safety circuits

BRAKE TESTS: Test that the brake can hold the rated load at the rated speed. Further test that the brake can hold the overload conditions at the test speed specified in the Lift Code AS1735.

BALANCE TEST Check the car balancing complies with the Lift Code AS1735.

PROTECTION AND TIMING DEVICES: Test the correct operation settings of protection and timing devices.

CLEARANCES: Check the top and bottoms clearances of the car and counterweight.

INSULATION RESISTANCE OF WIRING AND EQUIPMENT: Carry out tests as required under AS3000.

## 9.3 LOAD TESTS

REQUIREMENT: Carry out the following load tests:

PROCEDURE: Run the lift continuously for at least 30 minutes at the rated speed, and at full load.

Doors: Car doors and all landing doors shall operate correctly and at the required speed;

---

**STOPPING:** Operate the doors to open and close normally at each stop.

**MALFUNCTION:** Stop the test as soon as a malfunction is detected, rectify it, and restart the test. Do not count "down" time as part of the test period.

#### **9.4 SPEED AND LEVELLING TESTS**

**REQUIREMENT:** Demonstrate that the lift, when run before and after the load tests, meets the following requirements both with rated load and with no load:

**Rated Speed:** The lift shall achieve the specified rated speed in both directions.

**Floor-to-floor:** The time taken by the car to travel between landings, measured in either direction from the start of movement to stop, shall be within +/- 5% of the specified time.

**Levelling:** Levelling at each landing shall be within the limit specified.

**Quality of car ride:** Starting and stopping of the lift shall be smooth and complies with the specified limit.

#### **9.5 CAR CONTROL SYSTEM TESTS**

**REQUIREMENT:** Demonstrate by a comprehensive series of tests that the car control system complies with the specification. The tests shall include, but not limited to, testing all car buttons, key switches, alarm, indicators, timing devices

---

### **10 MAINTENANCE**

#### **10.1 OPERATIONAL MAINTENANCE**

**OPERATIONAL MAINTENANCE PERIOD:** The Operational Maintenance Periods shall be one year.

**REQUIREMENT:** During the operational maintenance period provide qualified and experienced personnel to perform the maintenance required for safe and reliable operation, including the following:

- **Regular maintenance:** Make service visits at least one per month. Service shall be carried out more frequently if necessary.
- **Breakdowns:** Attend lift breakdowns or unsatisfactory operation at any time of the day or night to restore the lift to proper working order.
- **Defects:** Make good faults or damage caused by defects in the installation and replace defective part or parts showing signs of wear.
- **Lift pit:** Clean lift pit and all associated equipment at regular interval. Lift pit shall be clean of debris at a quarterly interval.
- **Materials:** Supply all materials including parts, lubricants and cleaning materials.
- **Cleaning:** Leave clean and tidy after each visit the areas and equipment in and on which maintenance work was performed.

**RECORD:** Provide a record of each visit including the date and time, work carried out, name of the service operator and any relevant information.

#### **10.2 MAINTENANCE MANUAL**

**REQUIREMENT:** At practical completion provide two copies of operation manual which shall include basic lift parameters, drive and controller system, function of each key switches, emergency procedures and other information.



---

### 10.3 SAFE TO OPERATE CERTIFICATION

Before the end of the operational maintenance period, carry out a safety inspection to test the safety and protective devices. Rectify any defective parts or components and certify if the lift is safe to operate.

---

## 11 LIFT SCHEDULES

### 11.1 STANDARD PARAMETERS FOR ALL LIFTS

TYPE OF DRIVE:	Variable voltage variable frequency
LOCATION OF DRIVE UNIT:	In lift well (Machine Room Less)
ACCESS TO DRIVE:	From lift entrance only
DUTY:	180 starts/hour
CONTRACT SPEED:	1.0 m/s
CONTRACT LOAD:	2000 kg (26 persons)
WELL SIZE:	Suited to minimum car dimensions
OVERHEAD:	3,800 mm
PIT :	1,750 mm
CLEAR CAR SIZE [MINIMUM]:	1,500mm wide x 2,500mm deep
FLOOR LEVELLING ACCURACY:	+/- 5 mm
RIDE QUALITY (peak to peak):	< 20 milli(g) (0.2 m/s <sup>2</sup> ) in X, Y & Z
CONTROL:	Directional collective operation Single button (for 2 landings)
CONTROL ON CAR PANEL:	Exclusive Service Fire Service Car light key switch Fan key switch
CONTROL AT LANDING:	Fire Service at main landing Out of Service at main landing Landing security control
DOOR OPERATION	
DOOR TYPE:	2-panel centre-opening power operated
DOOR OPENING:	1300 mm wide x 2,300 mm high
DOOR PROTECT UNIT	Infra-red type

### CONTROL PANEL

NO OF CAR CONTROL PANELS:	Two
CAR & LANDING BUTTONS:	Stainless steel vandal resistance type
BUTTON & INDICATOR FACEPLATES:	Stainless steel satin finish

---

Leeton and Temora Hospital Install Lift Car

---

**DOORS AND FRAMES FINISHES**

LANDING DOOR:	Stainless steel satin finish
LANDING DOOR FRAME:	Stainless steel satin finish
CAR DOOR:	Stainless steel satin finish
SIGHT GUARDS:	Stainless steel satin finish
<b>CAR INTERIORS</b>	
FRONT WALL	Stainless steel satin finish
SIDE & REAR WALLS:	Stainless steel Rigidised metal similar to 'Rimex", pattern to be selected
CEILING:	White laminate with fluorescent light
FLOOR:	Vinyl sheet, colour to be selected
SKIRTING:	Stainless steel
HANDRAIL:	Stainless steel on side wall
LIGHTING ON CAR PANELS:	> 200 lux

**INDICATIVE FLOOR LEVELS EACH SITE**

LEETON HOSPITAL	Ground Floor Level RL 100.00 1 <sup>st</sup> Floor Level RL 103.86 2 <sup>nd</sup> Floor Level RL 107.69
TEMORA HOSPITAL	Ground Floor Level RL 100.00 1 <sup>st</sup> Floor Level RL 103.14 2 <sup>nd</sup> Floor Level RL 106.39

---

**11.2 VARIABLE PARAMETERS [NOT USED]**

**11.3 OPERATIONAL MAINTENANCE SCHEDULE**

OPERATIONAL MAINTENANCE SERVICE: 52 weeks

MINIMUM SERVICE FREQUENCY: One per month

CALLOUT RESPONSE TIMES:

- when passenger trapped within 30 minutes
- Other breakdowns Two hours



STATEMENT OF ENVIRONMENTAL EFFECTS

# TEMORA DISTRICT HOSPITAL LIFT REPLACEMENT



JULY 2012

PREPARED FOR MURRUMBIDGEE LOCAL HEALTH DISTRICT



**Public Works**  
Government Architect's Office

<b>TEMORA SHIRE COUNCIL</b>	
DEVELOPMENT APPLICATION No. 1213/0120	
Approved subject to compliance with the E.P. & A. Act 1979 (as amended), The Temora Shire L.E.P., Building Code of Australia (NSW Provisions) and conditions set by Council	
17/8/2012	
Date	Director of Health & Building
<small>For and on behalf of Temora Shire Council</small>	

## STATEMENT OF ENVIRONMENTAL EFFECTS

### Forward

This Statement of Environmental Effects (SEE) assesses the potential impacts that may arise from the proposal to undertake provision of a new passenger lift at Temora Hospital. The SEE has been prepared in accordance with the relevant provisions of the Environmental Planning and Assessment Act 1979 and Environmental Planning and Assessment Regulation 2000.

### Property Address

TEMORA & DISTRICT HOSPITAL  
119 Gloucester Street  
TEMORA NSW 2666

### Contact Details

#### Client

Murrumbidgee Local Health District

#### Project Manager

Project Management (Wagga Office)  
NSW Public Works

Peter Hughes  
T 02 6938 2877  
M 0407 757 638  
[peter.hughes@services.nsw.gov.au](mailto:peter.hughes@services.nsw.gov.au)

#### Project Architect

Government Architect's Office  
NSW Public Works

Philip Rose/Robert Isles  
T 02 9372 8380  
[Phil.Rose@services.nsw.gov.au](mailto:Phil.Rose@services.nsw.gov.au)

G:\Projects\HEALTH\LEET\_TEM\_HOSP\_LIFT\4\_da\arch\TEMORA SEE\TEMORA Hospital SEE 120625.docx

TEMORA DISTRICT HOSPITAL – NEW LIFT

**Table of Contents**

<b>1.0</b>	<b>INTRODUCTION</b>	Page 3
<b>2.0</b>	<b>LOCATION DESCRIPTION</b>	Page 4
<b>3.0</b>	<b>PROPOSED DEVELOPMENT</b>	Page 6
<b>4.0</b>	<b>ENVIRONMENTAL ASSESSMENT</b>	Page 7
<b>5.0</b>	<b>SAFEGUARDS DURING CONSTRUCTION</b>	Page 9
<b>6.0</b>	<b>CONCLUSION</b>	Page 12
	<b>ATTACHMENTS</b>	Page 14

<b>REVISION</b>	<b>DATE</b>	<b>DESCRIPTION</b>
Draft	5.07.2012	Draft for review

G:\Projects\HEALTH\LEET\_TEM\_HOSP\_LIFT\4\_da\arch\TEMORA SEE\TEMORA Hospital SEE 120625.docx



## **1. INTRODUCTION**

### **1.1 Background to the Proposal**

Temora & District Hospital is a 32 bed Public hospital and offers the following services Accident/emergency, Diabetes, Diversional therapy, Geriatric assessment, Home nursing, Maternity, Medical, Anaesthetics, Occupational therapy, Outpatients, Paediatric, Palliative care, Pathology, Physiotherapy, Podiatry, Radiology and Surgical.

NSW Health is proposing to carry out the provision of a new passenger lift. The existing lift is approaching the end of its service life and may experience mechanical failures. Due to the requirement to maintain operation within the hospital it is not feasible to replace the existing lift.

The Hospital is owned by NSW Health. It is located at the corner of Loftus Street and Gloucester Street, Temora in the Riverina NSW.

The new lift will provide a modern facility that ensures safe and convenient access for NSW Health, its employees, patients and the community.

### **1.2 Council Area**

The local council for the development is Temora Shire Council.

105 Loftus Street  
TEMORA 2666  
Ph: 02 6980 1100  
Fax: 02 6980 1138  
Email: [temshire@temora.nsw.gov.au](mailto:temshire@temora.nsw.gov.au)

### **1.3 Proposed Development**

The proposed development includes the following components:

- Provision of a new lift over 3 levels constructed within the existing building envelope.

The current operation of the Hospital will be un-changed.

## STATEMENT OF ENVIRONMENTAL EFFECTS

### 2. LOCATION

#### 2.1 Site Locality

Temora & District Hospital is located within the town centre of Temora, on the corner of Loftus Street and Gloucester Street. The site is defined as Lot 2 DP 572392. The hospital is readily accessible by vehicle and occupies generous, well landscaped grounds.

The site is primarily accessible by a driveway from Gloucester Street as well as secondary entries off surrounding roads. The site is approximately 110m x 242m giving a total site area of approx 2.4 Ha.



Figure 1 Town precinct. Temora Hospital in the centre of the photo.

The main 3 storey hospital building is part of Temora's heritage building stock. It dates from the late 1930s and is an example of art deco architecture. Like all hospitals it has undergone a series of additions over the last 50 years. The site is well established and contains a number of mature trees.

The site is zoned Special Purpose SP2 Infrastructure pursuant to Temora Shire Council Local Environmental Plan 2010. The hospital is not listed in Schedule 5 Environmental Heritage so has no formal heritage classification.

#### TEMORA DISTRICT HOSPITAL – NEW LIFT

## STATEMENT OF ENVIRONMENTAL EFFECTS

### 2.2 Existing Facility

The existing hospital comprises a major 2-3 storey brick building with adjacent 1-2 storey buildings providing a range of ancillary services, including staff accommodation and catering, laundry etc. The main facade of the hospital is quite imposing with a strong expression of the “art deco” style of cantilevered balconies and curved plan forms. The main building is in good condition and the main interior spaces are also well maintained and in largely original condition. The grounds are well established and have a strong link to the town centre. It is largely screened from surrounding properties and roads by generous landscaping, including mature trees.



PHOTO: Exterior of Temora Hospital showing vicinity of new lift.



PHOTO: Internal corridor showing location of new lift.

### TEMORA DISTRICT HOSPITAL – NEW LIFT

### 3. PROPOSED DEVELOPMENT

#### 3.1 Objectives of the Proposal

The main objective of the development is to ensure the continuous operation of lift services at the hospital. The existing lift is due for replacement but due to operational requirements it is not feasible to have the lift out of operation for a period of weeks.


#### 3.2 Options Considered

The primary requirement is to provide a lift in a central location that satisfies the current internal circulation/corridors of the hospital. Clearly the best location is close to the existing lift and stairs. A range of options were explored including new stand-alone lift shaft external to the building in a number of locations. These options would have entailed extensive building work and had a major impact on the appearance of the hospital.

#### 3.3 Preferred Option

The preferred option was sited within the building close to the existing lift shaft and stairwell. This location was central to the existing corridor layout and had no impact on the external appearance of the hospital. In addition it can be constructed with minimal disruption to the day to day operations of the hospital. There is some re-working of a small number of rooms close to the new lift. The lift shaft will extend beyond the existing roof line for approximately 1m but will be very unobtrusive.

#### Plan of Proposed Development



#### TEMORA DISTRICT HOSPITAL

##### Proposed New Lift

Preferred Concept Option  
Government Architects Office

20<sup>th</sup> April 2012  
Temora.001

#### TEMORA DISTRICT HOSPITAL – NEW LIFT

## **4. ENVIRONMENTAL ASSESSMENT**

Section 79C (1b) of the Environmental Planning and Assessment Act 1979, as amended, specifies the matters which a consent authority must consider when determining a development application. Comments on these matters are provided as follows.

### **4.1 Context and Setting**

The Hospital occupies its own dedicated site with generous external grounds set well back from the adjoining roads and neighbouring properties. The main building is an imposing 3 storey brick structure built in the late 1930s. The surrounding context is residential.

Activities on the site are hospital activities, including patient transfers, visitors and staff movements, as well as deliveries for catering, maintenance and waste. Generally the activities do not generate high levels of noise and do not involve any industrial processes. Operating times are 24 hours a day, 7 days a week.

### **4.2 Access and Transport**

Vehicular movements to the hospital for staff and visitors will not be affected by the new lift. The roads in the locality have sufficient capacity to accommodate the current volume of traffic and there will be no changes due to the proposed development.

### **4.3 Utilities**

The site is fully serviced by existing utilities including electrical and telecommunication infrastructure. All infrastructure and services required to support the development are available in the existing facility.

### **4.4 Heritage**

Temora Hospital was built in the interwar years and is a good example of Art Deco architecture. The neighbouring towns of Leeton and Griffith contain many fine examples of art deco architecture.

The Hospital is not listed as having local heritage significance. The proposed development has no impact on the primary facades of the main building as it will be constructed within the building envelope. Similarly, the new lift will have minimal impact on the interior spaces of the hospital, especially the existing open stair.

### **4.5 Other Land Resources**

Not Applicable.

### **4.6 Water**

The proposed lift will have no impact on water services.

### **4.7 Fire Fighting Water**

The proposed lift will have no impact on fire fighting services.

### **4.8 Sewer**

The proposed lift will have no impact on sewer. Any existing sewer within the building zone will be re-routed.

## STATEMENT OF ENVIRONMENTAL EFFECTS

### **4.9 Stormwater**

The proposed lift will have no impact on stormwater. The roof of the new lift shaft will drain to the existing roof with no increase in roof area.

### **4.10 Soils**

The lift shaft will be contained within the existing sub-floor.

### **4.11 Air and Microclimate**

There are no adverse impacts from the proposed development. There may be minimal short term impacts during construction but these impacts can be effectively managed.

### **4.12 Flora and Fauna**

There is no vegetation within the construction zone.

### **4.13 Waste**

NSW Health manages solid waste storage and collection facilities on the site, complying with Council waste requirements.

### **4.14 Energy**

Where possible energy-saving devices and fittings will be installed into the proposed development through compliance with Part J of the Building Construction Code (BCC).

### **4.15 Noise and Vibration**

Noise and vibration will be limited to that generated during construction of the works. Noise mitigation will be undertaken during the construction phase.

### **4.16 Natural Hazards**

The site is not subject to flooding. The site is not bushfire prone

### **4.17 Safety Security and Crime Prevention**

Hospital operations are designed to maximize safety and minimize opportunities for criminal behaviour. Security personnel maintain 24 hour oversight of the grounds and interior. After-hours access is by means of controlled entry.

### **4.18 Social Impact in the Locality**

The proposed development is compatible with the land use zoning. It has minimal impact on the local community. Temora Hospital is an important provider of health services to the Leeton community.

### **4.19 Economic Impact in the Locality**

The proposed development will facilitate the delivery of Health services to the community of Temora. The Hospital is an important local employer.

### **4.20 Cumulative Impacts**

The existing Hospital has been operating successfully for many years. It is anticipated the proposed development works will have no impact on the surrounding community and will facilitate the delivery of Health services to the community of Temora.

### **4.21 The Public Interest**

The proposed development is consistent with the public interest.

## 5. SAFEGUARDS DURING CONSTRUCTION

The following safeguards will be implemented during the construction phase. In addition to Council conditions, Public Works NSW requires a high level of environmental protection through its contract requirements.

### Construction Areas and Hours of Construction

- Establishment of a temporary contractor's security compound and gates adjacent the building site.
- Controlled vehicle and workforce access points.
- Construction areas maintained in a clean and tidy state at all times.
- Construction hours would comply with local Council requirements.
- The workforce will use the nearest amenity areas within the contractor's construction compound for rest breaks and temporary "portaloos" toilet facilities on site.

### Plant & Equipment

- All internal combustion engines would be maintained and in proper working order to ensure air and noise emissions were minimised.
- No vehicle maintenance would be permitted outside the work area except in emergencies.
- Mufflers would be fitted to all construction plant and equipment to meet EPA air and noise requirements.
- All plant / equipment would be inspected daily to avoid leakage of fuel, oil or hydraulic fluid to the worksite. Machinery found to be leaking would be repaired or replaced.
- All machinery would be secured against vandalism outside working hours.

### Traffic Management and Access

- Construction access to the site will be within the Hospital site.
- Where possible truck movements would occur outside peak traffic flow periods.
- Inconvenience to adjacent users and nearby communities would be minimised through best construction and management practices and include the requirement for safe and efficient access for all local vehicles and pedestrians.
- Traffic during construction would be managed in accordance with the requirements of Australian Standard 1742.3 – 1996 *Manual of Uniform Traffic Control Devices Part 3: Traffic Control Devices for Works on Roads*.
- Access will be maintained at all times to private properties and businesses.

### Waste Management and Contamination

- Waste management practices for the proposal would follow the resource management hierarchy principles (in priority order, avoidance, reuse, recycle, treatment and disposal) embodied in the *Waste Avoidance and Resource Recovery Act 2001*.
- Appropriate waste management practices will be adopted e.g. no burning or burying of wastes on site.
- All non-recyclable waste would be disposed of at legally operating waste disposal sites.
- No contaminated material would be used in any earthworks.
- Cleaning out of batched concrete mixing plant would not be permitted within the construction area.
- If any contaminated material (e.g. asbestos) were encountered during the carrying out of the works then safe work method statements and appropriate practices would be implemented.

## STATEMENT OF ENVIRONMENTAL EFFECTS

- Any contaminated material would be classified first and then disposed of in accordance with EPA requirements at an EPA licensed waste facility.
- The workforce would use temporary portable toilet facilities on site.
- During construction the building contractor(s) will be required to segregate waste and recycle, where possible, for regular removal.
- The waste management plan should refer to ensuring that all waste generated by the project, shall be beneficially reused, recycled or directed to a waste facility lawfully permitted to accept the materials in accordance with the Waste Classification Guidelines (DECC, 2008) and the Protection of the Environment Operations Act 1997.

### Erosion and Sediment Control

- Temporary erosion and sedimentation controls would be installed around the site.
- Regular monitoring and maintenance of the sedimentation controls would be implemented to ensure they perform in a fully functioning condition at all times.
- Exposed earthworks would be stabilised as quickly as possible.
- Exposed earthworks areas would be stabilised as quickly as possible.
- Mud deposited on the road network due to truck movements to and from the site would be either prevented or cleaned immediately.

### Air Quality

- Best management practices would be implemented for minimising off-site dust impacts from the project.
- Loose materials transported in trucks travelling on public roads would be covered.
- Construction work would be regularly monitored and hand held water sprays would be used to suppress dust as required.
- Tailgates of all vehicles transporting materials on public roads will be securely fixed.

### Noise

- Implementation of noise control measures, such as those in Australian Standard 2436-1981 *Guide to Noise Control on Construction, Maintenance and Demolition Sites* will be used to reduce construction noise levels. Reference to this Australian Standard suggests possible remedies such as screening, acoustic enclosures, engine silencing and substitution by alternative processes to reduce noise emission levels from typical construction equipment. In addition to these physical noise controls, the following general noise management measures would be followed:
- The contractor would use the best available techniques not entailing excessive cost to meet construction noise requirements as far as practicable in accordance with the Interim Construction Noise Guideline (DECC, 2009).

### Additional Mitigation Measures

Additional mitigation measures to minimise the impact on the environment should include:

- Preparation of a Construction Environmental Management Plan (CEMP) in accordance with the 2004 DIPNR guideline for the Preparation of Environmental Management Plans.
- All materials on-site or being delivered to the site must be contained within the site. The



## STATEMENT OF ENVIRONMENTAL EFFECTS

- Requirements of the Protection of the Environment Operations Act 1997 are to be complied with when placing/stockpiling loose material or when disposing of waste products or during any other activities which have the potential to pollute drains. The CEMP should include management procedures to ensure no pollution event occurs.
- All care and due diligence would be taken to prevent pollutant material entering drain inlets.
- Prior to commencement of construction activities, any services near the proposed building site which may be impacted by the works would be accurately located, which may include contacting 'Dial Before You Dig'.
- Authorities in relation to water utility provider, electricity supply authority, approved telecommunications carrier and gas carrier (as relevant to the site) should be consulted regarding any new connections to service infrastructure
- Construction hold points would be enforced in the following circumstances:
  - Failure to comply with environmental requirements;
  - Failure to secure all relevant approvals, licences and permits prior to commencement of any work relating to that approval, licence or permit;
  - Discovery of suspected or potentially contaminated ground.
- Concrete would be transported from legally operating established batching plants located near the proposal.
- The requirements of all applicable legislation would be met.

Each safeguard previously listed is the responsibility of the contractor and will be verified using a checklist, dated and signed off each workday over the construction period. NSW Department of Finance & Services representatives may periodically audit the contractor's construction environmental management plan to assess compliance.

The contractor's construction environmental management plan would indicate the names, responsibilities and authority of site management personnel who would have primary responsibility for implementing all environmental safeguards, monitoring effectiveness, rectifying environmental deficiencies, controlling further construction activities until deficiencies were rectified and the keeping of environmental records. The construction environmental management plan would include provision for hold points where environmental damage may occur, regular reports and audits on the environmental management of the project, details of non-conformance, verification activities and emergency responses.

## **6. CONCLUSION**

The proposed development will contribute to the amenity and operational effectiveness of the existing Hospital. It has economic and social benefits and will have no environmental impacts in the locality.

The proposed development is consistent with the land use zoning and will contribute to the creation of a modern facility that provides positive workplace and occupational health benefits for NSW Health, its employees and the community.

STATEMENT OF ENVIRONMENTAL EFFECTS



TEMORA DISTRICT HOSPITAL – NEW LIFT

STATEMENT OF ENVIRONMENTAL EFFECTS

**ATTACHMENTS**

**01 Development Submission (Plans)**

- **DA01 Site Plan**
- **DA02 Building Plan**
- **DA03 Elevations**



STATEMENT OF ENVIRONMENTAL EFFECTS

# TEMORA DISTRICT HOSPITAL LIFT REPLACEMENT



JULY 2012

PREPARED FOR MURRUMBIDGEE LOCAL HEALTH DISTRICT



Public Works  
Government Architect's Office

## STATEMENT OF ENVIRONMENTAL EFFECTS

### Forward

This Statement of Environmental Effects (SEE) assesses the potential impacts that may arise from the proposal to undertake provision of a new passenger lift at Temora Hospital. The SEE has been prepared in accordance with the relevant provisions of the Environmental Planning and Assessment Act 1979 and Environmental Planning and Assessment Regulation 2000.

### Property Address

TEMORA & DISTRICT HOSPITAL  
119 Gloucester Street  
TEMORA NSW 2666

### Contact Details

#### Client

Murrumbidgee Local Health District

#### Project Manager

Project Management (Wagga Office)  
NSW Public Works

Peter Hughes

T 02 6938 2877

M 0407 757 638

[peter.hughes@services.nsw.gov.au](mailto:peter.hughes@services.nsw.gov.au)

#### Project Architect

Government Architect's Office  
NSW Public Works

Philip Rose/Robert Isles

T 02 9372 8380

[Phil.Rose@services.nsw.gov.au](mailto:Phil.Rose@services.nsw.gov.au)

G:\Projects\HEALTH\LEET\_TEM\_HOSP\_LIFT\4\_da\arch\TEMORA SEE\TEMORA Hospital SEE 120625.docx

TEMORA DISTRICT HOSPITAL – NEW LIFT

## Table of Contents

<b>1.0</b>	<b>INTRODUCTION</b>	Page 3
<b>2.0</b>	<b>LOCATION DESCRIPTION</b>	Page 4
<b>3.0</b>	<b>PROPOSED DEVELOPMENT</b>	Page 6
<b>4.0</b>	<b>ENVIRONMENTAL ASSESSMENT</b>	Page 7
<b>5.0</b>	<b>SAFEGUARDS DURING CONSTRUCTION</b>	Page 9
<b>6.0</b>	<b>CONCLUSION</b>	Page 12
	<b>ATTACHMENTS</b>	Page 14

REVISION	DATE	DESCRIPTION
Draft	5.07.2012	Draft for review

G:\Projects\HEALTHLEET\_TEM\_HOSP\_LIFT4\_da\arch\TEMORA SEE\TEMORA Hospital SEE 120625.docx



## 1. INTRODUCTION

### 1.1 Background to the Proposal

Temora & District Hospital is a 32 bed Public hospital and offers the following services Accident/emergency, Diabetes, Diversional therapy, Geriatric assessment, Home nursing, Maternity, Medical, Anaesthetics, Occupational therapy, Outpatients, Paediatric, Palliative care, Pathology, Physiotherapy, Podiatry, Radiology and Surgical.

NSW Health is proposing to carry out the provision of a new passenger lift. The existing lift is approaching the end of its service life and may experience mechanical failures. Due to the requirement to maintain operation within the hospital it is not feasible to replace the existing lift.

The Hospital is owned by NSW Health. It is located at the corner of Loftus Street and Gloucester Street, Temora in the Riverina NSW.

The new lift will provide a modern facility that ensures safe and convenient access for NSW Health, its employees, patients and the community.

### 1.2 Council Area

The local council for the development is Temora Shire Council.

105 Loftus Street  
TEMORA 2666  
Ph: 02 6980 1100  
Fax: 02 6980 1138  
Email: [temshire@temora.nsw.gov.au](mailto:temshire@temora.nsw.gov.au)

### 1.3 Proposed Development

The proposed development includes the following components:

- Provision of a new lift over 3 levels constructed within the existing building envelope.

The current operation of the Hospital will be un-changed.

## 2. LOCATION

### 2.1 Site Locality

Temora & District Hospital is located within the town centre of Temora, on the corner of Loftus Street and Gloucester Street. The site is defined as Lot 2 DP 572392. The hospital is readily accessible by vehicle and occupies generous, well landscaped grounds.

The site is primarily accessible by a driveway from Gloucester Street as well as secondary entries off surrounding roads. The site is approximately 110m x 242m giving a total site area of approx 2.4 Ha.



Figure 1 Town precinct. Temora Hospital in the centre of the photo.

The main 3 storey hospital building is part of Temora's heritage building stock. It dates from the late 1930s and is an example of art deco architecture. Like all hospitals it has undergone a series of additions over the last 50 years. The site is well established and contains a number of mature trees.

The site is zoned Special Purpose SP2 Infrastructure pursuant to Temora Shire Council Local Environmental Plan 2010. The hospital is not listed in Schedule 5 Environmental Heritage so has no formal heritage classification.

## 2.2 Existing Facility

The existing hospital comprises a major 2-3 storey brick building with adjacent 1-2 storey buildings providing a range of ancillary services, including staff accommodation and catering, laundry etc. The main facade of the hospital is quite imposing with a strong expression of the “art deco” style of cantilevered balconies and curved plan forms. The main building is in good condition and the main interior spaces are also well maintained and in largely original condition. The grounds are well established and have a strong link to the town centre. It is largely screened from surrounding properties and roads by generous landscaping, including mature trees.



PHOTO: Exterior of Temora Hospital showing vicinity of new lift.



PHOTO: Internal corridor showing location of new lift.

### TEMORA DISTRICT HOSPITAL – NEW LIFT

### 3. PROPOSED DEVELOPMENT

#### 3.1 Objectives of the Proposal

The main objective of the development is to ensure the continuous operation of lift services at the hospital. The existing lift is due for replacement but due to operational requirements it is not feasible to have the lift out of operation for a period of weeks.


#### 3.2 Options Considered

The primary requirement is to provide a lift in a central location that satisfies the current internal circulation/corridors of the hospital. Clearly the best location is close to the existing lift and stairs. A range of options were explored including new stand-alone lift shaft external to the building in a number of locations. These options would have entailed extensive building work and had a major impact on the appearance of the hospital.

#### 3.3 Preferred Option

The preferred option was sited within the building close to the existing lift shaft and stairwell. This location was central to the existing corridor layout and had no impact on the external appearance of the hospital. In addition it can be constructed with minimal disruption to the day to day operations of the hospital. There is some re-working of a small number of rooms close to the new lift. The lift shaft will extend beyond the existing roof line for approximately 1m but will be very unobtrusive.

#### Plan of Proposed Development



#### TEMORA DISTRICT HOSPITAL

Proposed New Lift  
Preferred Concept Option  
Government Architects Office

20<sup>th</sup> April 2012  
Temora.001

#### TEMORA DISTRICT HOSPITAL – NEW LIFT

## **4. ENVIRONMENTAL ASSESSMENT**

Section 79C (1b) of the Environmental Planning and Assessment Act 1979, as amended, specifies the matters which a consent authority must consider when determining a development application. Comments on these matters are provided as follows.

### **4.1 Context and Setting**

The Hospital occupies its own dedicated site with generous external grounds set well back from the adjoining roads and neighbouring properties. The main building is an imposing 3 storey brick structure built in the late 1930s. The surrounding context is residential.

Activities on the site are hospital activities, including patient transfers, visitors and staff movements, as well as deliveries for catering, maintenance and waste. Generally the activities do not generate high levels of noise and do not involve any industrial processes. Operating times are 24 hours a day, 7 days a week.

### **4.2 Access and Transport**

Vehicular movements to the hospital for staff and visitors will not be affected by the new lift. The roads in the locality have sufficient capacity to accommodate the current volume of traffic and there will be no changes due to the proposed development.

### **4.3 Utilities**

The site is fully serviced by existing utilities including electrical and telecommunication infrastructure. All infrastructure and services required to support the development are available in the existing facility.

### **4.4 Heritage**

Temora Hospital was built in the interwar years and is a good example of Art Deco architecture. The neighbouring towns of Leeton and Griffith contain many fine examples of art deco architecture.

The Hospital is not listed as having local heritage significance. The proposed development has no impact on the primary facades of the main building as it will be constructed within the building envelope. Similarly, the new lift will have minimal impact on the interior spaces of the hospital, especially the existing open stair.

### **4.5 Other Land Resources**

Not Applicable.

### **4.6 Water**

The proposed lift will have no impact on water services.

### **4.7 Fire Fighting Water**

The proposed lift will have no impact on fire fighting services.

### **4.8 Sewer**

The proposed lift will have no impact on sewer. Any existing sewer within the building zone will be re-routed.

## STATEMENT OF ENVIRONMENTAL EFFECTS

### **4.9 Stormwater**

The proposed lift will have no impact on stormwater. The roof of the new lift shaft will drain to the existing roof with no increase in roof area.

### **4.10 Soils**

The lift shaft will be contained within the existing sub-floor.

### **4.11 Air and Microclimate**

There are no adverse impacts from the proposed development. There may be minimal short term impacts during construction but these impacts can be effectively managed.

### **4.12 Flora and Fauna**

There is no vegetation within the construction zone.

### **4.13 Waste**

NSW Health manages solid waste storage and collection facilities on the site, complying with Council waste requirements.

### **4.14 Energy**

Where possible energy-saving devices and fittings will be installed into the proposed development through compliance with Part J of the Building Construction Code (BCC).

### **4.15 Noise and Vibration**

Noise and vibration will be limited to that generated during construction of the works. Noise mitigation will be undertaken during the construction phase.

### **4.16 Natural Hazards**

The site is not subject to flooding. The site is not bushfire prone

### **4.17 Safety Security and Crime Prevention**

Hospital operations are designed to maximize safety and minimize opportunities for criminal behaviour. Security personnel maintain 24 hour oversight of the grounds and interior. After-hours access is by means of controlled entry.

### **4.18 Social Impact in the Locality**

The proposed development is compatible with the land use zoning. It has minimal impact on the local community. Temora Hospital is an important provider of health services to the Leeton community.

### **4.19 Economic Impact in the Locality**

The proposed development will facilitate the delivery of Health services to the community of Temora. The Hospital is an important local employer.

### **4.20 Cumulative Impacts**

The existing Hospital has been operating successfully for many years. It is anticipated the proposed development works will have no impact on the surrounding community and will facilitate the delivery of Health services to the community of Temora.

### **4.21 The Public Interest**

The proposed development is consistent with the public interest.

## 5. SAFEGUARDS DURING CONSTRUCTION

The following safeguards will be implemented during the construction phase. In addition to Council conditions, Public Works NSW requires a high level of environmental protection through its contract requirements.

### Construction Areas and Hours of Construction

- Establishment of a temporary contractor's security compound and gates adjacent the building site.
- Controlled vehicle and workforce access points.
- Construction areas maintained in a clean and tidy state at all times.
- Construction hours would comply with local Council requirements.
- The workforce will use the nearest amenity areas within the contractor's construction compound for rest breaks and temporary "portaloos" toilet facilities on site.

### Plant & Equipment

- All internal combustion engines would be maintained and in proper working order to ensure air and noise emissions were minimised.
- No vehicle maintenance would be permitted outside the work area except in emergencies.
- Mufflers would be fitted to all construction plant and equipment to meet EPA air and noise requirements.
- All plant / equipment would be inspected daily to avoid leakage of fuel, oil or hydraulic fluid to the worksite. Machinery found to be leaking would be repaired or replaced.
- All machinery would be secured against vandalism outside working hours.

### Traffic Management and Access

- Construction access to the site will be within the Hospital site.
- Where possible truck movements would occur outside peak traffic flow periods.
- Inconvenience to adjacent users and nearby communities would be minimised through best construction and management practices and include the requirement for safe and efficient access for all local vehicles and pedestrians.
- Traffic during construction would be managed in accordance with the requirements of Australian Standard 1742.3 – 1996 *Manual of Uniform Traffic Control Devices Part 3: Traffic Control Devices for Works on Roads*.
- Access will be maintained at all times to private properties and businesses.

### Waste Management and Contamination

- Waste management practices for the proposal would follow the resource management hierarchy principles (in priority order, avoidance, reuse, recycle, treatment and disposal) embodied in the *Waste Avoidance and Resource Recovery Act 2001*.
- Appropriate waste management practices will be adopted e.g. no burning or burying of wastes on site.
- All non-recyclable waste would be disposed of at legally operating waste disposal sites.
- No contaminated material would be used in any earthworks.
- Cleaning out of batched concrete mixing plant would not be permitted within the construction area.
- If any contaminated material (e.g. asbestos) were encountered during the carrying out of the works then safe work method statements and appropriate practices would be implemented.

## STATEMENT OF ENVIRONMENTAL EFFECTS

- Any contaminated material would be classified first and then disposed of in accordance with EPA requirements at an EPA licensed waste facility.
- The workforce would use temporary portable toilet facilities on site.
- During construction the building contractor(s) will be required to segregate waste and recycle, where possible, for regular removal.
- The waste management plan should refer to ensuring that all waste generated by the project, shall be beneficially reused, recycled or directed to a waste facility lawfully permitted to accept the materials in accordance with the Waste Classification Guidelines (DECC, 2008) and the Protection of the Environment Operations Act 1997.

### **Erosion and Sediment Control**

- Temporary erosion and sedimentation controls would be installed around the site.
- Regular monitoring and maintenance of the sedimentation controls would be implemented to ensure they perform in a fully functioning condition at all times.
- Exposed earthworks would be stabilised as quickly as possible.
- Exposed earthworks areas would be stabilised as quickly as possible.
- Mud deposited on the road network due to truck movements to and from the site would be either prevented or cleaned immediately.

### **Air Quality**

- Best management practices would be implemented for minimising off-site dust impacts from the project.
- Loose materials transported in trucks travelling on public roads would be covered.
- Construction work would be regularly monitored and hand held water sprays would be used to suppress dust as required.
- Tailgates of all vehicles transporting materials on public roads will be securely fixed.

### **Noise**

- Implementation of noise control measures, such as those in Australian Standard 2436-1981 *Guide to Noise Control on Construction, Maintenance and Demolition Sites* will be used to reduce construction noise levels. Reference to this Australian Standard suggests possible remedies such as screening, acoustic enclosures, engine silencing and substitution by alternative processes to reduce noise emission levels from typical construction equipment. In addition to these physical noise controls, the following general noise management measures would be followed:
- The contractor would use the best available techniques not entailing excessive cost to meet construction noise requirements as far as practicable in accordance with the Interim Construction Noise Guideline (DECC, 2009).

### **Additional Mitigation Measures**

Additional mitigation measures to minimise the impact on the environment should include:

- Preparation of a Construction Environmental Management Plan (CEMP) in accordance with the 2004 DIPNR guideline for the Preparation of Environmental Management Plans.
- All materials on-site or being delivered to the site must be contained within the site. The



## STATEMENT OF ENVIRONMENTAL EFFECTS

- Requirements of the Protection of the Environment Operations Act 1997 are to be complied with when placing/stockpiling loose material or when disposing of waste products or during any other activities which have the potential to pollute drains. The CEMP should include management procedures to ensure no pollution event occurs.
- All care and due diligence would be taken to prevent pollutant material entering drain inlets.
- Prior to commencement of construction activities, any services near the proposed building site which may be impacted by the works would be accurately located, which may include contacting 'Dial Before You Dig'.
- Authorities in relation to water utility provider, electricity supply authority, approved telecommunications carrier and gas carrier (as relevant to the site) should be consulted regarding any new connections to service infrastructure
- Construction hold points would be enforced in the following circumstances:
  - Failure to comply with environmental requirements;
  - Failure to secure all relevant approvals, licences and permits prior to commencement of any work relating to that approval, licence or permit;
  - Discovery of suspected or potentially contaminated ground.
- Concrete would be transported from legally operating established batching plants located near the proposal.
- The requirements of all applicable legislation would be met.

Each safeguard previously listed is the responsibility of the contractor and will be verified using a checklist, dated and signed off each workday over the construction period. NSW Department of Finance & Services representatives may periodically audit the contractor's construction environmental management plan to assess compliance.

The contractor's construction environmental management plan would indicate the names, responsibilities and authority of site management personnel who would have primary responsibility for implementing all environmental safeguards, monitoring effectiveness, rectifying environmental deficiencies, controlling further construction activities until deficiencies were rectified and the keeping of environmental records. The construction environmental management plan would include provision for hold points where environmental damage may occur, regular reports and audits on the environmental management of the project, details of non-conformance, verification activities and emergency responses.

## **6. CONCLUSION**

The proposed development will contribute to the amenity and operational effectiveness of the existing Hospital. It has economic and social benefits and will have no environmental impacts in the locality.

The proposed development is consistent with the land use zoning and will contribute to the creation of a modern facility that provides positive workplace and occupational health benefits for NSW Health, its employees and the community.

STATEMENT OF ENVIRONMENTAL EFFECTS



TEMORA DISTRICT HOSPITAL – NEW LIFT

## STATEMENT OF ENVIRONMENTAL EFFECTS

### **ATTACHMENTS**

#### **01 Development Submission (Plans)**


- **DA01 Site Plan**
- **DA02 Building Plan**
- **DA03 Elevations**





**Public Works**  
Project Management

Riverina Western Region  
2-6 Coleman Street WAGGA WAGGA, NSW 2650  
T 02 6938 2880 F 02 6925 2087 TTY 1300 300 000  
ABN 81 913 830 179 www.publicworks.nsw.gov.au



Temora Shire Council,  
PO Box 262,  
TEMORA  
NSW 2666

To Whom It May Concern,

**DA: Temora District Hospital: Supply, Installation and construction of lift shaft and lift car**

**Development Application**

Please find enclosed the Development Application for the Temora District Hospital Lift Project.

- Two (2) copies of the following:
  - Development Application Form
  - The Project Brief
  - The location of proposed works in relation to the building,
  - Floor plans of proposed buildings showing layout,
  - Elevations and Sections showing proposed works
  - Specifications that specify the Lift Service Scope.
  - Statement of Environmental Effects

If you require any further information please do not hesitate to contact me.

Yours sincerely,

Peter Hughes  
Project Manager

12 July 2012



B/04/03



7<sup>th</sup> May 2012

The General Manager  
Temora Shire Council  
PO BOX 262  
TEMORA NSW 2666

Ref: BCM4597

Dear Sir

**Re: Annual Fire Safety Statements  
Greenstone Ldg & Narraburra Ldg  
The Whiddon Group – Temora**

Please find enclosed the following documents:

- (a) The Frank Whiddon Masonic Homes of NSW Annual Fire Safety Statements for both buildings duly completed.
- (b) National Fire Solutions Pty Ltd – Annual Fire Safety Statements for both buildings dated 2<sup>nd</sup> May 2012.
- (c) As noted on Certificate, copies have been forwarded to NSW Fire Brigade.

Trusting the above meeting with your approval.

Yours faithfully

Phill Brown  
Manager Building Services

Enc:

**Building Dept. Fax No: 9827.6699**



ATTACHMENT C

**ANNUAL FIRE SAFETY STATEMENT**  
Environmental Planning and Assessment Regulation 2000

**FACILITY - Greenstone Lodge - Noel Warren Masonic Village - Temora**

**CERTIFICATION**

I, Phillip Brown, of The Frank Whiddon Masonic Homes of NSW, being the owner of the building described below, or the agent of the owner certify -

- A) That each of the essential fire or other safety measures listed below:
- 1) has been assessed by a properly qualified person, and
  - 2) was found when it was assessed, to be capable of performing:
    - (i) in the case of an essential fire safety measure applicable by virtue of a fire safety schedule, to a standard no less than that specified in the schedule, or
    - (ii) in the case of an essential fire safety measure applicable otherwise than by virtue of a fire safety schedule, to a standard no less than that to which the measure was originally designed and implemented, and
- B) That the building has been inspected by a properly qualified person and was found, when it was inspected, to be in a condition that did not disclose any grounds for a prosecution under Division 7.
- C) That the information contained in this Certificate is, to the best of my knowledge and belief, true and accurate.

**IDENTIFICATION OF BUILDING**

House/unit no. or name: Greenstone Lodge  
Street: Gloucester Street  
Suburb: Temora  
Nearest cross street: Loftus

**PARTICULARS OF BUILDING**

Whole/part: Whole  
Description of part: Class 3

**DATE OF INSPECTION - 20.01.2012 22.02.2012 19.04.2012**

**OWNER'S DETAILS**

Name: The Frank Whiddon Masonic Homes of NSW  
Address: 81 Belmont Road, GLENFIELD NSW 2167

THE FRANK WHIDDON MASONIC HOMES OF NSW  
Standard Procedures  
ANNUAL FIRE SAFETY STATEMENTS –

Greenstone Lodge- Temora

**CURRENT FIRE SAFETY SCHEDULE**

The current Fire Safety Schedule for the building is attached to this statement.

**ESSENTIAL FIRE SAFETY MEASURES**

Measure	Standard of Performance	Date of Assessment
Fire Extinguishers	AS 2444	20.01.2012
Fire Hose Reels	AS 2444	20.01.2012
OWS System	AS 2220.2	19.04.2012
Fire/ Smoke Doors	AS 1905.1	22.02.2012
Emergency Lighting	AS 2293.1	22.02.2012
Fire Detection Systems	AS 1670	19.04.2012
Exit Signs	AS 2293.1	22.02.2012
Fail Safe Devices	1670.1	19.04.2012
Sprinkler System	AS 2188.4	19.04.2012
Electric Pump Sets	AS 2419	19.04.2012

Dated this 7<sup>th</sup> day of May 2012

Signed  .....

(Capacity Agent)

A copy of this statement has been forwarded to:

- ✓ Temora Shire Council
- ✓ NSW Fire Brigades

ATTACHMENT C

**ANNUAL FIRE SAFETY STATEMENT**  
Environmental Planning and Assessment Regulation 2000

**FACILITY -** *Narraburra Lodge – Noel Warren Masonic Village - Temora*

**CERTIFICATION**

I, Phillip Brown, of The Frank Whiddon Masonic Homes of NSW, being the owner of the building described below, or the agent of the owner certify –

- A) That each of the essential fire or other safety measures listed below:
- 1) has been assessed by a properly qualified person, and
  - 2) was found when it was assessed, to be capable of performing:
    - (i) in the case of an essential fire safety measure applicable by virtue of a fire safety schedule, to a standard no less than that specified in the schedule, or
    - (ii) in the case of an essential fire safety measure applicable otherwise than by virtue of a fire safety schedule, to a standard no less than that to which the measure was originally designed and implemented, and
- B) That the building has been inspected by a properly qualified person and was found, when it was inspected, to be in a condition that did not disclose any grounds for a prosecution under Division 7.
- C) That the information contained in this Certificate is, to the best of my knowledge and belief, true and accurate.

**IDENTIFICATION OF BUILDING**

House/unit no. or name: Narraburra Lodge  
Street: Kitchener Road  
Suburb: Temora  
Nearest cross street: Bundawarra Road

**PARTICULARS OF BUILDING**

Whole/part: Whole  
Description of part: Class 9A

**DATE OF INSPECTION –** 19.04.2012 15.02.2012 21.02.2012 27.01.2012

**OWNER'S DETAILS**

Name: The Frank Whiddon Masonic Homes of NSW  
Address: 81 Belmont Road, GLENFIELD NSW 2167

THE FRANK WHIDDON MASONIC HOMES OF NSW  
Standard Procedures  
ANNUAL FIRE SAFETY STATEMENTS –

Narraburra Lodge Temora

**CURRENT FIRE SAFETY SCHEDULE**

The current Fire Safety Schedule for the building is attached to this statement.

**ESSENTIAL FIRE SAFETY MEASURES**

Measure	Standard of Performance	Date of Assessment
Fire Extinguishers	AS 2444	27.01.2012
Fire Hose Reels	AS 2444	27.01.2012
Fire/ Smoke Doors	AS 1905 BCA C3.4	21.02.2012
Emergency Lights	AS 2293.1	21.02.2012
Fire Hydrants	AS 2419.1	15.02.2012
Fire Detection Systems	AS 1670.1	19.04.2012
EWIS/ OWS System	AS 2220.2	19.04.2012
Fail Safe Devices	AS 1670.1	19.04.2012
Exit Lights	AS 2293.1	19.04.2012

Dated this 7<sup>th</sup> day of May 2012

Signed  .....

(Capacity Agent)

A copy of this statement has been forwarded to:

✓ Temora Shire Council  
✓ NSW Fire Brigades



# Fire Safety Certificate

National Fire Solutions Pty Ltd

ABN: 56 087 239 085

Sydney | Melbourne | Perth | Brisbane | Canberra | Albury | Wagga Wagga | Wollongong

www.natfire.com.au

National Fire Solutions Pty Ltd confirm they have conducted the inspection and testing of Fire Protection Equipment or other safety measures at the property noted below

### Description of property being certified.

Name of property: Greenstone Lodge Temora  
 Address of property: 37 Gloucester Street Temora, NSW, 2666  
 Certificate date range: 02/05/2011 to 02/05/2012

### Assessment of safety measures.

The following list of essential services or other safety measures were found to be, at the date of inspection, maintained to the relevant standard and were capable of operating to a standard not less than that to which it was originally designed.

Product Name	Maintenance Standard	Original Design Standard	Date of last service within period
Booster Pump Set - Sprinklers	AS 1851-2005.3	AS2419-1994	19/04/2012
Domestic Fire Sprinkler System	AS 1851-2005.2	AS 2118	19/04/2012
Fire Extinguishers, Hose Reels and Blankets	AS 1851-2005.14,15,16	AS 2444 / AS 2441	20/01/2012
Fire/Smoke Doors	AS 1851-2005.17	AS 1905.1	22/02/2012
Fire/Smoke Doors	AS 1851-2005.17	AS 1905.1	22/02/2012
Inertla - Occupant Warning System	AS 1851-2005.10	AS 2220.2	19/04/2012
Notifier - 2800 Fire Indicator Panel	AS 1851-2005.6	AS 1670.1	19/04/2012
Stand Alone - Emergency & Exit Lighting	AS 2293.2	AS 2293.1	22/02/2012

### Equipment status

As at the date of this document, FireTraX has recorded no defects for the equipment listed above.

### Certification.

I Robert Ingold of National Fire Solutions Pty Ltd

Being an authorised certifying officer for and on behalf of National Fire Solutions Pty Ltd, being the fire protection maintenance contractor of the building described above, certify that:

- Each of the essential fire safety measures listed above:
- has been assessed by a properly qualified person, and
  - was found, as at the date of inspection, to be capable of performing to at least the standard listed on this document
- The information contained in this statement is true and accurate to the best of my knowledge and belief.

### Signature.

Name: Robert Ingold  
 Position: Regional Manager  
 Company: National Fire Solutions Pty Ltd

Signature: per [Handwritten Signature]



# Fire Safety Certificate

National Fire Solutions Pty Ltd

ABN: 56 087 239 085

Sydney | Melbourne | Perth | Brisbane | Canberra | Albury | Wagga Wagga | Wollongong

www.natfire.com.au

National Fire Solutions Pty Ltd confirm they have conducted the inspection and testing of Fire Protection Equipment or other safety measures at the property noted below

### Description of property being certified.

Name of property: Narraburra Lodge Temora  
 Address of property: Kitchener Road Temora , NSW, 2666  
 Certificate date range: 02/05/2011 to 02/05/2012

### Assessment of safety measures.

The following list of essential services or other safety measures were found to be, at the date of inspection, maintained to the relevant standard and were capable of operating to a standard not less than that to which it was originally designed.

Product Name	Maintenance Standard	Original Design Standard	Date of last service within period
EWIS System	AS 1851-2005.9,10	AS 2220.2	19/04/2012
Fire Extinguishers, Hose Reels and Blankets	AS 1851-2005.14,15,16	AS 2444 / AS 2441	27/01/2012
Fire Hydrants	AS 1851-2005.4	AS 2419.1	15/02/2012
Fire/Smoke Doors	AS 1851-2005.17	AS 1805.1	21/02/2012
Firenet - Analogue/Addressable Fire Control Panel	AS 1851-2005.6	AS 1670.1	19/04/2012
Stand Alone - Emergency & Exit Lighting	AS 2293.2	AS 2293.1	21/02/2012

### Equipment status

As at the date of this document, FireTraX has recorded no defects for the equipment listed above.

### Certification.

I **Robert Ingold** of **National Fire Solutions Pty Ltd**

being an authorised certifying officer for and on behalf of National Fire Solutions Pty Ltd, being the fire protection maintenance contractor of the building described above, certify that:

- Each of the essential fire safety measures listed above:
  - has been assessed by a properly qualified person, and
  - was found, as at the date of inspection, to be capable of performing to at least the standard listed on this document
- The information contained in this statement is true and accurate to the best of my knowledge and belief.

### Signature.


Name: **Robert Ingold**  
 Position: **Regional Manager**  
 Company: **National Fire Solutions Pty Ltd**

Signature: *per R Ingold*



B/0499

14 May 2010



The General Manager  
Temora Shire Council  
PO BOX 262  
TEMORA NSW 2666

Ref: BCM3798

Dear Sir

**Re: Annual Fire Safety Statements  
Greenstone Ldg & Narraburra Ldg  
The Whiddon Group – Temora**

Please find enclosed the following documents:

- (a) The Frank Whiddon Masonic Homes of NSW Annual Fire Safety Statements for both buildings duly completed.
- (b) Wagga Fire Security – Annual Fire Safety Statements for both buildings dated 11<sup>th</sup> May 2010.
- (c) As noted on Certificate, copies have been forwarded to NSW Fire Brigade.

---

Trusting the above meeting with your approval.

Yours faithfully



Phill Brown  
Manager Building Services

Enc:

**Building Dept. Fax No: 9827.6699**



ATTACHMENT C

**ANNUAL FIRE SAFETY STATEMENT**  
Environmental Planning and Assessment Regulation 2000

**FACILITY -** *Narraburra Lodge - Noel Warren Masonic Village - Temora*

**CERTIFICATION**

I, Phillip Brown, of The Frank Whiddon Masonic Homes of NSW, being the owner of the building described below, or the agent of the owner certify -

- A) That each of the essential fire or other safety measures listed below:
- 1) has been assessed by a properly qualified person, and
  - 2) was found when it was assessed, to be capable of performing:
    - (i) in the case of an essential fire safety measure applicable by virtue of a fire safety schedule, to a standard no less than that specified in the schedule, or
    - (ii) in the case of an essential fire safety measure applicable otherwise than by virtue of a fire safety schedule, to a standard no less than that to which the measure was originally designed and implemented, and
- B) That the building has been inspected by a properly qualified person and was found, when it was inspected, to be in a condition that did not disclose any grounds for a prosecution under Division 7.
- C) That the information contained in this Certificate is, to the best of my knowledge and belief, true and accurate.

**IDENTIFICATION OF BUILDING**

House/unit no. or name: Narraburra Lodge  
Street: Kitchener Road  
Suburb: Temora  
Nearest cross street: Bundawarra Road

**PARTICULARS OF BUILDING**

Whole/part: Whole  
Description of part:

**DATE OF INSPECTION - 22.04.2010**

**OWNER'S DETAILS**

Name: The Frank Whiddon Masonic Homes of NSW  
Address: 81 Belmont Road, GLENFIELD NSW 2167

### CURRENT FIRE SAFETY SCHEDULE

The current Fire Safety Schedule for the building is attached to this statement.

### ESSENTIAL FIRE SAFETY MEASURES

Measure	Standard of Performance	Date of Assessment
Fire Extinguishers	AS 2444	22.04.2010
Fire Hose Reels	AS 2441	22.04.2010
Fire/ Smoke Doors	AS 1905 BCA C3.4	22.04.2010
Emergency Lights	AS 2293.1	22.04.2010
Fire Hydrants	AS 2419.1	22.04.2010
Fire Detection Systems	AS 1670	22.04.2010
EWIS/ OWS System	AS 1670.4	22.04.2010
Fail Safe Devices	BCA D2.21	22.04.2010
Exit Lights	AS 2293.1	22.04.2010
Fire Damper	AS 1668.1	26.03.2010

Dated this 14<sup>th</sup> day of May 2010

Signed.....

(Capacity Agent)

A copy of this statement has been forwarded to:

✓ Temora Shire Council  
✓ NSW Fire Brigades



## Annual Fire Safety Statement

Under the Environmental Planning and Assessment Regulation 2000  
- Division 5, Clauses 175 and 178

COPY

### Type of Certificate

Annual

Supplementary

I, **Richard Turner**

Of **Wagga Fire & Security,  
Unit 2/1 Jones St.  
Wagga Wagga NSW 2650  
P: (02) 6921 5554 F: (02) 69213943 E: admin@waggafiresecurity.com.au**

### Certify:

- 1) That each essential fire safety measure specified in this statement has been assessed by a properly qualified person and was found, when it was assessed, to be capable of performing:
  - i. In the case of an essential fire safety measure applicable by virtue of a fire safety schedule, to a standard no less than that specified in the schedule, or
  - ii. In the case of an essential fire safety measure applicable otherwise than by virtue of a fire safety schedule, to a standard no less than that to which the measure was originally designed and implemented, and;
- 2) The building has been inspected by a properly qualified person and was found, that at the date it was inspected, to be in a condition that did not disclose any grounds for a prosecution under Division 7 of the Environmental Planning and Assessment Regulation 2000, and;
- 3) The information contained in this statement is, to the best of my knowledge and belief, true and accurate.

### Identification of Building

Identification: **Narraburra Lodge**  
Street: **Kitchener Road**  
Nearest Cross Street: **French Street**  
Locality / Town: **TEMORA NSW 2666**

### Particulars of Building

Whole  
 Part of Building Description:

### Date of Assessment

Dated this **22<sup>nd</sup>** day of **April** 2010

### Owners Details

Name(s) **The Frank Whiddon Masonic Homes of New South Wales**  
Address **Narraburra Lodge, Kitchener Road**  
**TEMORA** State **NSW** Post Code **2666**

### Essential Fire Safety Measures

Measure/Item	Standard of Performance	Standard of Maintenance
Fire Extinguishers	AS 2444	AS1851.1
Fire Hose Reels	AS 1221	AS 1851.2
Fire Hydrants	AS 2419.1	AS 1851.4
EWIS / OWS	AS 1670.4	AS 1851.10
Fire / Smoke Doors	AS 1905	AS 1851.7
Exit/Emergency Lighting	AS 2293.1	AS 2293.2
Fire Detection System	AS 1670.1	AS 1851.8
Fail Safe Devices	D2, 21 of BCA	

### Declaration

I declare that all the information given is true and correct

Signature: 

Date: **11<sup>th</sup> May 2010.**

A copy of this certificate together with the relevant fire safety schedule must be forwarded to the Council and to the Commissioner of the New South Wales Fire Brigades

A copy of this certificate together with the relevant fire safety schedule must be prominently displayed within the building



**MARTIN & WHEELER PTY. LTD**

ABN 50 003 531 557

AIR CONDITIONING ENGINEERS  
DESIGN & INSTALLATION SERVICE

mandwptyld@bigpond.com

187 MORGAN STREET  
WAGGA WAGGA, NSW, 2650  
P.O. Box 4009, ASHMONT  
TEL: (02) 6921 6390  
FAX: (02) 6921 2332

**N.W. BLAND & SONS**

26<sup>th</sup> March 2010

Attn : Rob Bland

# CERTIFICATE of COMPLIANCE

This is to certify that the intumescent fire damper installed to the drier exhaust in the Laundry ductwork at Narraburra Lodge – Temora has been installed in accordance with AS1668.1.

**Signed:**

**Bryan Wheeler**  
(Director)

ATTACHMENT C

**ANNUAL FIRE SAFETY STATEMENT**  
Environmental Planning and Assessment Regulation 2000

**FACILITY - Greenstone Lodge - Noel Warren Masonic Village - Temora**

**CERTIFICATION**

I, Phillip Brown, of The Frank Whiddon Masonic Homes of NSW, being the owner of the building described below, or the agent of the owner certify --

- A) That each of the essential fire or other safety measures listed below:
- 1) has been assessed by a properly qualified person, and
  - 2) was found when it was assessed, to be capable of performing:
    - (i) In the case of an essential fire safety measure applicable by virtue of a fire safety schedule, to a standard no less than that specified in the schedule, or
    - (ii) in the case of an essential fire safety measure applicable otherwise than by virtue of a fire safety schedule, to a standard no less than that to which the measure was originally designed and implemented, and
- B) That the building has been inspected by a properly qualified person and was found, when it was inspected, to be in a condition that did not disclose any grounds for a prosecution under Division 7.
- C) That the information contained in this Certificate is, to the best of my knowledge and belief, true and accurate.

**IDENTIFICATION OF BUILDING**

House/unit no. or name: Greenstone Lodge  
Street: Gloucester Street  
Suburb: Temora  
Nearest cross street: Loftus

**PARTICULARS OF BUILDING**

Whole/part: Whole  
Description of part:

**DATE OF INSPECTION - 22.04.2010**

**OWNER'S DETAILS**

Name: The Frank Whiddon Masonic Homes of NSW  
Address: 81 Belmont Road, GLENFIELD NSW 2167

### CURRENT FIRE SAFETY SCHEDULE

The current Fire Safety Schedule for the building is attached to this statement.

### ESSENTIAL FIRE SAFETY MEASURES

Measure	Standard of Performance	Date of Assessment
Fire Extinguishers	AS 2444	22.04.2010
Fire Hose Reels	AS 2441	22.04.2010
Fire Hydrants	AS 2419.1	22.04.2010
OWS System	AS 1670.4	22.04.2010
Fire/ Smoke Doors	AS 1905 BCA C3.4	22.04.2010
Emergency Lighting	AS 2293.1	22.04.2010
Fire Detection Systems	AS 1670	22.04.2010
Exit Signs	AS 2293.1	22.04.2010
Fail Safe Devices	BCA D2.21	22.04.2010
Sprinkler System	AS 2188.4	22.04.2010
Electric Pump Sets	AS 2941	22.04.2010

Dated this 14<sup>th</sup> day of May 2010

Signed.....

(Capacity Agent)

A copy of this statement has been forwarded to:

✓ Temora Shire Council  
✓ NSW Fire Brigades



# Annual Fire Safety Statement

Under the Environmental Planning and Assessment Regulation 2000  
- Division 5, Clauses 175 and 178

COPY  
Covered

**Type of Certificate**

Annual

Supplementary

I **Richard Turner**

Of **Wagga Fire & Security,  
Unit 2/1 Jones St  
Wagga Wagga NSW 2650  
P: (02) 6921 5554 F: (02) 69213943 E: admin@waggafiresecurity.com.au**

**Certify:**

- 1) That each essential fire safety measure specified in this statement has been assessed by a properly qualified person and was found, when it was assessed, to be capable of performing:
  - i. In the case of an essential fire safety measure applicable by virtue of a fire safety schedule, to a standard no less than that specified in the schedule, or
  - ii. In the case of an essential fire safety measure applicable otherwise than by virtue of a fire safety schedule, to a standard no less than that to which the measure was originally designed and implemented, and;
- 2) The building has been inspected by a properly qualified person and was found, that at the date it was inspected, to be in a condition that did not disclose any grounds for a prosecution under Division 7 of the Environmental Planning and Assessment Regulation 2000, and;
- 3) The information contained in this statement is, to the best of my knowledge and belief, true and accurate.

**Identification of Building**

Identification: **Greenstone Lodge**  
Street: **Gloucester Street**  
Nearest Cross Street: **Temora Young Road**  
Locality / Town: **TEMORA NSW 2666**

**Particulars of Building**

Whole  
 Part of Building Description:

**Date of Assessment**

Dated this **22<sup>nd</sup>** day of **April** **2010**

**Owners Details**

Name(s) **The Frank Whiddon Masonic Homes of New South Wales**  
Address **Greenstone Lodge, Gloucester Street**  
**TEMORA** State **NSW** Post Code **2666**

**Essential Fire Safety Measures**

Measure/Item	Standard of Performance	Standard of Maintenance
Fire Extinguishers	AS 2444	AS1851.1
Fire Hose Reels	AS 1221	AS 1851.2
Fire Hydrants	AS 2419.1	AS 1851.4
OWS	AS 1670.4	AS 1851.10
Fire / Smoke Doors	AS 1905	AS 1851.7
Exit/Emergency Lighting	AS 2293.1	AS 2293.2
Fire Detection System	AS 1670.1	AS 1851.8
Fail Safe Devices	D2, 21 of BCA	
Sprinkler System - Residential	AS 2118.4	AS 1851.3
Electric Pump Sets	AS 2941	AS1851.14

**Declaration**

I declare that all the information given is true and correct

Signature:

Date: **11<sup>th</sup> May 2010.**

A copy of this certificate together with the relevant fire safety schedule must be forwarded to the Council and to the Commissioner of the New South Wales Fire Brigades

A copy of this certificate together with the relevant fire safety schedule must be prominently displayed within the building



---

## Section 10.7 Certificates





# TEMORA SHIRE COUNCIL

ALL COMMUNICATIONS TO:  
**THE GENERAL MANAGER**  
**PO BOX 262**  
**TEMORA NSW 2666**

TEL: 02-6980 1100  
FAX: 02-6980 1138  
E: [temshire@temora.nsw.gov.au](mailto:temshire@temora.nsw.gov.au)

## PLANNING CERTIFICATE S10.7 (2) Environmental Planning and Assessment Act 1979

*Applicant:* **JK Environments**

**C/- JK Geotechnics**

**115 Wicks Road**

**MACQUARIE PARK NSW 2113**

*Applicant Ref:*

*Certificate No:* **60/2023**

*Fees:* **\$62.00**

*Receipt No:* **277086**

### Description of Land

House No/Name: **169-189**

Locality: **Temora**

Lot No: **2**

Owner: **Health Administration Corporation**

Address: **C/- Murrumbidgee Local Health**

**Locked Bag 10**

**WAGGA WAGGA NSW 2650**

Street: **Loftus**

Council's Assessment No: **2387**

Section:

DP: **572392**



© Temora Shire Council.

© LPI Department of Finance and Services, Panorama Avenue, Bathurst, 2795. [www.lpi.nsw.gov.au](http://www.lpi.nsw.gov.au).

While every care is taken to ensure the accuracy of this product, Temora Shire Council and the Local / State / Federal Government departments and Non-Government organisations whom supply datasets, make no representations or warranties about its accuracy, reliability, completeness or suitability for any particular purpose and disclaims all responsibility and all liability (including without limitation, liability in negligence) for all expenses, losses, damages (including indirect or consequential damage) and costs which you might incur as a result of the product being inaccurate or incomplete in any way and for any reason.

**1. Names of relevant planning instruments and development control plans:**

**(a) Name of any Local Environmental Plan (LEP) that applies to the land and the date when that planning instrument took effect:**

Temora Local Environmental Plan 2010 – 10<sup>th</sup> June, 2010  
(As amended 9<sup>th</sup> March, 2022)

**(b) Name of any DRAFT Local Environmental Plan (LEP) that applies to the land:**

Nil

**(c) Name of any Development Control Plan (DCP) that applies to the land:**

Temora Shire Development Control Plan 2012

**(d) Name of any Development Control Plan (DCP) prepared by the Director-General:**

Nil

**(e) Name of any State Environmental Planning Policy (SEPP) that applies to the land:**

- State Environmental Planning Policy (Biodiversity and Conservation) 2021
- State Environmental Planning Policy (Building Sustainability Index: BASIX) 2004
- State Environmental Planning Policy (Exempt and Complying Development Codes) 2008
- State Environmental Planning Policy (Housing) 2021
- State Environmental Planning Policy (Industry and Employment) 2021
- State Environmental Planning Policy 65 – Design Quality of Residential Flat Development.
- State of Environmental Planning Policy (Planning Systems) 2021
- State of Environmental Planning Policy (Precincts - Regional) 2021
- State Environmental Planning Policy (Primary Production) 2021
- State Environmental Planning Policy (Resilience and Hazards) 2021
- State Environmental Planning Policy (Resources and Energy) 2021
- State Environmental Planning Policy (Transport and Infrastructure) 2021

**2. Zoning and Land Use under relevant planning instruments:**

**(a) The land is within Zone:**

Zone SP2 Infrastructure

**(b) Objectives of this Zone:**

- To provide for infrastructure and related uses.
- To prevent development that is not compatible with or that may detract from the provision of infrastructure.

**(c) The types of development that may be carried out in Zone SP2 Infrastructure without development consent:**

Roads.

**(d) The types of development that may not be carried out in Zone SP2 Infrastructure except with development consent:**

The purpose shown on the Land Zoning Map, including any development that is ordinarily incidental or ancillary to development for that purpose.

**(e) The types of development that are PROHIBITED in Zone SP2 Infrastructure:**

Any developments not specified in item (c) & (d)

**(f) Whether the lands' dimensions are such as to permit the erection of a dwelling-house on the land, and if so, the minimum land dimensions so fixed:**

Not Permitted

**(g) Whether the land includes or comprises critical habitat:**

No

**(h) Whether the land is in a conservation area:**

No

**(i) Whether an item of environmental heritage is situated on the land:**

No

**3. Contribution Plans:**

**(a) The following contribution plans apply to the land:**

Temora Shire Developer Contributions Plan 2020

**4. Complying Development:**

**(a) Whether the land subject of this Certificate, is land on which complying development may be carried out under each of the codes for complying development because of the provisions of clause 1.17A(1)(c)-(e), (2), (3) or (4), 1.18(1) (c3) or 1.19 of the State Environmental Planning Policy (Exempt and Complying Development Codes, 2008)**

No – Complying development under the Housing Code, Rural Housing Code, General Development Code, Commercial and Industrial Alterations Code, Commercial and

Industrial (New Buildings and Alterations) Code, Container Recycling Facilities Code, Subdivisions Code, Demolition Code and Fire Safety Code may not be carried out on this land. This land is excluded from the SEPP because it is land that is reserved for a public purpose in an environmental planning instrument and/or land that is bushfire prone and/or a flood control lot and/or is a site of historical significance.

## 5. Exempt Development:

**(a) Whether the land subject of this Certificate, is land on which exempt development may be carried out under the codes for exempt development because of the provisions of clause 1.16(1) (b1)-(d) or 1.16A of the State Environmental Planning Policy (Exempt and Complying Development Codes, 2008)**

Yes – Exempt development under the Exempt Development Codes may be carried out on this land.

## 6. Affected building notices and building product rectification orders:

**(a) Whether there is any affected building notice of which the Council is aware in force in respect of the land**

Temora Shire Council is not aware of any affected building notice that is in force in respect of the land.

**(b) Whether there is any building product rectification order of which the Council is aware in force in respect of the land and has not been fully complied with**

Temora Shire Council is not aware of any building rectification order that is in force in respect of the land that has not been fully complied with.

**(c) Whether there is any notice of intention to make a building product rectification order of which the council is aware has been given in respect of the land and is outstanding**

Temora Shire has not been advised of any intention to make a building product rectification order in respect of the land

## 7. Land Reserved for Acquisition:

**(a) Whether the land is subject to acquisition by a public authority under any planning instrument or draft planning instrument:**

The land is NOT affected by any environmental planning instrument or proposed environmental planning instrument referred to Clause 1 that makes provision in relation to the acquisition of the land by a public authority referred to in Section 3.15 of the Act.

## 8. Road Widening and Road Realignment:

**(a) Whether the land is affected by any road widening and road realignment proposals under Division 2 of Part 3 of the Roads Act 1993, any Environmental Planning Instrument or any resolution of the Council:**

(i) The land is NOT affected by any road widening or realignment under:

- Division 2 of Part 3 of the Roads Act, 1993
- Provisions of the Temora Local Environmental Plan, 2010
- Any resolution of Council.

## 9. Flood related development controls:

**(a) Is the land or part of the land within the flood planning area and subject to flood related development controls:**

No

**(b) Is the land or part of the land is between the flood planning area and the probable maximum flood and subject to floor related development controls:**

No

**10. Council and other public authority policies on hazard risk restrictions:**

**(a) Whether any of the land is affected by an adopted policy that restricts the development of the land because of the likelihood of land slip, bush fire, tidal inundation, subsidence, acid sulfate soils, contamination, aircraft noise, salinity, coastal hazards, sea level rise or another risk, other than flooding:**

No

**11. Bushfire Prone Land:**

**(a) Is the land identified as Bushfire Prone Land:**

The land is NOT bushfire prone land.

**12. Loose fill asbestos insulation:**

**(a) If the land includes any residential premises (within the meaning of Division 1 A of Part 8 of the Home Building Act 1989) that are listed on the register that is required to be maintained under that Division:**

Temora Shire Council is not aware of any listing on the register of any residential premises on the land.

**13. Mine Subsidence:**

**(a) Whether the land has been proclaimed to be within a mine subsidence district under Section 15 of the *Mine Subsidence Compensation Act*:**

Unknown

**14. Paper subdivision information:**

**(a) The name of any development plan adopted by the relevant authority that applies to the land:**

There is no paper subdivision development plan adopted by the relevant authority that applies to the land.

**15. Property Vegetation Plans**

**(a) Whether the land to which the certificate relates has a property vegetation plan approved under Part 4 of the Native Vegetation Act 2003:**

Temora Shire Council has not been advised by Local Land Services of the existence of a property vegetation plan relating to this land, by a person or body that approves plans under the Act.

## 16. Biodiversity Stewardship Sites:

**(a) Whether the land to which the certificate relates has a Biodiversity Stewardship site under a biodiversity stewardship agreement under Part 5 of the Biodiversity Conservation Act 2016:**

Temora Shire Council has not been advised by the Chief Executive of the Office of Environment and Heritage of the existence of a Biodiversity Stewardship Agreement relating to this land.

## 17. Biodiversity Certified Land

**(a) Whether the land is biodiversity certified under Part 8 of the Biodiversity Conservation Act 2016:**

The land is NOT biodiversity certified.

## 18. Orders under Trees (Disputes Between Neighbours) Act, 2006:

**(a) Whether an order has been made under the Trees (Disputes Between Neighbours) Act, 2006 to carry out work in relation to a tree on the land (but only to the extent Council has been notified of the order:**

The land is NOT land to which an order under Trees (Disputes Between Neighbours) Act, 2006 applies.

## 19. Annual charges under Local Government Act 1993 for coastal protection services that relate to existing coastal protection works:

**(a) If the [Coastal Management Act 2016](#) applies to the council**

Not applicable

## 20. State Environmental Planning Policy (Western Sydney Aerotropolis) 2020

**(a) Whether under [State Environmental Planning Policy \(Precincts–Western Parkland City\) 2021](#), applies to the council**

Not applicable

## 21. Development consent conditions for seniors housing:

**(a) If [State Environmental Planning Policy \(Housing\) 2021](#), Chapter 3, Part 5 applies to the land, any conditions of a development consent granted after 11 October 2007 in relation to the land that are of the kind set out in that Policy, section 88(2):**

Not applicable

**22. Site compatibility certificates and development consent conditions for Affordable Rental Housing:**

**(a) Whether there is a valid site compatibility certificate under State Environmental Planning Policy (Housing) 2021, of which Council is aware in relation to affordable housing in respect of proposed development on the land:**

The land is NOT subject to a valid site compatibility certificate for affordable rental housing.

**(b) Whether there are any conditions of a development consent in relation to section 21(1) or 40(1) in that Policy in respect to proposed development on the land:**

Not applicable

This certificate provides prescribed and other relevant information affecting how land may be used including certain restrictions on its development. The Certificate contains information Council is aware of through its records and environmental plans, along with data supplied by the State Government. The information is provided in good faith subject to sections 145B and 149(6) of the Environmental Planning and Assessment Act 1979. The above information has been taken from the Council's records but Council cannot accept any responsibility for any omission or inaccuracy.

Date: 28-Mar-23

Shire of Temora

Director of Environmental Services:.....  
For the General Manager



---

*Any request for further information in connection with the above should be marked for attention of Mr KJ Dunstan, Telephone No: 02 6980 1100*

**GENERAL NOTE**

The *Environmental Planning and Assessment Amendment Act 2018* commenced operation on 1<sup>st</sup> March, 2018. As a consequence of the Act the information contained in this certificate needs to be read in conjunction with the provisions of the Environmental Planning and Assessment Regulation 2000.



Our reference:

Certificate No: 60/2023

**INFORMATION SUPPLIED PURSUANT TO SECTION 10.7(5) OF THE ACT**

**OWNER RECORDED BY COUNCIL:**

HEALTH ADMINISTRATION CORPORATION  
C/- MURRUMBIDGEE LOCAL HEALTH DISTRICT  
LOCKED BAG 10  
WAGGA WAGGA NSW 2650

**PROPERTY DESCRIPTION:**

Lot 2; DP 572392  
169-189 LOFTUS STREET  
TEMORA NSW 2666

a.	Has any development consent with respect to the land been granted within the last two (2) years?	No
b.	What is the current approved use of the property?	SP2 Infrastructure
c.	Is the current use of the property in accordance with such approval?	Yes
d.	Is the land affected by any resolution of the Council to seek amendment to any environmental planning instrument or draft environmental planning instrument applying to the land?	No
e.	Is the land subject of this Certificate, land on which complying development can be carried out under the provisions of SEPP Exempt and complying Development Codes 2008?	Yes

- The above information has been taken from the Council's records but council cannot accept responsibility for any omission or inaccuracy.

\$94.00

27/03/2023

**Fees Paid**

**Date Paid**

  
KJ Dunstan  
DIR. ENVIRONMENTAL SERVICES  
For the **GENERAL MANAGER**





---

## **SafeWork NSW Records**

**Natalie Froud**

---

**From:** Licensing <licensing@safework.nsw.gov.au>  
**Sent:** Thursday, 6 April 2023 6:51 AM  
**To:** Craig Ridley  
**Subject:** SafeWork NSW: 00820831 –Site Search application – Result found [ ref:\_00D281hl6J.\_500Mn44npx:ref ]

This message originated outside the JKG network. If this looks to be from a staff member, it is likely to be malicious (spam/phish attack). Do not click links or open attachments unless you recognise the sender and know the content is safe.

---

**Security Classification: Sensitive Personal**  
**Please do not amend the subject line of this email**

Dear Craig,

**Re: Site Search for Schedule 11 Hazardous Chemicals on premises Application – Result found.**

I refer to your application for a Site Search for Schedule 11 Hazardous Chemicals on premises, received by SafeWork NSW on 28/03/2023 for the following site: 169-198 Loftus Street Temora NSW 2666.

Please find attached copies of the documents that SafeWork NSW holds on record number 35/028071 relating to the storage of Hazardous Chemicals at the above-mentioned premises.

If you have any further information or if you have any questions, please use one of the following options, quoting the SafeWork NSW enquiry reference number: 00820831

- Email: [licensing@safework.nsw.gov.au](mailto:licensing@safework.nsw.gov.au)
- Phone: 13 10 50

Kind regards

**Mo Lotonuu**

SafeWork NSW | Better Regulation Division

Department of Customer Service

p- 13 10 50

e- [licensing@safework.nsw.gov.au](mailto:licensing@safework.nsw.gov.au) | [www.customerservice.nsw.gov.au](http://www.customerservice.nsw.gov.au)

Level 3, 32 Mann Street, Gosford, NSW 2250



We are always looking for ways that we can improve our services. You may be contacted by email in the next few weeks to complete a short survey and provide us with your feedback on what we did well and where we can improve. If you do not wish to participate in our surveys, please email us at: [licensingQA@customerservice.nsw.gov.au](mailto:licensingQA@customerservice.nsw.gov.au) and we will ensure that you are not contacted.

[169-198 Loftus Street Temora NSW 2666 - File 1.pdf](#)

[169-198 Loftus Street Temora NSW 2666 - Site Maps.pdf](#)



ref:\_00D281hl6J.\_500Mn44npx:ref

**WORKCOVER AUTHORITY  
DANGEROUS GOODS ACT, 1975**

LICENCE No. 35 028071

APPLICATION FOR LICENCE (or AMENDMENT or TRANSFER of LICENCE) FOR THE KEEPING OF DANGEROUS GOODS

Plan: 085



checked

(\* Delete whichever is not required)

Name of Applicant in full (see Item 1 - Explanatory notes - page 4)	TEMORA + DISTRICT HOSPITAL		
Trading name or occupier's name (if any)			
Postal Address	PO Box 172 TEMORA	Postcode	2666
Address of the premises to be licensed. (Including Street No.)	LOFTUS ST TEMORA	Postcode	2666
Nature of premises (See Item 2 - Explanatory notes - page 4)	PUBLIC HOSPITAL		
Telephone number of applicant	STD Code 069	Number	771066

Particulars of type of depots and maximum quantities of dangerous goods to be kept at any one time.

Depot number	Type of depot (See item 3 - Explanatory notes - page 4)	Storage capacity	Dangerous goods	C & C Office use only
			Product being stored	
1	Above ground	1x 7.5 KL	L.P.G	
2	Tank	1x 2.75 KL	L.P.G	
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				

DATA  
- 5 JAN 1993  
ENTERED

4 DEC 1992  
WAGGA WAGGA

SCIENTIFIC SERVICES  
BRANCH  
18 FEB 1994  
DANGEROUS  
GOODS

Has site plan been approved by the Dangerous Goods Branch? Yes  No  If yes, no plans required. If no please attach site plan, or provide sketch plan overleaf.

Have premises previously been licensed? Yes  No  If yes, state name of previous occupier, and licence No. (if known)

Name of oil company supplying flammable liquid (if applicable)

TEMORA + DISTRICT HOSPITAL

Signature of applicant: *[Signature]* Date: 6-11-92

CHIEF EXECUTIVE OFFICER

FOR OFFICE USE ONLY

**CERTIFICATE OF INSPECTION**

I, being an Inspector under the Dangerous Goods Act, 1975, do hereby certify that the premises described above do comply with the requirements of the Dangerous Goods Act, 1975, and the Dangerous Goods Regulation with regard to their situation and construction for the keeping of dangerous goods of the

Complete 1 section per depot

**If you have more depots than the space provided, photocopy sufficient sheets first.**

Depot number	Type of depot	Class		Licensed maximum storage capacity		
1	Above Ground Tank	2.1		7,500	litres	
UN number	Shipping name	Pkg. Class Group	EPG	Product or common name	Typical quantity	Uniteg. L, kg, m <sup>3</sup>
X1075	Propane	2.1		LPGas	6800 <del>7500</del>	litre

Depot number	Type of depot	Class		Licensed maximum storage capacity		
2	Above Ground tank	2.1				
UN number	Shipping name	Pkg. Class Group	EPG	Product or common name	Typical quantity	Uniteg. L, kg, m <sup>3</sup>
X1075	Propane	2.1		LPGas	2300	litre

Depot number	Type of depot	Class		Licensed maximum storage capacity		
UN number	Shipping name	Pkg. Class Group	EPG	Product or common name	Typical quantity	Uniteg. L, kg, m <sup>3</sup>

Depot number	Type of depot	Class		Licensed maximum storage capacity		
UN number	Shipping name	Pkg. Class Group	EPG	Product or common name	Typical quantity	Uniteg. L, kg, m <sup>3</sup>

**\*\* CONDITIONAL LICENCE \*\***

WorkCover New South Wales, 400 Kent Street, Sydney 2000. Telephone 370 5000 ALL MAIL TO LOCKED BAG 10, CLARENCE STREET SYDNEY 2000

Reference

**SCIENTIFIC SERVICES BRANCH**  
Dangerous Goods Licensing  
ph. (02) 370 5187 fax (02) 370 6105



**Licensee** RIVERINA HEALTH SERVICE  
TEMORA & DISTRICT HOSPITAL  
BOX 172 P O  
TEMORA 2666

**LICENCE FOR THE KEEPING OF DANGEROUS GOODS**

ISSUED UNDER AND SUBJECT TO THE PROVISIONS OF THE DANGEROUS GOODS ACT, 1975 AND REGULATION THEREUNDER

**Licence Number** 35/028071      **Expiry Date** 22/01/96      **No. of Depots** 2

**Licencee Contact** J Hingerty Ph. 069 77 1066 Fax. 069 771 545

**Premises Licensed to Keep Dangerous Goods**  
LOFTUS ST & GLOUCESTER ST  
TEMORA 2666

**Nature of Site** HOSPITALS (EXCEPT PSYCHIATRIC HOSPITALS)

**Emergency Contact for this Site** J Hingerty 069 771 066 24 hrs 7 days

**Major Supplier of Dangerous Goods** BORAL

**DETAILS OF DEPOTS**

Depot No.	Depot Type	Goods Stored in Depot	Qty
1	ABOVEGROUND TANK	Class 2.1 UN 1075 PETROLEUM GASES, LIQUE	7500 L 6800 L
2	ABOVEGROUND TANK	Class 2.1 UN 1075 PETROLEUM GASES, LIQUE	2750 L 2300 L

**\*\* Licence has been issued on condition that an A4 size site sketch is submitted to WorkCover by 27 October 1995. \*\***

**PLEASE RETAIN AS PROOF OF LICENCE**

Issued by Chief Inspector of Dangerous Goods on 27 September 1995

# TEMORA AND DISTRICT HOSPITAL





## Legend

### Buildings

- 1 Main Hospital Building
- 2 Day Care Centre
- 3 Engineering and Maintenance
- 4 Boiler Room
- 5 Mortuary
- 6 Nurses Home
- 7 Water Treatment Plant
- 8 Carport
- 9 TENNIS COURT
- 10 B.B.Q

### Entries

- A Main Entry
- B Ambulance Entry
- C Pathology Entry
- D Service Entry
- E Rear Entry
- F Outpatient Entry
- G 142 GAS STORAGE
- H INFECTIONOUS WASTE
- I 142 OXYGEN CYLINDERS

-  LAWNS AND GARDENS MAINTAINED BY T. D. H.
-  FIRE HYDRANTS.

exit

Gloucester Street

Greenstone Lodge

Temora Reservoirs

Loftus Street

Main Entry

ATF

~~1685 CTS 4701~~



### APPLICATION FOR RENEWAL OF LICENCE TO KEEP DANGEROUS GOODS

ISSUED UNDER AND SUBJECT TO THE PROVISIONS OF THE DANGEROUS GOODS ACT, 1975 AND REGULATION THEREUNDER

**DECLARATION:** Please renew licence number 35/028071 to 1999. I confirm that all the licence details shown below are correct (amend if necessary).

*Paul Morrow* ..... *Paul Morrow* ..... *20/5/98* .....  
 (Signature) (Please print name) (Date signed)  
 for: RIVERINA HEALTH SERVICE  
 GREATER MURRAY HEALTH SERVICE

**THIS SIGNED DECLARATION SHOULD BE RETURNED TO:**  
 WorkCover New South Wales  
 Dangerous Goods Licensing Section (Level 3)  
 Locked Bag 10  
 P O CLARENCE STREET 2000

Enquiries: ph (02) 9370 5187  
 fax (02) 9370 6105



**Details of licence on 5 December 1997**

Licence Number 35/028071      Expiry Date 22/01/98  
 Licensee ~~RIVERINA HEALTH SERVICE GREATER MURRAY HEALTH SERVICE~~  
 TEMORA & DISTRICT HOSPITAL  
 Postal Address BOX 172 P O, TEMORA 2666  
 Licensee Contact ~~J Hingerty Ph. 069 77 1066 Fax. 069 771 545~~  
 Premises Licensed to Keep Dangerous Goods  
 LOFTUS ST & GLOUCESTER ST  
 TEMORA 2666  
 Nature of Site HOSPITALS (EXCEPT PSYCHIATRIC HOSPITALS) Major Supplier of Dangerous Goods  
 BORAL  
 Emergency Contact for this Site ~~J Hingerty ph. 069 771 066~~  
 Site staffing 24 hrs 7 days

**Details of Depots**

Depot No.	Depot Type	Goods Stored in Depot	Qty
1	ABOVE-GROUND TANK	Class 2.1 UN 1075 PETROLEUM GASES, LIQUE	7500 L 6800 L
2	ABOVE-GROUND TANK	Class 2.1 UN 1075 PETROLEUM GASES, LIQUE	2750 L 2300 L



*Paul Morrow*  
*Act Network Eng*  
*Ph 02 69 386664*

*22 MAY 1998*  
*licence renewed on SCIDI*  
*db*









---

## **Appendix C: Laboratory Results Summary Tables**

## ABBREVIATIONS AND EXPLANATIONS

### Abbreviations used in the Tables:

<b>ABC:</b>	Ambient Background Concentration	<b>PCBs:</b>	Polychlorinated Biphenyls
<b>ACM:</b>	Asbestos Containing Material	<b>PCE:</b>	Perchloroethylene (Tetrachloroethylene or Tetrachloroethene)
<b>ADWG:</b>	Australian Drinking Water Guidelines	<b>pH<sub>KCL</sub>:</b>	pH of filtered 1:20, 1M KCL extract, shaken overnight
<b>AF:</b>	Asbestos Fines	<b>pH<sub>ox</sub>:</b>	pH of filtered 1:20 1M KCL after peroxide digestion
<b>ANZG:</b>	Australian and New Zealand Guidelines	<b>PQL:</b>	Practical Quantitation Limit
<b>B(a)P:</b>	Benzo(a)pyrene	<b>RS:</b>	Rinsate Sample
<b>CEC:</b>	Cation Exchange Capacity	<b>RSL:</b>	Regional Screening Levels
<b>CRC:</b>	Cooperative Research Centre	<b>RSW:</b>	Restricted Solid Waste
<b>CT:</b>	Contaminant Threshold	<b>SAC:</b>	Site Assessment Criteria
<b>EILs:</b>	Ecological Investigation Levels	<b>SCC:</b>	Specific Contaminant Concentration
<b>ESLs:</b>	Ecological Screening Levels	<b>S<sub>C</sub>:</b>	Chromium reducible sulfur
<b>FA:</b>	Fibrous Asbestos	<b>S<sub>POS</sub>:</b>	Peroxide oxidisable Sulfur
<b>GIL:</b>	Groundwater Investigation Levels	<b>SSA:</b>	Site Specific Assessment
<b>GSW:</b>	General Solid Waste	<b>SSHSs:</b>	Site Specific Health Screening Levels
<b>HILs:</b>	Health Investigation Levels	<b>TAA:</b>	Total Actual Acidity in 1M KCL extract titrated to pH6.5
<b>HSLs:</b>	Health Screening Levels	<b>TB:</b>	Trip Blank
<b>HSL-SSA:</b>	Health Screening Level-Site Specific Assessment	<b>TCA:</b>	1,1,1 Trichloroethane (methyl chloroform)
<b>kg/L</b>	kilograms per litre	<b>TCE:</b>	Trichloroethylene (Trichloroethene)
<b>NA:</b>	Not Analysed	<b>TCLP:</b>	Toxicity Characteristics Leaching Procedure
<b>NC:</b>	Not Calculated	<b>TPA:</b>	Total Potential Acidity, 1M KCL peroxide digest
<b>NEPM:</b>	National Environmental Protection Measure	<b>TS:</b>	Trip Spike
<b>NHMRC:</b>	National Health and Medical Research Council	<b>TRH:</b>	Total Recoverable Hydrocarbons
<b>NL:</b>	Not Limiting	<b>TSA:</b>	Total Sulfide Acidity (TPA-TAA)
<b>NSL:</b>	No Set Limit	<b>UCL:</b>	Upper Level Confidence Limit on Mean Value
<b>OCP:</b>	Organochlorine Pesticides	<b>USEPA</b>	United States Environmental Protection Agency
<b>OPP:</b>	Organophosphorus Pesticides	<b>VOCC:</b>	Volatile Organic Chlorinated Compounds
<b>PAHs:</b>	Polycyclic Aromatic Hydrocarbons	<b>WHO:</b>	World Health Organisation
<b>%w/w:</b>	weight per weight		
<b>ppm:</b>	Parts per million		

### Table Specific Explanations:

#### HIL Tables:

- The chromium results are for Total Chromium which includes Chromium III and VI. For initial screening purposes, we have assumed that the samples contain only Chromium VI unless demonstrated otherwise by additional analysis.
- Carcinogenic PAHs is a toxicity weighted sum of analyte concentrations for a specific list of PAH compounds relative to B(a)P. It is also referred to as the B(a)P Toxic Equivalence Quotient (TEQ).

#### EIL/ESL Table:

- ABC Values for selected metals have been adopted from the published background concentrations presented in Olszowy et. al., (1995), Trace Element Concentrations in Soils from Rural and Urban New South Wales (the 25th percentile values for old suburbs with low traffic have been quoted).

#### Waste Classification and TCLP Table:

- Data assessed using the NSW EPA Waste Classification Guidelines, Part 1: Classifying Waste (2014).
- The assessment of Total Moderately Harmful pesticides includes: Dichlorovos, Dimethoate, Fenthion, Fenitrothion, Ethion, Malathion, Methidathion and Parathion Methyl.
- Assessment of Total Scheduled pesticides include: HBC, alpha-BHC, gamma-BHC, beta-BHC, Heptachlor, Aldrin, Heptachlor Epoxide, gamma-Chlordane, alpha-chlordane, pp-DDE, Dieldrin, Endrin, pp-DDD, pp-DDT, Endrin Aldehyde.

#### QA/QC Table:

- Field blank, Inter and Intra laboratory duplicate results are reported in mg/kg.
- Trip spike results are reported as percentage recovery.
- Field rinsate results are reported in µg/L.

TABLE S1 SOIL LABORATORY RESULTS COMPARED TO NEPM 2013. HIL-A: 'Residential with garden/accessible soils; children's day care centers; preschools; and primary schools'																						
All data in mg/kg unless stated otherwise			HEAVY METALS							PAHs		ORGANOCHLORINE PESTICIDES (OCPs)							OP PESTICIDES (OPPs)	TOTAL PCBs	ASBESTOS FIBRES	
			Arsenic	Cadmium	Chromium	Copper	Lead	Mercury	Nickel	Zinc	Total PAHs	Carcinogenic PAHs	HCB	Endosulfan	Methoxychlor	Aldrin & Dieldrin	Chlordane	DDT, DDD & DDE	Heptachlor	Chlorpyrifos		
PQL - Envirolab Services			4	0.4	1	1	1	0.1	1	1	-	0.5	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1
Site Assessment Criteria (SAC)			100	20	100	6000	300	40	400	7400	300	3	10	270	300	6	50	240	6	160	1	Detected/Not Detected
Sample Reference	Sample Depth	Sample Description																				
BH1	0-0.3	Silty Clay	<4	<0.4	<b>37</b>	<b>70</b>	<b>7</b>	<0.1	<b>10</b>	<b>22</b>	<b>0.2</b>	<0.5	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
BH1 - [LAB_DUP]	0-0.3	Laboratory Duplicate	<4	<0.4	<b>38</b>	<b>70</b>	<b>9</b>	<0.1	<b>10</b>	<b>25</b>	<b>0.55</b>	<0.5	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
BH1	0.8-1.0	XW Andersite	<4	<0.4	<b>62</b>	<b>130</b>	<b>9</b>	<0.1	<b>14</b>	<b>31</b>	<0.05	<0.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
BH2	0-0.2	F: Gravelly Sandy Clay	<b>6</b>	<0.4	<b>38</b>	<b>200</b>	<b>8</b>	<0.1	<b>11</b>	<b>36</b>	<b>6.9</b>	<b>1</b>	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
BH2	0.3-0.5	Sandy Silty Clay	<b>6</b>	<0.4	<b>91</b>	<b>280</b>	<b>5</b>	<0.1	<b>18</b>	<b>37</b>	<0.05	<0.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
BH2	0.8-1.0	Silty Clay	<b>6</b>	<0.4	<b>63</b>	<b>200</b>	<b>6</b>	<0.1	<b>13</b>	<b>30</b>	<0.05	<0.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
BH3	0-0.1	F: Silty Clay	<b>7</b>	<0.4	<b>23</b>	<b>57</b>	<b>12</b>	<0.1	<b>9</b>	<b>24</b>	<b>0.64</b>	<0.5	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
BH3	0.3-0.5	F: Sandy Silty Clay	<b>8</b>	<0.4	<b>47</b>	<b>86</b>	<b>15</b>	<b>0.2</b>	<b>11</b>	<b>33</b>	<b>85</b>	<b>7.7</b>	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
BH3	1.3-1.5	Sandy Silty Clay	<b>4</b>	<0.4	<b>72</b>	<b>120</b>	<b>9</b>	<0.1	<b>12</b>	<b>22</b>	<b>3.3</b>	<0.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
BH4	0-0.1	F: Silty Clay	<b>5</b>	<0.4	<b>30</b>	<b>82</b>	<b>28</b>	<0.1	<b>7</b>	<b>53</b>	<b>0.66</b>	<0.5	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
BH4 - [LAB_DUP]	0-0.1	Laboratory Duplicate	<b>5</b>	<0.4	<b>28</b>	<b>80</b>	<b>26</b>	<0.1	<b>6</b>	<b>53</b>	<b>0.5</b>	<0.5	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
BH4	0.3-0.5	Sandy Silty Clay	<b>7</b>	<0.4	<b>18</b>	<b>300</b>	<b>3</b>	<0.1	<b>11</b>	<b>31</b>	<0.05	<0.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
BH4	0.8-1.0	XW Andersite	<b>6</b>	<0.4	<b>16</b>	<b>210</b>	<b>2</b>	<0.1	<b>9</b>	<b>24</b>	<0.05	<0.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
BH5	0-0.1	Silty Clay	<b>9</b>	<0.4	<b>26</b>	<b>230</b>	<b>13</b>	<0.1	<b>9</b>	<b>30</b>	<b>2.9</b>	<0.5	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
BH5	0.8-1.0	Silty Clay	<b>4</b>	<0.4	<b>52</b>	<b>180</b>	<b>7</b>	<0.1	<b>12</b>	<b>20</b>	<0.05	<0.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
BH6	0-0.1	F: Silty Clay	<4	<0.4	<b>22</b>	<b>220</b>	<b>17</b>	<0.1	<b>9</b>	<b>54</b>	<0.05	<0.5	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
BH6	0.3-0.5	Sandy Silty Clay	<4	<0.4	<b>19</b>	<b>440</b>	<b>3</b>	<0.1	<b>10</b>	<b>51</b>	<0.05	<0.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
BH6	0.8-1.0	XW Andersite	<4	<0.4	<b>16</b>	<b>400</b>	<b>1</b>	<0.1	<b>9</b>	<b>55</b>	<0.05	<0.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
BH7	0.02-0.3	F: Gravelly Silty Sand	<b>7</b>	<0.4	<b>36</b>	<b>94</b>	<b>24</b>	<0.1	<b>9</b>	<b>36</b>	<0.05	<0.5	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
BH7 - [LAB_DUP]	0.02-0.3	Laboratory Duplicate	<b>6</b>	<0.4	<b>51</b>	<b>100</b>	<b>20</b>	<0.1	<b>11</b>	<b>34</b>	<0.05	<0.5	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
BH7	0.3-0.5	F: Silty Sand	<b>7</b>	<0.4	<b>66</b>	<b>120</b>	<b>10</b>	<b>0.6</b>	<b>13</b>	<b>29</b>	<0.05	<0.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
BH8	0.02-0.2	F: Silty Sand	<4	<0.4	<b>13</b>	<b>12</b>	<b>7</b>	<0.1	<b>2</b>	<b>7</b>	<b>27</b>	<b>3.6</b>	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
BH8	0.3-0.5	Sandy Silty Clay	<4	<0.4	<b>53</b>	<b>170</b>	<b>7</b>	<0.1	<b>15</b>	<b>42</b>	<b>3.3</b>	<0.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
TP13	0-0.1	F: Silty Clay	<b>5</b>	<0.4	<b>20</b>	<b>210</b>	<b>22</b>	<b>0.1</b>	<b>8</b>	<b>59</b>	<b>0.2</b>	<0.5	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
TP13	0.5-0.6	Silty Clay	<b>7</b>	<0.4	<b>24</b>	<b>490</b>	<b>4</b>	<0.1	<b>11</b>	<b>28</b>	<0.05	<0.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
TP14	0-0.1	F: Silty Clay	<b>15</b>	<0.4	<b>31</b>	<b>99</b>	<b>120</b>	<b>0.1</b>	<b>3</b>	<b>88</b>	<b>1.1</b>	<0.5	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
TP14	0.4-0.5	Silty Clay	<4	<0.4	<b>17</b>	<b>420</b>	<b>6</b>	<0.1	<b>10</b>	<b>57</b>	<b>0.5</b>	<0.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
TP14	0.9-1.0	XW Andersite	<4	<0.4	<b>10</b>	<b>470</b>	<b>2</b>	<0.1	<b>10</b>	<b>47</b>	<0.05	<0.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
TP15	0-0.1	F: Silty Clay	<b>6</b>	<0.4	<b>21</b>	<b>34</b>	<b>12</b>	<0.1	<b>7</b>	<b>30</b>	<b>0.3</b>	<0.5	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
TP15 - [LAB_DUP]	0-0.1	Laboratory Duplicate	<b>5</b>	<0.4	<b>19</b>	<b>29</b>	<b>12</b>	<0.1	<b>7</b>	<b>30</b>	<b>0.2</b>	<0.5	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
TP15	0.9-1.0	F: Sandy Silty Clay	<b>7</b>	<0.4	<b>24</b>	<b>32</b>	<b>14</b>	<0.1	<b>5</b>	<b>11</b>	<b>43</b>	<b>4.9</b>	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
TP15	1.3-1.5	Silty Clay	<4	<0.4	<b>52</b>	<b>110</b>	<b>7</b>	<b>0.7</b>	<b>9</b>	<b>18</b>	<0.05	<0.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
TP16	0-0.1	Silty Clay	<b>10</b>	<0.4	<b>56</b>	<b>190</b>	<b>25</b>	<0.1	<b>14</b>	<b>61</b>	<b>1.4</b>	<0.5	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
TP16	0.4-0.5	Silty Clay	<b>5</b>	<0.4	<b>74</b>	<b>180</b>	<b>4</b>	<0.1	<b>15</b>	<b>27</b>	<0.05	<0.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
SDUP1	0-0.1	Duplicate of TP16	<b>10</b>	<0.4	<b>55</b>	<b>190</b>	<b>25</b>	<0.1	<b>14</b>	<b>66</b>	<b>1.7</b>	<0.5	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
SDUP2	0-0.1	Duplicate of TP15	<b>6</b>	<0.4	<b>20</b>	<b>31</b>	<b>12</b>	<0.1	<b>7</b>	<b>29</b>	<b>0.1</b>	<0.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
SDUP3	0-0.1	Duplicate of TP14	<b>11</b>	<0.4	<b>22</b>	<b>130</b>	<b>170</b>	<0.1	<b>6</b>	<b>140</b>	<b>0.86</b>	<0.5	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
SDUP4	0-0.1	Duplicate of TP13	<b>5</b>	<0.4	<b>16</b>	<b>160</b>	<b>24</b>	<0.1	<b>7</b>	<b>67</b>	<b>0.3</b>	<0.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
SDUP4 - [LAB_DUP]	0-0.1	Laboratory Duplicate	<b>5</b>	<0.4	<b>15</b>	<b>170</b>	<b>19</b>	<0.1	<b>7</b>	<b>60</b>	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
BH4-FCF1	0-0.2	Fragment	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	Detected
BH4-FCF2	0-0.2	Fragment	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	Detected
<b>Total Number of Samples</b>			39	39	39	39	39	39	39	39	38	38	20	20	20	20	20	20	20	20	20	16
<b>Maximum Value</b>			15	<PQL	91	490	170	0.7	18	140	85	7.7	<PQL	<PQL	<PQL	<PQL	<PQL	<PQL	<PQL	<PQL	<PQL	Detected
Concentration above the SAC			<b>VALUE</b>																			
Concentration above the PQL			<b>Bold</b>																			

**TABLE S2**  
**SOIL LABORATORY RESULTS COMPARED TO HSLs**  
 All data in mg/kg unless stated otherwise

						C <sub>6</sub> -C <sub>10</sub> (F1)	>C <sub>10</sub> -C <sub>16</sub> (F2)	Benzene	Toluene	Ethylbenzene	Xylenes	Naphthalene	Field PID Measurement
PQL - EnviroLab Services						25	50	0.2	0.5	1	1	1	ppm
NEPM 2013 HSL Land Use Category						<b>HSL-A/B: LOW/HIGH DENSITY RESIDENTIAL</b>							
Sample Reference	Sample Depth	Sample Description	Depth Category	Soil Category									
BH1	0-0.3	Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	0.5
BH1 - [LAB_DUP]	0-0.3	Laboratory Duplicate	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	NA
BH1	0.8-1.0	XW Andersite	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	0.3
BH2	0-0.2	F: Gravelly Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	1.3
BH2	0.3-0.5	Sandy Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	1.9
BH2	0.8-1.0	Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	1.8
BH3	0-0.1	F: Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	0.6
BH3	0.3-0.5	F: Sandy Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<b>2</b>	<1	0.7
BH3	1.3-1.5	Sandy Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	1.5
BH4	0-0.1	F: Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	2.2
BH4 - [LAB_DUP]	0-0.1	Laboratory Duplicate	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	NA
BH4	0.3-0.5	Sandy Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	2
BH4	0.8-1.0	XW Andersite	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	3.8
BH5	0-0.1	Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	0.6
BH5	0.8-1.0	Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	0.6
BH6	0-0.1	F: Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	0.4
BH6	0.3-0.5	Sandy Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	0.1
BH6	0.8-1.0	XW Andersite	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	0.1
BH7	0.02-0.3	F: Gravelly Silty Sand	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	0.8
BH7 - [LAB_DUP]	0.02-0.3	Laboratory Duplicate	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	NA
BH7	0.3-0.5	F: Silty Sand	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	2
BH8	0.02-0.2	F: Silty Sand	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	0
BH8	0.3-0.5	Sandy Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	0.3
TP13	0-0.1	F: Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	0.6
TP13	0.5-0.6	Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	1.3
TP14	0-0.1	F: Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	1
TP14	0.4-0.5	Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	0.5
TP14	0.9-1.0	XW Andersite	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	1.1
TP15	0-0.1	F: Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	0.3
TP15 - [LAB_DUP]	0-0.1	Laboratory Duplicate	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	NA
TP15	0.9-1.0	F: Sandy Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	0.4
TP15	1.3-1.5	Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	0.5
TP16	0-0.1	Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	0.2
TP16	0.4-0.5	Silty Clay	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	1.2
SDUP1	0-0.1	Duplicate of TP16	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	NA
SDUP2	0-0.1	Duplicate of TP15	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	NA
SDUP3	0-0.1	Duplicate of TP14	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	NA
SDUP4	0-0.1	Duplicate of TP13	0m to <1m	Sand	<25	<50	<0.2	<0.5	<1	<1	<1	<1	NA
<b>Total Number of Samples</b>						38	38	38	38	38	38	38	30
<b>Maximum Value</b>						<PQL	<PQL	<PQL	<PQL	<PQL	<PQL	2	3.8

Concentration above the SAC **VALUE**  
 Concentration above the PQL **Bold**  
 The guideline corresponding to the concentration above the SAC is highlighted in grey in the Site Assessment Criteria Table below

**HSL SOIL ASSESSMENT CRITERIA**

Sample Reference	Sample Depth	Sample Description	Depth Category	Soil Category	C <sub>6</sub> -C <sub>10</sub> (F1)	>C <sub>10</sub> -C <sub>16</sub> (F2)	Benzene	Toluene	Ethylbenzene	Xylenes	Naphthalene
BH1	0-0.3	Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH1 - [LAB_DUP]	0-0.3	Laboratory Duplicate	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH1	0.8-1.0	XW Andersite	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH2	0-0.2	F: Gravelly Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH2	0.3-0.5	Sandy Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH2	0.8-1.0	Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH3	0-0.1	F: Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH3	0.3-0.5	F: Sandy Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH3	1.3-1.5	Sandy Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH4	0-0.1	F: Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH4 - [LAB_DUP]	0-0.1	Laboratory Duplicate	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH4	0.3-0.5	Sandy Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH4	0.8-1.0	XW Andersite	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH5	0-0.1	Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH5	0.8-1.0	Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH6	0-0.1	F: Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH6	0.3-0.5	Sandy Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH6	0.8-1.0	XW Andersite	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH7	0.02-0.3	F: Gravelly Silty Sand	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH7 - [LAB_DUP]	0.02-0.3	Laboratory Duplicate	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH7	0.3-0.5	F: Silty Sand	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH8	0.02-0.2	F: Silty Sand	0m to <1m	Sand	45	110	0.5	160	55	40	3
BH8	0.3-0.5	Sandy Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
TP13	0-0.1	F: Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
TP13	0.5-0.6	Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
TP14	0-0.1	F: Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
TP14	0.4-0.5	Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
TP14	0.9-1.0	XW Andersite	0m to <1m	Sand	45	110	0.5	160	55	40	3
TP15	0-0.1	F: Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
TP15 - [LAB_DUP]	0-0.1	Laboratory Duplicate	0m to <1m	Sand	45	110	0.5	160	55	40	3
TP15	0.9-1.0	F: Sandy Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
TP15	1.3-1.5	Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
TP16	0-0.1	Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
TP16	0.4-0.5	Silty Clay	0m to <1m	Sand	45	110	0.5	160	55	40	3
SDUP1	0-0.1	Duplicate of TP16	0m to <1m	Sand	45	110	0.5	160	55	40	3
SDUP2	0-0.1	Duplicate of TP15	0m to <1m	Sand	45	110	0.5	160	55	40	3
SDUP3	0-0.1	Duplicate of TP14	0m to <1m	Sand	45	110	0.5	160	55	40	3
SDUP4	0-0.1	Duplicate of TP13	0m to <1m	Sand	45	110	0.5	160	55	40	3

TABLE S3 SOIL LABORATORY RESULTS COMPARED TO MANAGEMENT LIMITS All data in mg/kg unless stated otherwise						
			C <sub>6</sub> -C <sub>10</sub> (F1) plus BTEX	>C <sub>10</sub> -C <sub>16</sub> (F2) plus naphthalene	>C <sub>16</sub> -C <sub>34</sub> (F3)	>C <sub>34</sub> -C <sub>40</sub> (F4)
PQL - Envirolab Services			25	50	100	100
NEPM 2013 Land Use Category			RESIDENTIAL, PARKLAND & PUBLIC OPEN SPACE			
Sample Reference	Sample Depth	Soil Texture				
BH1	0-0.3	Coarse	<25	<50	<100	<100
BH1 - [LAB_DUP]	0-0.3	Coarse	<25	<50	<100	<100
BH1	0.8-1.0	Coarse	<25	<50	<100	<100
BH2	0-0.2	Coarse	<25	<50	<100	<100
BH2	0.3-0.5	Coarse	<25	<50	<100	<100
BH2	0.8-1.0	Coarse	<25	<50	<100	<100
BH3	0-0.1	Coarse	<25	<50	<b>130</b>	<b>230</b>
BH3	0.3-0.5	Coarse	<25	<50	<b>320</b>	<b>120</b>
BH3	1.3-1.5	Coarse	<25	<50	<100	<100
BH4	0-0.1	Coarse	<25	<50	<100	<100
BH4 - [LAB_DUP]	0-0.1	Coarse	<25	<50	<100	<100
BH4	0.3-0.5	Coarse	<25	<50	<100	<100
BH4	0.8-1.0	Coarse	<25	<50	<100	<100
BH5	0-0.1	Coarse	<25	<50	<100	<100
BH5	0.8-1.0	Coarse	<25	<50	<100	<100
BH6	0-0.1	Coarse	<25	<50	<100	<100
BH6	0.3-0.5	Coarse	<25	<50	<100	<100
BH6	0.8-1.0	Coarse	<25	<50	<100	<100
BH7	0.02-0.3	Coarse	<25	<50	<100	<100
BH7 - [LAB_DUP]	0.02-0.3	Coarse	<25	<50	<100	<100
BH7	0.3-0.5	Coarse	<25	<50	<100	<100
BH8	0.02-0.2	Coarse	<25	<50	<100	<100
BH8	0.3-0.5	Coarse	<25	<50	<100	<100
TP13	0-0.1	Coarse	<25	<50	<100	<100
TP13	0.5-0.6	Coarse	<25	<50	<100	<100
TP14	0-0.1	Coarse	<25	<50	<100	<100
TP14	0.4-0.5	Coarse	<25	<50	<100	<100
TP14	0.9-1.0	Coarse	<25	<50	<100	<100
TP15	0-0.1	Coarse	<25	<50	<100	<100
TP15 - [LAB_DUP]	0-0.1	Coarse	<25	<50	<100	<100
TP15	0.9-1.0	Coarse	<25	<50	<100	<100
TP15	1.3-1.5	Coarse	<25	<50	<100	<100
TP16	0-0.1	Coarse	<25	<50	<100	<100
TP16	0.4-0.5	Coarse	<25	<50	<100	<100
SDUP1	0-0.1	Coarse	<25	<50	<100	<100
SDUP2	0-0.1	Coarse	<25	<50	<100	<100
SDUP3	0-0.1	Coarse	<25	<50	<100	<100
SDUP4	0-0.1	Coarse	<25	<50	<100	<100
<b>Total Number of Samples</b>			38	38	38	38
<b>Maximum Value</b>			<PQL	<PQL	320	230
Concentration above the SAC			<b>VALUE</b>			
Concentration above the PQL			<b>Bold</b>			

MANAGEMENT LIMIT ASSESSMENT CRITERIA

Sample Reference	Sample Depth	Soil Texture	C <sub>6</sub> -C <sub>10</sub> (F1) plus BTEX	>C <sub>10</sub> -C <sub>16</sub> (F2) plus naphthalene	>C <sub>16</sub> -C <sub>34</sub> (F3)	>C <sub>34</sub> -C <sub>40</sub> (F4)
BH1	0-0.3	Coarse	700	1000	2500	10000
BH1 - [LAB_DUP]	0-0.3	Coarse	700	1000	2500	10000
BH1	0.8-1.0	Coarse	700	1000	2500	10000
BH2	0-0.2	Coarse	700	1000	2500	10000
BH2	0.3-0.5	Coarse	700	1000	2500	10000
BH2	0.8-1.0	Coarse	700	1000	2500	10000
BH3	0-0.1	Coarse	700	1000	2500	10000
BH3	0.3-0.5	Coarse	700	1000	2500	10000
BH3	1.3-1.5	Coarse	700	1000	2500	10000
BH4	0-0.1	Coarse	700	1000	2500	10000
BH4 - [LAB_DUP]	0-0.1	Coarse	700	1000	2500	10000
BH4	0.3-0.5	Coarse	700	1000	2500	10000
BH4	0.8-1.0	Coarse	700	1000	2500	10000
BH5	0-0.1	Coarse	700	1000	2500	10000
BH5	0.8-1.0	Coarse	700	1000	2500	10000
BH6	0-0.1	Coarse	700	1000	2500	10000
BH6	0.3-0.5	Coarse	700	1000	2500	10000
BH6	0.8-1.0	Coarse	700	1000	2500	10000
BH7	0.02-0.3	Coarse	700	1000	2500	10000
BH7 - [LAB_DUP]	0.02-0.3	Coarse	700	1000	2500	10000
BH7	0.3-0.5	Coarse	700	1000	2500	10000
BH8	0.02-0.2	Coarse	700	1000	2500	10000
BH8	0.3-0.5	Coarse	700	1000	2500	10000
TP13	0-0.1	Coarse	700	1000	2500	10000
TP13	0.5-0.6	Coarse	700	1000	2500	10000
TP14	0-0.1	Coarse	700	1000	2500	10000
TP14	0.4-0.5	Coarse	700	1000	2500	10000
TP14	0.9-1.0	Coarse	700	1000	2500	10000
TP15	0-0.1	Coarse	700	1000	2500	10000
TP15 - [LAB_DUP]	0-0.1	Coarse	700	1000	2500	10000
TP15	0.9-1.0	Coarse	700	1000	2500	10000
TP15	1.3-1.5	Coarse	700	1000	2500	10000
TP16	0-0.1	Coarse	700	1000	2500	10000
TP16	0.4-0.5	Coarse	700	1000	2500	10000
SDUP1	0-0.1	Coarse	700	1000	2500	10000
SDUP2	0-0.1	Coarse	700	1000	2500	10000
SDUP3	0-0.1	Coarse	700	1000	2500	10000
SDUP4	0-0.1	Coarse	700	1000	2500	10000

**TABLE S4**  
**SOIL LABORATORY RESULTS COMPARED TO DIRECT CONTACT CRITERIA**  
 All data in mg/kg unless stated otherwise

Analyte	C <sub>6</sub> -C <sub>10</sub>	>C <sub>10</sub> -C <sub>16</sub>	>C <sub>16</sub> -C <sub>34</sub>	>C <sub>34</sub> -C <sub>40</sub>	Benzene	Toluene	Ethylbenzene	Xylenes	Naphthalene	PID	
PQL - Envirolab Services	25	50	100	100	0.2	0.5	1	1	1		
CRC 2011 -Direct contact Criteria	4,400	3,300	4,500	6,300	100	14,000	4,500	12,000	1,400		
Site Use	<b>RESIDENTIAL WITH ACCESSIBLE SOIL- DIRECT SOIL CONTACT</b>										
Sample Reference	Sample Depth										
BH1	0-0.3	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>0.5</b>
BH1 - [LAB_DUP]	0-0.3	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	NA
BH1	0.8-1.0	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>0.3</b>
BH2	0-0.2	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>1.3</b>
BH2	0.3-0.5	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>1.9</b>
BH2	0.8-1.0	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>1.8</b>
BH3	0-0.1	<25	<50	<b>130</b>	<b>230</b>	<0.2	<0.5	<1	<1	<1	<b>0.6</b>
BH3	0.3-0.5	<25	<50	<b>320</b>	<b>120</b>	<0.2	<0.5	<1	<1	<1	<b>0.7</b>
BH3	1.3-1.5	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>1.5</b>
BH4	0-0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>2.2</b>
BH4 - [LAB_DUP]	0-0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	NA
BH4	0.3-0.5	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>2</b>
BH4	0.8-1.0	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>3.8</b>
BH5	0-0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>0.6</b>
BH5	0.8-1.0	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>0.6</b>
BH6	0-0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>0.4</b>
BH6	0.3-0.5	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>0.1</b>
BH6	0.8-1.0	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>0.1</b>
BH7	0.02-0.3	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>0.8</b>
BH7 - [LAB_DUP]	0.02-0.3	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	NA
BH7	0.3-0.5	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>2</b>
BH8	0.02-0.2	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	0
BH8	0.3-0.5	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>0.3</b>
TP13	0-0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>0.6</b>
TP13	0.5-0.6	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>1.3</b>
TP14	0-0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>1</b>
TP14	0.4-0.5	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>0.5</b>
TP14	0.9-1.0	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>1.1</b>
TP15	0-0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>0.3</b>
TP15 - [LAB_DUP]	0-0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	NA
TP15	0.9-1.0	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>0.4</b>
TP15	1.3-1.5	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>0.5</b>
TP16	0-0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>0.2</b>
TP16	0.4-0.5	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	<b>1.2</b>
SDUP1	0-0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	NA
SDUP2	0-0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	NA
SDUP3	0-0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	NA
SDUP4	0-0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<1	NA
<b>Total Number of Samples</b>		38	38	38	38	38	38	38	38	38	30
<b>Maximum Value</b>		<PQL	<PQL	320	230	<PQL	<PQL	<PQL	<PQL	2	3.8

Concentration above the SAC **VALUE**  
 Concentration above the PQL **Bold**



TABLE S5 ASBESTOS QUANTIFICATION - FIELD OBSERVATIONS AND LABORATORY RESULTS HSL-A: Residential with garden/accessible soils; children's day care centers; preschools; and primary schools																										
FIELD DATA															LABORATORY DATA											
Date Sampled	Sample reference	Sample Depth	Visible ACM in top 100mm	Approx. Volume of Soil (L)	Soil Mass (g)	Mass ACM (g)	Mass Asbestos in ACM (g)	[Asbestos from ACM in soil] (%w/w)	Mass ACM <7mm (g)	Mass Asbestos in ACM <7mm (g)	[Asbestos from ACM <7mm in soil] (%w/w)	Mass FA (g)	Mass Asbestos in FA (g)	[Asbestos from FA in soil] (%w/w)	Lab Report Number	Sample reference	Sample Depth	Sample Mass (g)	Asbestos ID in soil (AS4964) >0.1g/kg	Trace Analysis	Total Asbestos (g/kg)	Asbestos ID in soil <0.1g/kg	ACM >7mm Estimation (g)	FA and AF Estimation (g)	ACM >7mm Estimation (%w/w)	FA and AF Estimation (%w/w)
SAC			No	0.01					0.001					0.01										0.001		
--	--	--	--	--	--	--	--	--	--	--	--	--	--	--		BH1	0-0.3		No asbestos detected at reporting limit of 0.1g/kg: Organic fibres detected	No asbestos detected	<0.1	No visible asbestos detected	--	--	<0.01	<0.001
3/05/2023	BH2	0-0.2	No	10	12,490	No ACM observed	--	--	No ACM <7mm observed	--	--	No FA observed	--	--		BH2	0-0.2		No asbestos detected at reporting limit of 0.1g/kg: Organic fibres detected	No asbestos detected	<0.1	No visible asbestos detected	--	--	<0.01	<0.001
4/05/2023	BH3	0-0.1	No	10	10,180	No ACM observed	--	--	No ACM <7mm observed	--	--	No FA observed	--	--		BH3	0-0.1		No asbestos detected at reporting limit of 0.1g/kg: Organic fibres detected	No asbestos detected	<0.1	No visible asbestos detected	--	--	<0.01	<0.001
4/05/2023	BH3	0.1-0.3	NA	2	2,240	No ACM observed	--	--	No ACM <7mm observed	--	--	No FA observed	--	--	--	--	--	--	--	--	--	--	--	--	--	--
4/05/2023	BH3	0.3-1.1	NA	8	8,960	No ACM observed	--	--	No ACM <7mm observed	--	--	No FA observed	--	--		BH3	0.3-0.5		No asbestos detected at reporting limit of 0.1g/kg: Organic fibres detected	No asbestos detected	<0.1	No visible asbestos detected	--	--	<0.01	<0.001
4/05/2023	BH4	0-0.2	Yes	10	10,670	48.3	7.2495	0.0679	No ACM <7mm observed	--	--	No FA observed	--	--		BH4	0-0.1		No asbestos detected at reporting limit of 0.1g/kg: Organic fibres detected	No asbestos detected	<0.1	No visible asbestos detected	--	--	<0.01	<0.001
--	--	--	--	--	--	--	--	--	--	--	--	--	--	--		BH5	0-0.1		No asbestos detected at reporting limit of 0.1g/kg: Organic fibres detected	No asbestos detected	<0.1	No visible asbestos detected	--	--	<0.01	<0.001
2/05/2023	BH6	0-0.2	No	10	10,440	No ACM observed	--	--	No ACM <7mm observed	--	--	No FA observed	--	--		BH6	0-0.1		No asbestos detected at reporting limit of 0.1g/kg: Organic fibres detected	No asbestos detected	<0.1	No visible asbestos detected	--	--	<0.01	<0.001
2/05/2023	BH7	0.02-0.3	NA	1.7	1,880	No ACM observed	--	--	No ACM <7mm observed	--	--	No FA observed	--	--		BH7	0.02-0.3		No asbestos detected at reporting limit of 0.1g/kg: Organic fibres detected	No asbestos detected	<0.1	No visible asbestos detected	--	--	<0.01	<0.001
--	--	--	--	--	--	--	--	--	--	--	--	--	--	--		BH8	0.02-0.2		No asbestos detected at reporting limit of 0.1g/kg: Organic fibres detected	No asbestos detected	<0.1	No visible asbestos detected	--	--	<0.01	<0.001
4/05/2023	TP13	0-0.1	No	10	10,520	No ACM observed	--	--	No ACM <7mm observed	--	--	No FA observed	--	--		TP13	0-0.1		No asbestos detected at reporting limit of 0.1g/kg: Organic fibres detected	No asbestos detected	<0.1	No visible asbestos detected	--	--	<0.01	<0.001
4/05/2023	TP13	0.1-0.3	NA	10	10,220	No ACM observed	--	--	No ACM <7mm observed	--	--	No FA observed	--	--	--	--	--	--	--	--	--	--	--	--	--	--
4/05/2023	TP14	0-0.2	No	10	12,310	No ACM observed	--	--	No ACM <7mm observed	--	--	No FA observed	--	--		TP14	0-0.1		No asbestos detected at reporting limit of 0.1g/kg: Organic fibres detected	No asbestos detected	<0.1	No visible asbestos detected	--	--	<0.01	<0.001
4/05/2023	TP15	0-0.1	No	10	10,290	No ACM observed	--	--	No ACM <7mm observed	--	--	No FA observed	--	--		TP15	0-0.1		No asbestos detected at reporting limit of 0.1g/kg: Organic fibres detected	No asbestos detected	<0.1	No visible asbestos detected	--	--	<0.01	<0.001
4/05/2023	TP15	0.1-0.5	NA	10	10,340	No ACM observed	--	--	No ACM <7mm observed	--	--	No FA observed	--	--	--	--	--	--	--	--	--	--	--	--	--	--
4/05/2023	TP15	0.5-1.1	NA	10	12,520	No ACM observed	--	--	No ACM <7mm observed	--	--	No FA observed	--	--		TP15	0.9-1.0		No asbestos detected at reporting limit of 0.1g/kg: Organic fibres detected	No asbestos detected	<0.1	No visible asbestos detected	--	--	<0.01	<0.001
--	--	--	--	--	--	--	--	--	--	--	--	--	--	--		TP16	0-0.1		No asbestos detected at reporting limit of 0.1g/kg: Organic fibres detected	No asbestos detected	<0.1	No visible asbestos detected	--	--	<0.01	<0.001

Concentration above the SAC **VALUE**

**TABLE S6**  
**SOIL LABORATORY RESULTS COMPARED TO NEPM 2013 EILS AND ESLs**  
 All data in mg/kg unless stated otherwise

Land Use Category	pH	CEC (cmolc/kg)	Clay Content (% clay)	URBAN RESIDENTIAL AND PUBLIC OPEN SPACE								EILs				ESLs				B(a)P				
				Arsenic	Chromium	Copper	Lead	Nickel	Zinc	Naphthalene	DDT	C <sub>6</sub> -C <sub>10</sub> (F1)	>C <sub>10</sub> -C <sub>16</sub> (F2)	>C <sub>16</sub> -C <sub>34</sub> (F3)	>C <sub>34</sub> -C <sub>40</sub> (F4)	Benzene	Toluene	Ethylbenzene	Total Xylenes					
PQL - EnviroLab Services	-	1	-	4	1	1	1	1	1	1	1	0.1	25	50	100	100	0.2	0.5	1	1	0.05			
Ambient Background Concentration (ABC)	-	-	-	NSL	8	18	104	5	77	NSL	NSL	NSL	NSL	NSL	NSL	NSL	NSL	NSL	NSL	NSL	NSL			
Sample Reference	Sample Depth	Sample Description	Soil Texture	pH	CEC (cmolc/kg)	Clay Content (% clay)	Arsenic	Chromium	Copper	Lead	Nickel	Zinc	Naphthalene	DDT	C <sub>6</sub> -C <sub>10</sub> (F1)	>C <sub>10</sub> -C <sub>16</sub> (F2)	>C <sub>16</sub> -C <sub>34</sub> (F3)	>C <sub>34</sub> -C <sub>40</sub> (F4)	Benzene	Toluene	Ethylbenzene	Total Xylenes	B(a)P	
BH1	0-0.3	Silty Clay	Fine	NA	NA	NA	<4	37	70	7	10	22	<1	<0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<0.05	
BH1 - [LAB_DUP]	0-0.3	Laboratory Duplicate	Fine	NA	NA	NA	<4	38	70	9	10	25	<1	<0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	0.1	
BH1	0.8-1.0	XW Andersite	Fine	NA	NA	NA	<4	62	<b>130</b>	9	14	31	<1	NA	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<0.05	
BH2	0-0.2	F: Gravelly Silty Sand	Fine	NA	NA	NA	6	38	<b>200</b>	8	11	36	<1	<0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	0.69	
BH2	0.3-0.5	Sandy Silty Clay	Fine	NA	NA	NA	6	91	<b>280</b>	5	18	37	<1	NA	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<0.05	
BH2	0.8-1.0	Silty Clay	Fine	NA	NA	NA	6	63	<b>200</b>	6	13	30	<1	NA	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<0.05	
BH3	0-0.1	F: Silty Clay	Fine	NA	NA	NA	7	23	<b>57</b>	12	9	24	<1	<0.1	<25	<50	<b>130</b>	<b>230</b>	<0.2	<0.5	<1	<1	0.09	
BH3	0.3-0.5	F: Sandy Silty Clay	Fine	NA	NA	NA	8	47	<b>86</b>	15	11	33	2	<0.1	<25	<50	<b>320</b>	<b>120</b>	<0.2	<0.5	<1	<1	5.4	
BH3	1.3-1.5	Sandy Silty Clay	Fine	NA	NA	NA	4	72	<b>120</b>	9	12	22	<1	NA	<25	<50	<100	<100	<0.2	<0.5	<1	<1	0.2	
BH4	0-0.1	F: Silty Clay	Fine	NA	NA	NA	5	30	<b>82</b>	28	7	53	<1	<0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	0.1	
BH4 - [LAB_DUP]	0-0.1	Laboratory Duplicate	Fine	NA	NA	NA	5	28	<b>80</b>	26	6	53	<1	<0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	0.09	
BH4	0.3-0.5	Sandy Silty Clay	Fine	NA	NA	NA	7	18	<b>300</b>	3	11	31	<1	NA	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<0.05	
BH4	0.8-1.0	XW Andersite	Coarse	NA	NA	NA	6	16	<b>210</b>	2	9	24	<1	NA	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<0.05	
BH5	0-0.1	Silty Clay	Fine	NA	NA	NA	9	26	<b>230</b>	13	9	30	<1	<0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	0.3	
BH5	0.8-1.0	Silty Clay	Fine	NA	NA	NA	4	52	<b>180</b>	7	12	20	<1	NA	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<0.05	
BH6	0-0.1	F: Silty Clay	Fine	NA	NA	NA	<4	22	<b>220</b>	17	9	54	<1	<0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<0.05	
BH6	0.3-0.5	Sandy Silty Clay	Fine	NA	NA	NA	<4	19	<b>440</b>	3	10	51	<1	NA	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<0.05	
BH6	0.8-1.0	XW Andersite	Fine	NA	NA	NA	<4	16	<b>400</b>	1	9	55	<1	NA	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<0.05	
BH7	0.02-0.3	F: Gravelly Silty Sand	Coarse	NA	NA	NA	7	36	<b>94</b>	24	9	36	<1	<0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<0.05	
BH7 - [LAB_DUP]	0.02-0.3	Laboratory Duplicate	Coarse	NA	NA	NA	6	51	<b>100</b>	20	11	34	<1	<0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<0.05	
BH7	0.3-0.5	F: Silty Sand	Coarse	NA	NA	NA	7	66	<b>120</b>	10	13	29	<1	NA	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<0.05	
BH8	0.02-0.2	F: Silty Sand	Coarse	NA	NA	NA	<4	13	<b>12</b>	7	2	7	<1	<0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	2.6	
BH8	0.3-0.5	Sandy Silty Clay	Fine	NA	NA	NA	<4	53	<b>170</b>	7	15	42	<1	NA	<25	<50	<100	<100	<0.2	<0.5	<1	<1	0.3	
TP13	0-0.1	F: Silty Clay	Fine	NA	NA	NA	5	20	<b>210</b>	22	8	59	<1	<0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	0.05	
TP13	0.5-0.6	Silty Clay	Fine	NA	NA	NA	7	24	<b>490</b>	4	11	28	<1	NA	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<0.05	
TP14	0-0.1	F: Silty Clay	Fine	NA	NA	NA	15	31	<b>99</b>	120	3	88	<1	<0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	0.1	
TP14	0.4-0.5	Silty Clay	Fine	NA	NA	NA	<4	17	<b>420</b>	6	10	57	<1	NA	<25	<50	<100	<100	<0.2	<0.5	<1	<1	0.06	
TP14	0.9-1.0	XW Andersite	Coarse	NA	NA	NA	<4	10	<b>470</b>	2	10	47	<1	NA	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<0.05	
TP15	0-0.1	F: Silty Clay	Fine	NA	NA	NA	6	21	<b>34</b>	12	7	30	<1	<0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	0.05	
TP15 - [LAB_DUP]	0-0.1	Laboratory Duplicate	Fine	NA	NA	NA	5	19	<b>29</b>	12	7	30	<1	<0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	0.05	
TP15	0.9-1.0	F: Sandy Silty Clay	Fine	NA	NA	NA	7	24	<b>32</b>	14	5	11	<1	<0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	3.4	
TP15	1.3-1.5	Silty Clay	Fine	NA	NA	NA	<4	52	<b>110</b>	7	9	18	<1	NA	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<0.05	
TP16	0-0.1	Silty Clay	Fine	NA	NA	NA	10	56	<b>190</b>	25	14	61	<1	<0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	0.1	
TP16	0.4-0.5	Silty Clay	Fine	NA	NA	NA	5	74	<b>180</b>	4	15	27	<1	NA	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<0.05	
SDUP1	0-0.1	Duplicate of TP16	Fine	NA	NA	NA	10	55	<b>190</b>	25	14	66	<1	<0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	0.2	
SDUP2	0-0.1	Duplicate of TP15	Fine	NA	NA	NA	6	20	<b>31</b>	12	7	29	<1	NA	<25	<50	<100	<100	<0.2	<0.5	<1	<1	<0.05	
SDUP3	0-0.1	Duplicate of TP14	Fine	NA	NA	NA	11	22	<b>130</b>	170	6	140	<1	<0.1	<25	<50	<100	<100	<0.2	<0.5	<1	<1	0.08	
SDUP4	0-0.1	Duplicate of TP13	Fine	NA	NA	NA	5	16	<b>160</b>	24	7	67	<1	NA	<25	<50	<100	<100	<0.2	<0.5	<1	<1	0.05	
SDUP4 - [LAB_DUP]	0-0.1	Laboratory Duplicate	Fine	NA	NA	NA	5	15	<b>170</b>	19	7	60	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
<b>Total Number of Samples</b>	0	0	0	39	39	39	39	39	39	39	39	39	38	20	38	38	38	38	38	38	38	38	38	38
<b>Maximum Value</b>	NA	NA	NA	15	91	490	170	18	140	2	<PQL	<PQL	<PQL	<PQL	320	230	<PQL	<PQL	<PQL	<PQL	<PQL	<PQL	5.4	

Concentration above the SAC **VALUE**  
 Concentration above the PQL **bold**  
 The guideline corresponding to the elevated value is highlighted in grey in the EIL and ESL Assessment Criteria Table below

**EIL AND ESL ASSESSMENT CRITERIA**

Sample Reference	Sample Depth	Sample Description	Soil Texture	pH	CEC (cmolc/kg)	Clay Content (% clay)	Arsenic	Chromium	Copper	Lead	Nickel	Zinc	Naphthalene	DDT	C <sub>6</sub> -C <sub>10</sub> (F1)	>C <sub>10</sub> -C <sub>16</sub> (F2)	>C <sub>16</sub> -C <sub>34</sub> (F3)	>C <sub>34</sub> -C <sub>40</sub> (F4)	Benzene	Toluene	Ethylbenzene	Total Xylenes	B(a)P
BH1	0-0.3	Silty Clay	Fine	NA	NA	NA	100	200	80	1200	35	150	170	180	180	120	1300	5600	65	105	125	45	20
BH1 - [LAB_DUP]	0-0.3	Laboratory Duplicate	Fine	NA	NA	NA	100	200	80	1200	35	150	170	180	180	120	1300	5600	65	105	125	45	20
BH1	0.8-1.0	XW Andersite	Fine	NA	NA	NA	100	200	80	1200	35	150	170	--	180	120	1300	5600	65	105	125	45	20
BH2	0-0.2	F: Gravelly Silty Sand	Fine	NA	NA	NA	100	200	80	1200	35	150	170	--	180	120	1300	5600	65	105	125	45	20
BH2	0.3-0.5	Sandy Silty Clay	Fine	NA	NA	NA	100	200	80	1200	35	150	170	--	180	120	1300	5600	65	105	125	45	20
BH2	0.8-1.0	Silty Clay	Fine	NA	NA	NA	100	200	80	1200	35	150	170	--	180	120	1300	5600	65	105	125	45	20
BH3	0-0.1	F: Silty Clay	Fine	NA	NA	NA	100	200	80	1200	35	150	170	180	180	120	1300	5600	65	105	125	45	20
BH3	0.3-0.5	F: Sandy Silty Clay	Fine																				

**TABLE S7**  
**SOIL LABORATORY RESULTS COMPARED TO WASTE CLASSIFICATION GUIDELINES**  
 All data in mg/kg unless stated otherwise

	Sample Reference	Sample Depth	Sample Description	HEAVY METALS							PAHs		OC/OP PESTICIDES				Total PCBs	TRH					BTEX COMPOUNDS				ASBESTOS FIBRES	
				Arsenic	Cadmium	Chromium	Copper	Lead	Mercury	Nickel	Zinc	Total PAHs	B(a)P	Total Endosulfans	Chloropyrifos	Total Moderately Harmful		Total Scheduled	C <sub>6</sub> -C <sub>9</sub>	C <sub>10</sub> -C <sub>14</sub>	C <sub>15</sub> -C <sub>28</sub>	C <sub>29</sub> -C <sub>36</sub>	Total C <sub>10</sub> -C <sub>36</sub>	Benzene	Toluene	Ethyl benzene		Total Xylenes
PQL - Envirolab Services				4	0.4	1	1	1	0.1	1	1	-	0.05	0.1	0.1	0.1	0.1	0.1	25	50	100	100	50	0.2	0.5	1	1	100
General Solid Waste CT1				100	20	100	NSL	100	4	40	NSL	200	0.8	60	4	250	50	50	650		NSL		10,000	10	288	600	1,000	-
General Solid Waste SCC1				500	100	1900	NSL	1500	50	1050	NSL	200	10	108	7.5	250	50	50	650		NSL		10,000	18	518	1,080	1,800	-
Restricted Solid Waste CT2				400	80	400	NSL	400	16	160	NSL	800	3.2	240	16	1000	50	50	2600		NSL		40,000	40	1,152	2,400	4,000	-
Restricted Solid Waste SCC2				2000	400	7600	NSL	6000	200	4200	NSL	800	23	432	30	1000	50	50	2600		NSL		40,000	72	2,073	4,320	7,200	-
BH1	0-0.3		Silty Clay	<4	<0.4	<b>37</b>	<b>70</b>	<b>7</b>	<0.1	<b>10</b>	<b>22</b>	<b>0.2</b>	<0.05	<0.1	<0.1	<0.1	<0.1	<0.1	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	Not Detected
BH1 - [LAB_DUP]	0-0.3		Laboratory Duplicate	<4	<0.4	<b>38</b>	<b>70</b>	<b>9</b>	<0.1	<b>10</b>	<b>25</b>	<b>0.55</b>	<b>0.1</b>	<0.1	<0.1	<0.1	<0.1	<0.1	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
BH1	0.8-1.0		XW Andersite	<4	<0.4	<b>62</b>	<b>130</b>	<b>9</b>	<0.1	<b>14</b>	<b>31</b>	<0.05	<0.05	NA	NA	NA	NA	NA	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
BH2	0-0.2		F: Gravelly Silty Clay	<b>6</b>	<0.4	<b>38</b>	<b>200</b>	<b>8</b>	<0.1	<b>11</b>	<b>36</b>	<b>6.9</b>	<b>0.69</b>	<0.1	<0.1	<0.1	<0.1	<0.1	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	Not Detected
BH2	0.3-0.5		Sandy Silty Clay	<b>6</b>	<0.4	<b>91</b>	<b>280</b>	<b>5</b>	<0.1	<b>18</b>	<b>37</b>	<0.05	<0.05	NA	NA	NA	NA	NA	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
BH2	0.8-1.0		Silty Clay	<b>6</b>	<0.4	<b>63</b>	<b>200</b>	<b>6</b>	<0.1	<b>13</b>	<b>30</b>	<0.05	<0.05	NA	NA	NA	NA	NA	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
BH3	0-0.1		F: Silty Clay	<b>7</b>	<0.4	<b>23</b>	<b>57</b>	<b>12</b>	<0.1	<b>9</b>	<b>24</b>	<b>0.64</b>	<b>0.09</b>	<0.1	<0.1	<0.1	<0.1	<0.1	<25	<50	<100	<b>180</b>	<b>180</b>	<0.2	<0.5	<1	<1	Not Detected
BH3	0.3-0.5		F: Sandy Silty Clay	<b>8</b>	<0.4	<b>47</b>	<b>86</b>	<b>15</b>	<b>0.2</b>	<b>11</b>	<b>33</b>	<b>85</b>	<b>5.4</b>	<0.1	<0.1	<0.1	<0.1	<0.1	<25	<50	<b>170</b>	<b>200</b>	<b>370</b>	<0.2	<0.5	<1	<1	Not Detected
BH3	1.3-1.5		Sandy Silty Clay	<b>4</b>	<0.4	<b>72</b>	<b>120</b>	<b>9</b>	<0.1	<b>12</b>	<b>22</b>	<b>3.3</b>	<b>0.2</b>	NA	NA	NA	NA	NA	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
BH4	0-0.1		F: Silty Clay	<b>5</b>	<0.4	<b>30</b>	<b>82</b>	<b>28</b>	<0.1	<b>7</b>	<b>53</b>	<b>0.66</b>	<b>0.1</b>	<0.1	<0.1	<0.1	<0.1	<0.1	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	Not Detected
BH4 - [LAB_DUP]	0-0.1		Laboratory Duplicate	<b>5</b>	<0.4	<b>28</b>	<b>80</b>	<b>26</b>	<0.1	<b>6</b>	<b>53</b>	<b>0.5</b>	<b>0.09</b>	<0.1	<0.1	<0.1	<0.1	<0.1	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
BH4	0.3-0.5		Sandy Silty Clay	<b>7</b>	<0.4	<b>18</b>	<b>300</b>	<b>3</b>	<0.1	<b>11</b>	<b>31</b>	<0.05	<0.05	NA	NA	NA	NA	NA	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
BH4	0.8-1.0		XW Andersite	<b>6</b>	<0.4	<b>16</b>	<b>210</b>	<b>2</b>	<0.1	<b>9</b>	<b>24</b>	<0.05	<0.05	NA	NA	NA	NA	NA	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
BH5	0-0.1		Silty Clay	<b>9</b>	<0.4	<b>26</b>	<b>230</b>	<b>13</b>	<0.1	<b>9</b>	<b>30</b>	<b>2.9</b>	<b>0.3</b>	<0.1	<0.1	<0.1	<0.1	<0.1	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	Not Detected
BH5	0.8-1.0		Silty Clay	<b>4</b>	<0.4	<b>52</b>	<b>180</b>	<b>7</b>	<0.1	<b>12</b>	<b>20</b>	<0.05	<0.05	NA	NA	NA	NA	NA	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
BH6	0-0.1		F: Silty Clay	<4	<0.4	<b>22</b>	<b>220</b>	<b>17</b>	<0.1	<b>9</b>	<b>54</b>	<0.05	<0.05	<0.1	<0.1	<0.1	<0.1	<0.1	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	Not Detected
BH6	0.3-0.5		Sandy Silty Clay	<4	<0.4	<b>19</b>	<b>440</b>	<b>3</b>	<0.1	<b>10</b>	<b>51</b>	<0.05	<0.05	NA	NA	NA	NA	NA	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
BH6	0.8-1.0		XW Andersite	<4	<0.4	<b>16</b>	<b>400</b>	<b>1</b>	<0.1	<b>9</b>	<b>55</b>	<0.05	<0.05	NA	NA	NA	NA	NA	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
BH7	0.02-0.3		F: Gravelly Silty Sand	<b>7</b>	<0.4	<b>36</b>	<b>94</b>	<b>24</b>	<0.1	<b>9</b>	<b>36</b>	<0.05	<0.05	<0.1	<0.1	<0.1	<0.1	<0.1	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	Not Detected
BH7 - [LAB_DUP]	0.02-0.3		Laboratory Duplicate	<b>6</b>	<0.4	<b>51</b>	<b>100</b>	<b>20</b>	<0.1	<b>11</b>	<b>34</b>	<0.05	<0.05	<0.1	<0.1	<0.1	<0.1	<0.1	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
BH7	0.3-0.5		F: Silty Sand	<b>7</b>	<0.4	<b>66</b>	<b>120</b>	<b>10</b>	<b>0.6</b>	<b>13</b>	<b>29</b>	<0.05	<0.05	NA	NA	NA	NA	NA	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
BH8	0.02-0.2		F: Silty Sand	<4	<0.4	<b>13</b>	<b>12</b>	<b>7</b>	<0.1	<b>2</b>	<b>7</b>	<b>27</b>	<b>2.6</b>	<0.1	<0.1	<0.1	<0.1	<0.1	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	Not Detected
BH8	0.3-0.5		Sandy Silty Clay	<4	<0.4	<b>53</b>	<b>170</b>	<b>7</b>	<0.1	<b>15</b>	<b>42</b>	<b>3.3</b>	<b>0.3</b>	NA	NA	NA	NA	NA	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
TP13	0-0.1		F: Silty Clay	<b>5</b>	<0.4	<b>20</b>	<b>210</b>	<b>22</b>	<b>0.1</b>	<b>8</b>	<b>59</b>	<b>0.2</b>	<b>0.05</b>	<0.1	<0.1	<0.1	<0.1	<0.1	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	Not Detected
TP13	0.5-0.6		Silty Clay	<b>7</b>	<0.4	<b>24</b>	<b>490</b>	<b>4</b>	<0.1	<b>11</b>	<b>28</b>	<0.05	<0.05	NA	NA	NA	NA	NA	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
TP14	0-0.1		F: Silty Clay	<b>15</b>	<0.4	<b>31</b>	<b>99</b>	<b>120</b>	<b>0.1</b>	<b>3</b>	<b>88</b>	<b>1.1</b>	<b>0.1</b>	<0.1	<0.1	<0.1	<0.1	<0.1	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	Not Detected
TP14	0.4-0.5		Silty Clay	<4	<0.4	<b>17</b>	<b>420</b>	<b>6</b>	<0.1	<b>10</b>	<b>57</b>	<b>0.5</b>	<b>0.06</b>	NA	NA	NA	NA	NA	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
TP14	0.9-1.0		XW Andersite	<4	<0.4	<b>10</b>	<b>470</b>	<b>2</b>	<0.1	<b>10</b>	<b>47</b>	<0.05	<0.05	NA	NA	NA	NA	NA	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
TP15	0-0.1		F: Silty Clay	<b>6</b>	<0.4	<b>21</b>	<b>34</b>	<b>12</b>	<0.1	<b>7</b>	<b>30</b>	<b>0.3</b>	<b>0.05</b>	<0.1	<0.1	<0.1	<0.1	<0.1	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	Not Detected
TP15 - [LAB_DUP]	0-0.1		Laboratory Duplicate	<b>5</b>	<0.4	<b>19</b>	<b>29</b>	<b>12</b>	<0.1	<b>7</b>	<b>30</b>	<b>0.2</b>	<b>0.05</b>	<0.1	<0.1	<0.1	<0.1	<0.1	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
TP15	0.9-1.0		F: Sandy Silty Clay	<b>7</b>	<0.4	<b>24</b>	<b>32</b>	<b>14</b>	<0.1	<b>5</b>	<b>11</b>	<b>43</b>	<b>3.4</b>	<0.1	<0.1	<0.1	<0.1	<0.1	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	Not Detected
TP15	1.3-1.5		Silty Clay	<4	<0.4	<b>52</b>	<b>110</b>	<b>7</b>	<b>0.7</b>	<b>9</b>	<b>18</b>	<0.05	<0.05	NA	NA	NA	NA	NA	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
TP16	0-0.1		Silty Clay	<b>10</b>	<0.4	<b>56</b>	<b>190</b>	<b>25</b>	<0.1	<b>14</b>	<b>61</b>	<b>1.4</b>	<b>0.1</b>	<0.1	<0.1	<0.1	<0.1	<0.1	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	Not Detected
TP16	0.4-0.5		Silty Clay	<b>5</b>	<0.4	<b>74</b>	<b>180</b>	<b>4</b>	<0.1	<b>15</b>	<b>27</b>	<0.05	<0.05	NA	NA	NA	NA	NA	<25	<50	<100	<100	<50	<0.2	<0.5	<1	<1	NA
SDUP1	0-0.1		Duplicate of TP16	<b>10</b>	<0.4	<b>55</b>	<b>190</b>	<b>25</b>	<0.1																			

<b>TABLE S8</b>				
<b>SOIL LABORATORY TCLP RESULTS</b>				
All data in mg/L unless stated otherwise				
			Lead	B(a)P
PQL - Envirolab Services			0.03	0.001
TCLP1 - General Solid Waste			5	0.04
TCLP2 - Restricted Solid Waste			20	0.16
TCLP3 - Hazardous Waste			>20	>0.16
Sample Reference	Sample Depth	Sample Description		
BH3	0.3-0.5	F: Sandy Silty Clay	NA	<b>0.0086</b>
BH8	0.02-0.2	F: Silty Sand	NA	<0.001
TP14	0-0.1	F: Silty Clay	<b>0.07</b>	NA
TP15	0.9-1.0	F: Sandy Silty Clay	NA	<0.001
SDUP3	0-0.1	Duplicate of TP14	<b>0.3</b>	NA
<b>Total Number of samples</b>			2	3
<b>Maximum Value</b>			0.30	0.0086
General Solid Waste			VALUE	
Restricted Solid Waste			VALUE	
Hazardous Waste			VALUE	
Concentration above PQL			<b>Bold</b>	





---

## **Appendix D: Borehole & Test Pit Logs**

## BOREHOLE LOG

**Client:** HEALTH INFRASTRUCTURE  
**Project:** PROPOSED ALTERATIONS AND ADDITIONS  
**Location:** TEMORA HOSPITAL, 169-189 LOFTUS STREET, TEMORA, NSW

**Job No.:** 35822BF      **Method:** SPIRAL AUGER      **R.L. Surface:** ~309.2 m  
**Date:** 4/5/23      **Datum:** AHD  
**Plant Type:** HANJIN DB8      **Logged/Checked By:** C.S.Y./O.F.

Groundwater Record	SAMPLES				Field Tests	RL (m AHD)	Depth (m)	Graphic Log	Unified Classification	DESCRIPTION	Moisture Condition/ Weathering	Strength/ Rel Density	Hand Penetrometer Readings (kPa)	Remarks
	ES	U50	DB	DS										
DRY ON COMPLETION						309		CL	Silty CLAY: low plasticity, red brown, trace of fine to medium grained quartz and igneous gravel, and root fibres.	w>PL	Hd		GRASS COVER	
					N > 17 11, 17/ 150mm REFUSAL					w<PL		>600 >600 >600	TEMORA VOLCANICS	
						308	1		Extremely Weathered andesite: sandy silty CLAY, low plasticity, red brown, fine to medium grained sand, with fine to medium grained quartz and igneous gravel. as above, but brown.	XW	Hd		VERY LOW TO LOW 'V' BIT RESISTANCE	
					N=SPT 10/ 50mm REFUSAL	307	2							
						306	3		ANDESITE: grey, with quartz inclusions.	DW	L - M			LOW RESISTANCE
						305	4							LOW TO MODERATE RESISTANCE
					304	5							GROUNDWATER MONITORING WELL INSTALLED TO 6m. CLASS 18 MACHINE SLOTTED 50mm DIA. PVC STANDPIPE 6m TO 0.12m. 2mm SAND FILTER PACK 6m TO 0.12m. BACKFILLED WITH SAND TO THE SURFACE. COMPLETED WITH A CONCRETED GATIC COVER.	
					303	6			END OF BOREHOLE AT 6.00 m				MODERATE RESISTANCE	

JK 9.02.4 LIB.GLB Log\_JK AUGERHOLE - MASTER\_35822BF TEMORA.GPJ <-DrawingFile> 25/05/2023 13:10 10.01.00.01 D:\geot\Lab and In Situ Tool - DGD\Lib\_JK\_9.02.4\_2019-05-31 Proj\_JK\_9.01.0\_2018-03-20

## BOREHOLE LOG

**Client:** HEALTH INFRASTRUCTURE  
**Project:** PROPOSED ALTERATIONS AND ADDITIONS  
**Location:** TEMORA HOSPITAL, 169-189 LOFTUS STREET, TEMORA, NSW

**Job No.:** 35822BF      **Method:** SPIRAL AUGER      **R.L. Surface:** ~317.2 m  
**Date:** 3/5/23      **Datum:** AHD  
**Plant Type:** HANJIN DB8      **Logged/Checked By:** C.S.Y./O.F.

Groundwater Record	SAMPLES ES U50 DB DS	Field Tests	RL (m AHD)	Depth (m)	Graphic Log	Unified Classification	DESCRIPTION	Moisture Condition/ Weathering	Strength/ Rel Density	Hand Penetrometer Readings (kPa)	Remarks
			317			CL	FILL: Gravelly sandy clay, low plasticity, red brown, fine to coarse grained sand, fine to medium grained igneous gravel. Sandy Silty CLAY: low plasticity, brown, fine to medium grained sand, trace of fine to medium grained igneous gravel.	w<PL w<PL	F - St		GRAVEL AND GRASS COVER SCREEN: 12.49kg 0-0.2m, NO FCF RESIDUAL
		N = 3 1,1,2		1		CI	Silty CLAY: medium plasticity, red brown, with fine to medium grained sand, trace of fine grained igneous gravel.		(F - St)		TOO FRIABLE FOR HP TESTING
				2			as above, but brown.		(St - VSt)		
		N=SPT 12/ 50mm REFUSAL	315			-	Extremely Weathered andesite: silty clayey SAND, fine to coarse grained, brown, trace of fine grained andesite gravel.	XW	(D)		TEMORA VOLCANICS
			314				ANDESITE: brown, with quartz inclusions.	DW	EL - VL		VERY LOW 'V' BIT RESISTANCE
			313				as above, but trace of medium to high strength bands.		VL - L		VERY LOW RESISTANCE
			312								
							END OF BOREHOLE AT 5.50 m				
			311								







JK 9.02.4 LIB.GLB Log\_JK AUGERHOLE - MASTER\_35822BF TEMORA.GPJ <-DrawingFile> 25/05/2023 13:10 10.01.00.01 Design Lab and In Situ Tool - DGD Lib\_JK 9.02.4 2019-05-31 Proj\_JK 9.01.0 2018-03-20



## BOREHOLE LOG


<b>Client:</b> HEALTH INFRASTRUCTURE		<b>Project:</b> PROPOSED ALTERATIONS AND ADDITIONS		<b>Location:</b> TEMORA HOSPITAL, 169-189 LOFTUS STREET, TEMORA, NSW	
<b>Job No.:</b> 35822BF		<b>Method:</b> SPIRAL AUGER		<b>R.L. Surface:</b> ~316.3 m	
<b>Date:</b> 4/5/23		<b>Logged/Checked By:</b> C.S.Y./O.F.		<b>Datum:</b> AHD	
<b>Plant Type:</b> HANJIN DB8					

Groundwater Record	SAMPLES	Field Tests	RL (m AHD)	Depth (m)	Graphic Log	Unified Classification	DESCRIPTION	Moisture Condition/ Weathering	Strength/ Rel Density	Hand Penetrometer Readings (kPa)	Remarks	
												ES
DRY ON COMPLETION			316	1			FILL: Silty clay, medium plasticity, brown and red brown, trace of quartz, igneous and ironstone gravel and root fibres. FILL: Sandy silty clay, low to medium plasticity, brown and red brown, fine to coarse grained sand, trace of quartz and igneous gravel and boulders.	w>PL			GRASS COVER APPEARS MODERATELY COMPACTED SCREEN: 10.18kg 0-0.1m, NO FCF SCREEN: 2.24kg 0.1-0.3m, NO FCF SCREEN: 8.96kg 0.3-1.1m, NO FCF RESIDUAL	
			315	2		CI	Sandy Silty CLAY: medium plasticity, red brown, fine to coarse grained sand, trace of fine to coarse grained quartz and igneous gravel.	w<PL	VSt - Hd			
			314	3		-	Extremely Weathered andesite: sandy silty CLAY, low to medium plasticity, brown, fine to coarse grained sand, with fine grained igneous and quartz gravel.	XW	Hd	>600 >600 >600	TEMORA VOLCANICS VERY LOW 'V' BIT RESISTANCE	
			313	4								LOW RESISTANCE
			312	5			Extremely Weathered andesite: silty clayey SAND, fine to coarse grained, brown, low plasticity, trace of fine to medium grained quartz and igneous gravel.					MODERATE RESISTANCE
			311	6								LOW RESISTANCE
			310	6			END OF BOREHOLE AT 6.00 m					

JK 9.02.4 LIB.GLB Log\_JK AUGERHOLE - MASTER\_35822BF TEMORA.GPJ <-DrawingFile> 25/05/2023 13:11 10.01.00.01 Dgnpl Lab and In Situ Tool - DGD Lib JK 9.02.4 2019-05-31 Proj JK 9.01.0 2018-03-20

## BOREHOLE LOG

<b>Client:</b> HEALTH INFRASTRUCTURE <b>Project:</b> PROPOSED ALTERATIONS AND ADDITIONS <b>Location:</b> TEMORA HOSPITAL, 169-189 LOFTUS STREET, TEMORA, NSW														
<b>Job No.:</b> 35822BF				<b>Method:</b> SPIRAL AUGER				<b>R.L. Surface:</b> ~318.0 m						
<b>Date:</b> 4/5/23 TO 5/5/23														
<b>Plant Type:</b> HANJIN DB8				<b>Logged/Checked By:</b> C.S.Y./O.F.										
Groundwater Record	SAMPLES				Field Tests	RL (m AHD)	Depth (m)	Graphic Log	Unified Classification	DESCRIPTION	Moisture Condition/ Weathering	Strength/ Rel Density	Hand Penetrometer Readings (kPa)	Remarks
	ES	U50	DB	DS										
DRY ON COMPLETION OF AUGERING					N = 21 4,8,13	317	1		CL-CI	FILL: Silty clay, low to medium plasticity, brown, trace of fine grained igneous gravel, and root fibres.  Sandy Silty CLAY: low to medium plasticity, brown, fine to coarse grained sand, trace of fine grained igneous and andesite gravel.  Extremely Weathered andesite: gravelly clayey sand, fine to coarse grained, brown, low plasticity, fine to coarse grained igneous gravel.  ANDESITE: grey. REFER TO CORED BOREHOLE LOG	w>PL  w<PL  XW  DW	D  L - M	GRASS COVER  SCREEN: 10.67kg 0-0.2m, FCF1 & FCF2  TEMORA VOLCANICS  MODERATE 'V' BIT RESISTANCE  HIGH RESISTANCE 'V' BIT REFUSAL  GROUNDWATER MONITORING WELL INSTALLED TO 6m. CLASS 18 MACHINE SLOTTED 50mm DIA. PVC STANDPIPE 6m TO 0.12m. 2mm SAND FILTER PACK 6m TO 0.12m. BACKFILLED WITH SAND TO THE SURFACE. COMPLETED WITH A CONCRETED GATIC COVER.	
						316	2							
						315	3							
						314	4							
						313	5							
						312	6							

JK 0.02.4 LIB.GLB Log\_JK AUGERHOLE - MASTER\_35822BF TEMORA.GPJ <-DrawingFile> 25/05/2023 13:11 10.01.00.01 Design Lab and In Situ Tool - DGD Lib\_JK\_0.02.4\_2019-05-31 Proj\_JK\_0.01.0\_2018-03-20

# CORED BOREHOLE LOG

**Client:** HEALTH INFRASTRUCTURE  
**Project:** PROPOSED ALTERATIONS AND ADDITIONS  
**Location:** TEMORA HOSPITAL, 169-189 LOFTUS STREET, TEMORA, NSW

**Job No.:** 35822BF      **Core Size:** NMLC      **R.L. Surface:** ~318.0 m  
**Date:** 4/5/23 TO 5/5/23      **Inclination:** VERTICAL      **Datum:** AHD  
**Plant Type:** HANJIN DB8      **Bearing:** N/A      **Logged/Checked By:** C.S.Y./O.F.


Water Loss/Level Barrel Lift	RL (m AHD)	Depth (m)	Graphic Log	CORE DESCRIPTION Rock Type, grain characteristics, colour, texture and fabric, features, inclusions and minor components	Weathering	Strength	POINT LOAD STRENGTH INDEX I <sub>s</sub> (50)	SPACING (mm)	DEFECT DETAILS		Formation
									Specific	General	
				START CORING AT 1.30m							
80% RETURN	316	2		Extremely Weathered andesite: gravelly silty CLAY, low to medium plasticity, brown, fine to coarse grained andesite and ironstone gravel. ANDESITE: grey and brown.	XW HW MW	Hd L - M M - H			(1.50m) Cr, 0°, 110 mm.t (1.65m) J, 55°, P, Vr, Fe Sn (1.65m) Cr, 55°, 70 mm.t (1.73m) J, 70°, P, Vr, Fe Sn (1.76m) J, 60°, P, R, Fe Sn (1.80m) J, 50°, P, Vr, Fe Sn (1.80m) J x3, P, Vr, Fe Sn (1.86m) J, 60°, P, R, Fe Sn (1.87m) J, 80°, P, S, Clay Vn (1.92m) J, 65°, P, Vr, Fe Sn (2.00m) J, 50°, P, Vr, Fe Sn (2.10m) Cr, 50°, 180 mm.t (2.21m) J, 60°, P, Vr, Fe Sn (2.27m) J, 60°, P, Vr, Fe Sn (2.28m) J, 80°, P, Vr, Fe Sn (2.33m) J, 80°, P, R, Fe Sn (2.34m) Cr, 80°, 10 mm.t (2.38m) Cr, 80°, 20 mm.t (2.45m) Cr, 80°, 90 mm.t (2.70m) Cr, 20°, 100 mm.t (2.83m) J, 70°, P, Vr, Fe Sn (3.00m) J, 50°, P, R, Fe Sn, & Clay, Vn (3.10m) Be, 5°, Cr, S, Clay FILLED, 2 mm.t (3.16m) J, 25°, Cr, S, Clay Vn (3.22m) Be, 5°, Cr, R, Cn (3.33m) J, 55°, P, R, Fe Sn (3.50m) J, 55°, P, R, Fe Sn		Temora Volcanics
50% RETURN	315	3		Extremely Weathered andesite: gravelly silty CLAY, low to medium plasticity, brown, fine to coarse grained andesite and ironstone gravel. ANDESITE: fine grained, grey, trace of light grey speckles and gas bubbles.	XW SW	Hd VH			(3.65m) J, 45°, St, Vr, Fe Sn (3.68m) J, 10°, Ir, Vr, Fe Sn (3.80m) Cr, 15°, 100 mm.t, associated with J at 4.38m (3.88m) J, 70°, P, S, Clay Vn (3.89m) J, 15°, P, Vr, Cn (3.95m) J, 10°, P, S, Clay Vn (4.00m) Ji, 70°, P, Vr, Fe Sn (4.04m) J, 50°, P, Vr, Fe Sn (4.10m) Cr, 50°, 100 mm.t (4.16m) J, 50°, P, R, Fe Sn (4.23m) Be, 10°, P, S, Clay FILLED, 2 mm.t (4.25m) J, 60°, P, Vr, Fe Sn (4.40m) J, 70°, P, S, Clay Vn (4.47m) Be, 10°, P, S, Clay Vn (4.51m) J, 85°, P, S, Clay Vn (4.53m) J, 80°, P, S, Clay Vn (4.65m) J, 50°, P, Vr, Fe Sn (4.72m) Be, 85°, P, S, Clay Vn (4.80m) J, 20°, St, Vr, Fe Sn (4.83m) J, 80°, P, R, Fe Sn (5.06m) J, 10°, P, R, Fe Sn (5.12m) J, 50°, P, R, Fe Sn (5.27m) J, 30°, St, Vr, Fe Sn		
0% RETURN	314	4							(5.48m) J, 50°, P, R, Clay Vn (5.56m) Be, 80°, P, S, Clay FILLED, 5 mm.t (5.61m) J, 60°, P, Vr, Fe Sn		
	313	5							(5.76m) Cr, 50°, 5 mm.t (5.77m) CS, 50°, 5 mm.t (5.85m) J, 40°, P, Vr, Fe Sn (5.93m) J, 20°, P, R, Fe Sn		
	312	6		END OF BOREHOLE AT 6.00 m							
	311	7									

JK 0.02.4.LIB.GLB Log\_JK\_CORED BOREHOLE - MASTER\_35822BF TEMORA.GPJ <-DrawingFile> 25/05/2023 13:19:10.01.00.01 D:\gpl Lab and In Situ Tool - DGD\Lib\_JK\_0.02.4\_2019-05-31 Proj\_JK\_0.01\_0.2018-03-20

## BOREHOLE LOG

**Client:** HEALTH INFRASTRUCTURE  
**Project:** PROPOSED ALTERATIONS AND ADDITIONS  
**Location:** TEMORA HOSPITAL, 169-189 LOFTUS STREET, TEMORA, NSW

**Job No.:** 35822BF      **Method:** SPIRAL AUGER      **R.L. Surface:** ~318.2 m  
**Date:** 3/5/23      **Datum:** AHD  
**Plant Type:** HANJIN DB8      **Logged/Checked By:** C.S.Y./O.F.

Groundwater Record	SAMPLES				Field Tests	RL (m AHD)	Depth (m)	Graphic Log	Unified Classification	DESCRIPTION	Moisture Condition/ Weathering	Strength/ Rel Density	Hand Penetrometer Readings (kPa)	Remarks
	ES	U50	DB	DS										
DRY ON COMPLETION					N = 12 3,6,6  N=SPT 5/ 0mm REFUSAL	318		CL-CI	Silty CLAY: low to medium plasticity, brown, trace of fine to medium grained igneous gravel, and root fibres.	w>PL	(St)		GRASS COVER RESIDUAL	
						317		1	CI	Silty CLAY: medium plasticity, red brown, trace of fine to medium grained andesite gravel.	w>PL	Hd		
						316	2	-		Extremely Weathered andesite: silty clayey SAND, fine to coarse grained, brown, trace of fine grained igneous gravel.	XW	(D)		TEMORA VOLCANICS
						315	3			ANDESITE: brown and grey, fine to medium grained, trace of fine to medium grained quartz gravel, trace of high strength bands.	DW	L - M		LOW TO MODERATE 'V' BIT RESISTANCE
									END OF BOREHOLE AT 3.30 m				'V' BIT REFUSAL	
						314	4							
						313	5							
						312	6							

JK 0.02.4 LIB.GLB Log\_JK AUGERHOLE - MASTER\_35822BF TEMORA.GPJ <-DrawingFile> 25/05/2023 13:11 10.01.00.01 Dgnpl Lab and In Situ Tool - DGD Lib\_JK 9.02.2 2019-05-31 Proj\_JK 9.01.0 2018-03-20

## BOREHOLE LOG

**Client:** HEALTH INFRASTRUCTURE  
**Project:** PROPOSED ALTERATIONS AND ADDITIONS  
**Location:** TEMORA HOSPITAL, 169-189 LOFTUS STREET, TEMORA, NSW

**Job No.:** 35822BF      **Method:** SPIRAL AUGER      **R.L. Surface:** ~319.1 m  
**Date:** 2/5/23      **Datum:** AHD  
**Plant Type:** HANJIN DB8      **Logged/Checked By:** C.S.Y./O.F.



Groundwater Record	SAMPLES				Field Tests	RL (m AHD)	Depth (m)	Graphic Log	Unified Classification	DESCRIPTION	Moisture Condition/ Weathering	Strength/ Rel Density	Hand Penetrometer Readings (kPa)	Remarks		
	ES	U50	DB	DS												
DRY ON COMPLETION					N > 14 11, 14/ 100mm REFUSAL	319			CL-CI	FILL: Silty clay, low to medium plasticity, red brown, with fine to coarse grained quartz and igneous gravel, trace of root fibres.  Sandy Silty CLAY: low to medium plasticity, brown, fine to coarse grained sand, trace of fine to medium grained granite gravel.  Extremely Weathered andesite: gravelly sandy SILT, low plasticity, brown and light brown, fine to coarse grained igneous gravel.  ANDESITE: grey.  END OF BOREHOLE AT 1.30 m	w>PL  w<PL  XW  DW	(VSt - Hd)  (Hd)  H		GRASS COVER  SCREEN: 10.44kg 0-0.2m, NO FCF  RESIDUAL  TEMORA VOLCANICS  HIGH 'V' BIT RESISTANCE 'V' BIT REFUSAL  GROUNDWATER MONITORING WELL INSTALLED TO 1.3m. CLASS 18 MACHINE SLOTTED 50mm DIA. PVC STANDPIPE 1.3m TO 0.12m. 2mm SAND FILTER PACK 1.3m TO 0.12m. BACKFILLED WITH SAND TO THE SURFACE. COMPLETED WITH A CONCRETED GATIC COVER.		
							318	1								
								317	2							
								316	3							
								315	4							
								314	5							
						313	6									

JK 9.02.4 LIB.GLB Log\_JK AUGERHOLE - MASTER\_35822BF TEMORA.GPJ <-DrawingFile> 25/05/2023 13:11 10.01.00.01 D:\gep Lab and in Situ Tool - DGD \Lib\_JK 9.02.4 2019-05-31 Proj\_JK 9.01.0 2018-03-20

## BOREHOLE LOG

<b>Client:</b> HEALTH INFRASTRUCTURE		<b>Project:</b> PROPOSED ALTERATIONS AND ADDITIONS		<b>Location:</b> TEMORA HOSPITAL, 169-189 LOFTUS STREET, TEMORA, NSW	
<b>Job No.:</b> 35822BF		<b>Method:</b> SPIRAL AUGER		<b>R.L. Surface:</b> ~318.8 m	
<b>Date:</b> 2/5/23 TO 3/5/23		<b>Logged/Checked By:</b> C.S.Y./O.F.		<b>Datum:</b> AHD	
<b>Plant Type:</b> HANJIN DB8					



Groundwater Record	SAMPLES				Field Tests	RL (m AHD)	Depth (m)	Graphic Log	Unified Classification	DESCRIPTION	Moisture Condition/ Weathering	Strength/ Rel Density	Hand Penetrometer Readings (kPa)	Remarks
	ES	U50	DB	DS										
DRY ON COMPLETION OF AUGERING	█				N > 11 13,11/ 80mm REFUSAL	318	1	 	-	ASPHALTIC CONCRETE: 20mm.t FILL: Gravelly silty sand, fine to medium grained, brown, fine to coarse grained quartz and igneous gravel.	M			SCREEN: 1.88kg 0.02-0.3m, NO FCF POSSIBLY NATURAL
	█								-	FILL: Silty sand, fine to coarse grained, red brown, trace of fine grained quartz gravel. Extremely Weathered andesite: gravelly sandy SILT, low plasticity, brown, fine to coarse grained sand, fine grained igneous gravel.	XW	(Hd)		TEMORA VOLCANICS VERY LOW 'V' BIT RESISTANCE
						317	2			REFER TO CORED BOREHOLE LOG				MODERATE TO HIGH RESISTANCE
						316	3							
						315	4							
						314	5							
						313	6							
						312								

JK 9.02.4 LIB.GLB Log\_JK AUGERHOLE - MASTER\_35822BF TEMORA.GPJ <-DrawingFile> 25/05/2023 13:11 10.01.00.01 D:\gep Lab and In Situ Tool - DGD \Lib\_JK\_9.02.4\2019-05-31 Proj\_JK\_9.01.0\2018-03-20

## CORED BOREHOLE LOG

**Client:** HEALTH INFRASTRUCTURE  
**Project:** PROPOSED ALTERATIONS AND ADDITIONS  
**Location:** TEMORA HOSPITAL, 169-189 LOFTUS STREET, TEMORA, NSW

**Job No.:** 35822BF      **Core Size:** NMLC      **R.L. Surface:** ~318.8 m  
**Date:** 2/5/23 TO 3/5/23      **Inclination:** VERTICAL      **Datum:** AHD  
**Plant Type:** HANJIN DB8      **Bearing:** N/A      **Logged/Checked By:** C.S.Y./O.F.

Water Loss Level	Barrel Lift	RL (m AHD)	Depth (m)	Graphic Log	CORE DESCRIPTION Rock Type, grain characteristics, colour, texture and fabric, features, inclusions and minor components	Weathering	Strength	POINT LOAD STRENGTH INDEX $I_p(50)$	SPACING (mm)	DEFECT DETAILS		Formation
										Specific	General	
					START CORING AT 1.40m							
					NO CORE 1.82m							
		317	2									
		316	3									
		315	4		ANDESITE: fine to coarse grained, grey, with quartz inclusions.	SW	VH	44.1		(3.22m) Gr, 10 <sup>0</sup> , 30 mm.t (3.33m) J, 40 <sup>0</sup> , P, R, Fe Sn (3.39m) J, 35 <sup>0</sup> , P, Vr, Cn (3.43m) Jh, 45 <sup>0</sup> , P, S, Cn (3.48m) Be, 15 <sup>0</sup> , P, Vr, Cn (3.50m) J, 60 <sup>0</sup> , P, R, Cn (3.55m) Be, 10 <sup>0</sup> , Cr, Vr, Cn (3.60m) Be, 20 <sup>0</sup> , Cr, Vr, Fe Sn (3.70m) J, 70 <sup>0</sup> , P, Vr, Fe Sn, & Gravel FILLED		Temora Volcanics
					END OF BOREHOLE AT 3.80 m							
		314	5									
		313	6									
		312	7									
		311										

JK 0.02.4 LIB.GLB Log\_JK\_CORED BOREHOLE - MASTER\_35822BF TEMORA.GPJ <-DrawingFile> 25/05/2023 13:19 10.01.00.01 D:\ggl Lab and In Situ Tool\_DGD LIB\_JK 0.02.4 2019-05-31 Proj\_JK 0.01.0 2018-03-20

## BOREHOLE LOG

<b>Client:</b> HEALTH INFRASTRUCTURE		<b>Project:</b> PROPOSED ALTERATIONS AND ADDITIONS		<b>Location:</b> TEMORA HOSPITAL, 169-189 LOFTUS STREET, TEMORA, NSW	
<b>Job No.:</b> 35822BF		<b>Method:</b> SPIRAL AUGER		<b>R.L. Surface:</b> ~318.3 m	
<b>Date:</b> 5/5/23		<b>Logged/Checked By:</b> C.S.Y./O.F.		<b>Datum:</b> AHD	
<b>Plant Type:</b> HANJIN DB8					

Groundwater Record	SAMPLES				Field Tests	RL (m AHD)	Depth (m)	Graphic Log	Unified Classification	DESCRIPTION	Moisture Condition/ Weathering	Strength/ Rel Density	Hand Penetrometer Readings (kPa)	Remarks
	ES	U50	DB	DS										
DRY ON COMPLETION					N = 3 1,1,2	318		-	ASPHALTIC CONCRETE: 20mm.t	M			APPEARS POORLY COMPACTED  INSUFFICIENT RETURN FOR BULK SCREEN SAMPLE RESIDUAL	
							1	CL	FILL: Silty sand, fine to medium grained, red brown, with fine to coarse grained igneous gravel.  Sandy Silty CLAY: low plasticity, red brown, fine to coarse grained sand, trace of fine grained igneous and quartz gravel.	w<PL	(Hd)	>600 >600 >600		
					N = 25 5,11,14	317		-	Extremely Weathered andesite: sandy silty CLAY or silty clayey SAND, low plasticity, brown, fine to coarse grained sand, trace of fine grained quartz gravel.	XW	Hd		TEMORA VOLCANICS	
							2							
					N > 11 2,11/ 150mm REFUSAL	316			Extremely Weathered andesite: gravelly silty SAND, fine to coarse grained, brown, fine to medium grained igneous gravel.		VD		NO SPT RECOVERY FROM AUGER	
							3							
					315			ANDESITE: grey, trace of high strength bands.	DW	L		VERY LOW TO LOW 'V' BIT RESISTANCE		
					4									
					314									
					313									
					312				END OF BOREHOLE AT 6.00 m					

JK 9.02.4.LIB.GLB.Log\_JK\_AUGERHOLE - MASTER\_35822BF\_TEMORA.GPJ <-DrawingFile> 25/05/2023 13:11 10.01.00.01 D:\geot\Lab and In Situ Tool - DGD\Lib\_JK\_9.02.4.2019-05-31 Proj\_JK\_9.01.0.2019-03-20





**Borehole No.**  
**9**  
1 / 1

## BOREHOLE LOG

<b>Client:</b> HEALTH INFRASTRUCTURE <b>Project:</b> PROPOSED ALTERATIONS AND ADDITIONS <b>Location:</b> TEMORA HOSPITAL, 169-189 LOFTUS STREET, TEMORA, NSW														
<b>Job No.:</b> 35822BF <b>Date:</b> 3/5/23 <b>Plant Type:</b> HANJIN DB8			<b>Method:</b> SPIRAL AUGER <b>Logged/Checked By:</b> C.S.Y./O.F.				<b>R.L. Surface:</b> ~308.5 m <b>Datum:</b> AHD							
Groundwater Record	SAMPLES				Field Tests	RL (m AHD)	Depth (m)	Graphic Log	Unified Classification	DESCRIPTION	Moisture Condition/ Weathering	Strength/ Rel Density	Hand Penetrometer Readings (kPa)	Remarks
	ES	U50	DB	DS										
DRY ON COMPLETION						308	1		CL-CI	Silty CLAY: low to medium plasticity, red brown, trace of quartz gravel and root fibres.	w<PL	(St - VSt)		GRASS COVER RESIDUAL TOO FRIABLE FOR HP TESTING
						307	2		-	ANDESITE: brown. END OF BOREHOLE AT 1.20 m	DW	H		TEMORA VOLCANICS MODERATE TO HIGH 'V' BIT RESISTANCE 'V' BIT REFUSAL
						306	3							
						305	4							
						304	5							
						303	6							
						302								

JK 9.02.4 LIB.GLB Log\_JK AUGERHOLE - MASTER\_35822BF TEMORA.GPJ <-DrawingFile> 25/05/2023 13:11 10.01.00.01 Dgnpl Lab and In Situ Tool - DGD Lib\_JK 9.02.4 2019-05-31 Proj\_JK 9.01.0 2018-03-20



**Borehole No.**  
**10**  
1 / 1

## BOREHOLE LOG

<b>Client:</b> HEALTH INFRASTRUCTURE <b>Project:</b> PROPOSED ALTERATIONS AND ADDITIONS <b>Location:</b> TEMORA HOSPITAL, 169-189 LOFTUS STREET, TEMORA, NSW														
<b>Job No.:</b> 35822BF <b>Date:</b> 3/5/23 <b>Plant Type:</b> HANJIN DB8			<b>Method:</b> SPIRAL AUGER <b>Logged/Checked By:</b> C.S.Y./O.F.				<b>R.L. Surface:</b> ~307.8 m <b>Datum:</b> AHD							
Groundwater Record	SAMPLES				Field Tests	RL (m AHD)	Depth (m)	Graphic Log	Unified Classification	DESCRIPTION	Moisture Condition/ Weathering	Strength/ Rel Density	Hand Penetrometer Readings (kPa)	Remarks
	ES	U50	DB	DS										
DRY ON COMPLETION						307	1		CL-CI	Silty CLAY: low to medium plasticity, red brown, trace of fine to medium grained quartz gravel and fine to coarse grained andesite gravel.  as above, but brown.	w>PL  w<PL	(St - VSt)		GRASS COVER RESIDUAL TOO FRIABLE FOR HP TESTING
						306	2			END OF BOREHOLE AT 1.50 m				
						305	3							
						304	4							
						303	5							
						302	6							
						301								

JK 0.02.4 LIB.GLB Log\_JK AUGERHOLE - MASTER\_35822BF TEMORA.GPJ <-DrawingFile> 25/05/2023 13:11 10.01.00.01 D:\proj Lab and in Situ Tool - DGD \Lib\_JK\_0.02.4\_2019-05-31 Proj\_JK\_0.01.0\_2018-03-20



**Borehole No.**  
**11**  
1 / 1

## BOREHOLE LOG

<b>Client:</b> HEALTH INFRASTRUCTURE		<b>Project:</b> PROPOSED ALTERATIONS AND ADDITIONS		<b>Location:</b> TEMORA HOSPITAL, 169-189 LOFTUS STREET, TEMORA, NSW										
<b>Job No.:</b> 35822BF		<b>Method:</b> SPIRAL AUGER		<b>R.L. Surface:</b> ~318.1 m										
<b>Date:</b> 3/5/23		<b>Logged/Checked By:</b> C.S.Y./O.F.		<b>Datum:</b> AHD										
<b>Plant Type:</b> HANJIN DB8														
Groundwater Record	SAMPLES				Field Tests	RL (m AHD)	Depth (m)	Graphic Log	Unified Classification	DESCRIPTION	Moisture Condition/ Weathering	Strength/ Rel Density	Hand Penetrometer Readings (kPa)	Remarks
	ES	U50	DB	DS										
DRY ON COMPLETION						318			CL-CI	Silty CLAY: low to medium plasticity, red brown, trace of fine to medium grained igneous gravel, and root fibres.	w-PL			GRASS COVER RESIDUAL TOO FRIABLE FOR HP TESTING
						317	1		-	Extremely Weathered andesite: sandy silty CLAY, low to medium plasticity, red brown, trace of fine to coarse grained igneous gravel.	XW	(Hd)		TEMORA VOLCANICS
						316	2			END OF BOREHOLE AT 1.50 m				
						315	3							
						314	4							
						313	5							
						312	6							

JK 9.02.4 LIB.GLB Log\_JK AUGERHOLE - MASTER\_35822BF TEMORA.GPJ <-DrawingFile> 25/05/2023 13:11 10.01.00.01 Dgnpl Lab and In Situ Tool - DGD Lib JK 9.02.4 2019-05-31 Proj JK 9.01.0 2018-03-20

## BOREHOLE LOG

<b>Client:</b> HEALTH INFRASTRUCTURE <b>Project:</b> PROPOSED ALTERATIONS AND ADDITIONS <b>Location:</b> TEMORA HOSPITAL, 169-189 LOFTUS STREET, TEMORA, NSW														
<b>Job No.:</b> 35822BF			<b>Method:</b> SPIRAL AUGER				<b>R.L. Surface:</b> ~312.6 m							
<b>Date:</b> 3/5/23			<b>Logged/Checked By:</b> C.S.Y./O.F.				<b>Datum:</b> AHD							
<b>Plant Type:</b> HANJIN DB8														
Groundwater Record	SAMPLES				Field Tests	RL (m AHD)	Depth (m)	Graphic Log	Unified Classification	DESCRIPTION	Moisture Condition/ Weathering	Strength/ Rel Density	Hand Penetrometer Readings (kPa)	Remarks
	ES	U50	DB	DS										
DRY ON COMPLETION						312		CL-CI	Silty CLAY: low to medium plasticity, red brown, with fine to coarse grained quartz gravel, trace of quartz boulder, fine grained igneous gravel, and root fibres.	w-PL			GRASS COVER RESIDUAL	
						1			Sandy Silty CLAY: low to medium plasticity, brown, fine to medium grained sand, trace of fine grained igneous and ironstone gravel.	w<PL				
						311			END OF BOREHOLE AT 1.50 m					
						2								
						310								
						3								
						309								
						4								
						308								
						5								
						307								
						6								
						306								

JK 9.02.4 LIB.GLB Log\_JK AUGERHOLE - MASTER\_35822BF TEMORA.GPJ <-DrawingFile> 25/05/2023 13:11 10.01.00.01 Dgnpl Lab and In Situ Tool - DGD Lib JK 9.02.4 2019-05-31 Proj JK 9.01.0 2018-03-20

# JKEnvironments

## ENVIRONMENTAL LOG



Log No.  
**TP13**  
1/1

Environmental logs are not to be used for geotechnical purposes

SDUP4: 0-0.1m

**Client:** HEALTH INFRASTRUCTURE  
**Project:** PROPOSED ALTERATIONS AND ADDITIONS  
**Location:** TEMORA HOSPITAL, 169-189 LOFTUS STREET, TEMORA, NSW

**Job No.:** E35822PR      **Method:** STRIP TRENCH      **R.L. Surface:** ≈ 319.3m  
**Date:** 4/5/23      **Datum:** AHD  
**Plant Type:** 3T EXCAVATOR      **Logged/Checked by:** A.D./T.H.

Groundwater Record	SAMPLES				Field Tests	Depth (m)	Graphic Log	Unified Classification	DESCRIPTION	Moisture Condition/Weathering	Strength/Rel. Density	Hand Penetrometer Readings (kPa.)	Remarks
	ES	ASS	ASB	SAL									
DRY ON COMPLETION	█	█	█	█	█	0			FILL: Silty clay, low to medium plasticity, brown, trace of quartz gravel and root fibres.	w≈PL			GRASS COVER
	█	█	█	█	█	0.5		CI-CH	Silty CLAY: medium to high plasticity, red brown, trace of volcanic breccia.	w≈PL			SCREEN: 10.52kg 0-0.1m, NO FCF SCREEN: 10.22kg 0.1-0.3m, NO FCF RESIDUAL
						1			END OF BOREHOLE AT 1.05m				
						1.5							
						2							
						2.5							
						3							
						3.5							

# JKEnvironments

## ENVIRONMENTAL LOG



Log No.  
**TP14**  
1/1

Environmental logs are not to be used for geotechnical purposes

SDUP3: 0-0.1m

**Client:** HEALTH INFRASTRUCTURE  
**Project:** PROPOSED ALTERATIONS AND ADDITIONS  
**Location:** TEMORA HOSPITAL, 169-189 LOFTUS STREET, TEMORA, NSW

**Job No.:** E35822PR      **Method:** STRIP TRENCH      **R.L. Surface:** ≈ 320.5m  
**Date:** 4/5/23      **Datum:** AHD  
**Plant Type:** 3T EXCAVATOR      **Logged/Checked by:** A.D./T.H.

Groundwater Record	SAMPLES				Field Tests	Depth (m)	Graphic Log	Unified Classification	DESCRIPTION	Moisture Condition/ Weathering	Strength/ Rel. Density	Hand Penetrometer Readings (kPa.)	Remarks
	ES	ASS	ASB	SAL									
DRY ON COMPLETION						0			FILL: Silty clay, low to medium plasticity, brown, trace of igneous and quartz gravel, volcanic breccia, metal fragments and root fibres.	w~PL			GRASS COVER
						0.2		CI-CH	Silty CLAY: medium to high plasticity, red brown, trace of quartz and volcanic breccia.	w~PL			SCREEN: 12.31kg 0-0.2m, NO FCF RESIDUAL
						0.5		-	Extremely Weathered andesite: silty SAND, fine to coarse grained, brown.	XW			TEMORA VOLCANICS
						1			END OF BOREHOLE AT 1.0m				
						1.5							
						2							
						2.5							
						3							
						3.5							

# JKEnvironments

## ENVIRONMENTAL LOG



Log No.  
**TP15**  
1/1

Environmental logs are not to be used for geotechnical purposes

SDUP2: 0-0.1m

**Client:** HEALTH INFRASTRUCTURE  
**Project:** PROPOSED ALTERATIONS AND ADDITIONS  
**Location:** TEMORA HOSPITAL, 169-189 LOFTUS STREET, TEMORA, NSW

**Job No.:** E35822PR      **Method:** STRIP TRENCH      **R.L. Surface:** ≈ 316.7m  
**Date:** 4/5/23      **Datum:** AHD  
**Plant Type:** 3T EXCAVATOR      **Logged/Checked by:** A.D./T.H.

Groundwater Record	SAMPLES				Field Tests	Depth (m)	Graphic Log	Unified Classification	DESCRIPTION	Moisture Condition/ Weathering	Strength/ Rel. Density	Hand Penetrometer Readings (kPa.)	Remarks
	ES	ASS	ASB	SAL									
DRY ON COMPLETION						0			FILL: Silty clay, low to medium plasticity, brown, trace of quartz gravel, and root fibres.	w≈PL			GRASS COVER SCREEN: 10.29kg 0-0.1m, NO FCF SCREEN: 10.34kg 0.1-0.5m, NO FCF
						0.5			FILL: Sandy silty clay, low to medium plasticity, red brown, trace of volcanic breccia.	w≈PL			SCREEN: 12.52kg 0.5-1.1m, NO FCF
						1			CL-CI	Silty CLAY: low to medium plasticity, red brown, trace of quartz gravel.	w≈PL		
						1.5			END OF BOREHOLE AT 1.5m				
						2							
						2.5							
						3							
						3.5							

# JKEnvironments

## ENVIRONMENTAL LOG



Log No.  
**TP16**  
1/1

Environmental logs are not to be used for geotechnical purposes

SDUP1: 0-0.1m

**Client:** HEALTH INFRASTRUCTURE  
**Project:** PROPOSED ALTERATIONS AND ADDITIONS  
**Location:** TEMORA HOSPITAL, 169-189 LOFTUS STREET, TEMORA, NSW

**Job No.:** E35822PR      **Method:** STRIP TRENCH      **R.L. Surface:** ≈ 316.6m  
**Date:** 4/5/23      **Datum:** AHD  
**Plant Type:** 3T EXCAVATOR      **Logged/Checked by:** A.D./T.H.

Groundwater Record	SAMPLES				Field Tests	Depth (m)	Graphic Log	Unified Classification	DESCRIPTION	Moisture Condition/ Weathering	Strength/ Rel. Density	Hand Penetrometer Readings (kPa.)	Remarks
	ES	ASS	ASB	SAL									
DRY ON COMPLETION						0		CL-CI	Silty CLAY: low to medium plasticity, brown, trace of quartz gravel, and root fibres.	w≈PL			GRASS COVER RESIDUAL
						0.5		CL-CH	Silty CLAY: medium to high plasticity, red brown, trace of volcanic breccia.	w≈PL			
						1		-	Extremely Weathered andesite: silty SAND, fine to coarse grained, brown.	XW			TEMORA VOLCANICS
						1			END OF BOREHOLE AT 1.0m				
						1.5							
						2							
						2.5							
						3							
						3.5							





# ENVIRONMENTAL LOGS EXPLANATION NOTES

## INTRODUCTION

These notes have been provided to amplify the environmental report in regard to classification methods, field procedures and certain matters relating to the logging of soil and rock. Not all notes are necessarily relevant to all reports.

Where geotechnical borehole logs are utilised for environmental purpose, reference should also be made to the explanatory notes included in the geotechnical report. Environmental logs are not suitable for geotechnical purposes.

The ground is a product of continuing natural and man-made processes and therefore exhibits a variety of characteristics and properties which vary from place to place and can change with time. Environmental studies include gathering and assimilating limited facts about these characteristics and properties in order to understand or predict the behaviour of the ground on a particular site under certain conditions. This report may contain such facts obtained by inspection, excavation, probing, sampling, testing or other means of investigation. If so, they are directly relevant only to the ground at the place where and time when the investigation was carried out.

## DESCRIPTION AND CLASSIFICATION METHODS

The methods of description and classification of soils and rocks used in this report are based on Australian Standard 1726:2017 'Geotechnical Site Investigations'. In general, descriptions cover the following properties – soil or rock type, colour, structure, strength or density, and inclusions. Identification and classification of soil and rock involves judgement and the Company infers accuracy only to the extent that is common in current geoenvironmental practice.

Soil types are described according to the predominating particle size and behaviour as set out in the attached soil classification table qualified by the grading of other particles present (eg. sandy clay) as set out below:

Soil Classification	Particle Size
Clay	< 0.002mm
Silt	0.002 to 0.075mm
Sand	0.075 to 2.36mm
Gravel	2.36 to 63mm
Cobbles	63 to 200mm
Boulders	> 200mm

Non-cohesive soils are classified on the basis of relative density, generally from the results of Standard Penetration Test (SPT) as below:

Relative Density	SPT 'N' Value (blows/300mm)
Very loose (VL)	< 4
Loose (L)	4 to 10
Medium dense (MD)	10 to 30
Dense (D)	30 to 50
Very Dense (VD)	> 50

Cohesive soils are classified on the basis of strength (consistency) either by use of a hand penetrometer, vane shear, laboratory testing and/or tactile engineering examination. The strength terms are defined as follows.

Classification	Unconfined Compressive Strength (kPa)	Indicative Undrained Shear Strength (kPa)
Very Soft (VS)	≤ 25	≤ 12
Soft (S)	> 25 and ≤ 50	> 12 and ≤ 25
Firm (F)	> 50 and ≤ 100	> 25 and ≤ 50
Stiff (St)	> 100 and ≤ 200	> 50 and ≤ 100
Very Stiff (VSt)	> 200 and ≤ 400	> 100 and ≤ 200
Hard (Hd)	> 400	> 200
Friable (Fr)	Strength not attainable – soil crumbles	

Rock types are classified by their geological names, together with descriptive terms regarding weathering, strength, defects, etc. Where relevant, further information regarding rock classification is given in the text of the report. In the Sydney Basin, 'shale' is used to describe fissile mudstone, with a weakness parallel to bedding. Rocks with alternating inter-laminations of different grain size (eg. siltstone/claystone and siltstone/fine grained sandstone) are referred to as 'laminite'.

## INVESTIGATION METHODS

The following is a brief summary of investigation methods currently adopted by the Company and some comments on their use and application. All methods except test pits, hand auger drilling and portable Dynamic Cone Penetrometers require the use of a mechanical rig which is commonly mounted on a truck chassis or track base.

**Test Pits:** These are normally excavated with a backhoe or a tracked excavator, allowing close examination of the insitu soils and 'weaker' bedrock if it is safe to descend into the pit. The depth of penetration is limited to about 3m for a backhoe and up to 6m for a large excavator. Limitations of test pits are the problems associated with disturbance and difficulty of reinstatement and the consequent effects on close-by structures. Care must be taken if construction is to be carried out near test pit locations to either properly recompact the backfill during construction or to design and construct the

structure so as not to be adversely affected by poorly compacted backfill at the test pit location.

**Hand Auger Drilling:** A borehole of 50mm to 100mm diameter is advanced by manually operated equipment. Refusal of the hand auger can occur on a variety of materials such as obstructions within any fill, tree roots, hard clay, gravel or ironstone, cobbles and boulders, and does not necessarily indicate rock level.

**Continuous Spiral Flight Augers:** The borehole is advanced using 75mm to 115mm diameter continuous spiral flight augers, which are withdrawn at intervals to allow sampling and insitu testing. This is a relatively economical means of drilling in clays and in sands above the water table. Samples are returned to the surface by the flights or may be collected after withdrawal of the auger flights, but they can be very disturbed and layers may become mixed. Information from the auger sampling (as distinct from specific sampling by SPTs or undisturbed samples) is of limited reliability due to mixing or softening of samples by groundwater, or uncertainties as to the original depth of the samples. Augering below the groundwater table is of even lesser reliability than augering above the water table.

**Rock Augering:** Use can be made of a Tungsten Carbide (TC) bit for auger drilling into rock to indicate rock quality and continuity by variation in drilling resistance and from examination of recovered rock cuttings. This method of investigation is quick and relatively inexpensive but provides only an indication of the likely rock strength and predicted values may be in error by a strength order. Where rock strengths may have a significant impact on construction feasibility or costs, then further investigation by means of cored boreholes may be warranted.

**Wash Boring:** The borehole is usually advanced by a rotary bit, with water being pumped down the drill rods and returned up the annulus, carrying the drill cuttings. Only major changes in stratification can be assessed from the cuttings, together with some information from “feel” and rate of penetration.

**Mud Stabilised Drilling:** Either Wash Boring or Continuous Core Drilling can use drilling mud as a circulating fluid to stabilise the borehole. The term ‘mud’ encompasses a range of products ranging from bentonite to polymers. The mud tends to mask the cuttings and reliable identification is only possible from intermittent intact sampling (eg. from SPT and U50 samples) or from rock coring, etc.

**Continuous Core Drilling:** A continuous core sample is obtained using a diamond tipped core barrel. Provided full core recovery is achieved (which is not always possible in very low strength rocks and granular soils), this technique provides a very reliable (but relatively expensive) method of investigation. In rocks, NMLC or HQ triple tube core barrels, which give a core of about 50mm and 61mm diameter, respectively, is usually used with water flush. The length of core recovered is compared to the length drilled and any length not recovered is shown as NO CORE. The location of NO CORE recovery is determined on site by the supervising engineer; where the location is uncertain, the loss is placed at the bottom of the drill run.

**Standard Penetration Tests:** Standard Penetration Tests (SPT) are used mainly in non-cohesive soils, but can also be used in cohesive soils, as a means of indicating density or strength and also of obtaining a relatively undisturbed sample. The test procedure is

described in Australian Standard 1289.6.3.1–2004 (R2016) ‘*Methods of Testing Soils for Engineering Purposes, Soil Strength and Consolidation Tests – Determination of the Penetration Resistance of a Soil – Standard Penetration Test (SPT)*’.

The test is carried out in a borehole by driving a 50mm diameter split sample tube with a tapered shoe, under the impact of a 63.5kg hammer with a free fall of 760mm. It is normal for the tube to be driven in three successive 150mm increments and the ‘N’ value is taken as the number of blows for the last 300mm. In dense sands, very hard clays or weak rock, the full 450mm penetration may not be practicable and the test is discontinued.

The test results are reported in the following form:

- In the case where full penetration is obtained with successive blow counts for each 150mm of, say, 4, 6 and 7 blows, as

N = 13  
4, 6, 7

- In a case where the test is discontinued short of full penetration, say after 15 blows for the first 150mm and 30 blows for the next 40mm, as

N > 30  
15, 30/40mm

The results of the test can be related empirically to the engineering properties of the soil.

A modification to the SPT is where the same driving system is used with a solid 60° tipped steel cone of the same diameter as the SPT hollow sampler. The solid cone can be continuously driven for some distance in soft clays or loose sands, or may be used where damage would otherwise occur to the SPT. The results of this Solid Cone Penetration Test (SCPT) are shown as ‘N<sub>c</sub>’ on the borehole logs, together with the number of blows per 150mm penetration.

## LOGS

The borehole or test pit logs presented herein are an interpretation of the subsurface conditions, and their reliability will depend to some extent on the frequency of sampling and the method of drilling or excavation. Ideally, continuous undisturbed sampling or core drilling will enable the most reliable assessment, but is not always practicable or possible to justify on economic grounds. In any case, the boreholes or test pits represent only a very small sample of the total subsurface conditions.

The terms and symbols used in preparation of the logs are defined in the following pages.

Interpretation of the information shown on the logs, and its application to design and construction, should therefore take into account the spacing of boreholes or test pits, the method of drilling or excavation, the frequency of sampling and testing and the possibility of other than ‘straight line’ variations between the boreholes or test pits. Subsurface conditions between boreholes or test pits may vary significantly from conditions encountered at the borehole or test pit locations.



---

## **GROUNDWATER**

Where groundwater levels are measured in boreholes, there are several potential problems:

- Although groundwater may be present, in low permeability soils it may enter the hole slowly or perhaps not at all during the time it is left open.
- A localised perched water table may lead to an erroneous indication of the true water table.
- Water table levels will vary from time to time with seasons or recent weather changes and may not be the same at the time of construction.
- The use of water or mud as a drilling fluid will mask any groundwater inflow. Water has to be blown out of the hole and drilling mud must be washed out of the hole or 'reverted' chemically if reliable water observations are to be made.

More reliable measurements can be made by installing standpipes which are read after the groundwater level has stabilised at intervals ranging from several days to perhaps weeks for low permeability soils. Piezometers, sealed in a particular stratum, may be advisable in low permeability soils or where there may be interference from perched water tables or surface water.

## **FILL**

The presence of fill materials can often be determined only by the inclusion of foreign objects (eg. bricks, steel, etc) or by distinctly unusual colour, texture or fabric. Identification of the extent of fill materials will also depend on investigation methods and frequency. Where natural soils similar to those at the site are used for fill, it may be difficult with limited testing and sampling to reliably assess the extent of the fill.

The presence of fill materials is usually regarded with caution as the possible variation in density and material type is much greater than with natural soil deposits. Consequently, there is an increased risk of adverse environmental characteristics or behaviour. If the volume and nature of fill is of importance to a project, then frequent test pit excavations are preferable to boreholes.

## **LABORATORY TESTING**

Laboratory testing has not been undertaken to confirm the soil classification and rock strengths indicated on the environmental logs unless noted in the report.

## SYMBOL LEGENDS

### SOIL



FILL



TOPSOIL



CLAY (CL, CI, CH)



SILT (ML, MH)



SAND (SP, SW)



GRAVEL (GP, GW)



SANDY CLAY (CL, CI, CH)



SILTY CLAY (CL, CI, CH)



CLAYEY SAND (SC)



SILTY SAND (SM)



GRAVELLY CLAY (CL, CI, CH)



CLAYEY GRAVEL (GC)



SANDY SILT (ML, MH)



PEAT AND HIGHLY ORGANIC SOILS (Pt)

### ROCK



CONGLOMERATE



SANDSTONE



SHALE/MUDSTONE



SILTSTONE



CLAYSTONE



COAL



LAMINITE



LIMESTONE



PHYLLITE, SCHIST



TUFF



GRANITE, GABBRO



DOLERITE, DIORITE



BASALT, ANDESITE



QUARTZITE

### OTHER MATERIALS



BRICKS OR PAVERS



CONCRETE



ASPHALTIC CONCRETE



## CLASSIFICATION OF COARSE AND FINE GRAINED SOILS

Major Divisions	Group Symbol	Typical Names	Field Classification of Sand and Gravel	Laboratory Classification		
Coarse grained soil (more than 68% of soil excluding oversize fraction is greater than 0.075mm)	GRAVEL (more than half of coarse fraction is larger than 2.36mm)	GW	Gravel and gravel-sand mixtures, little or no fines	Wide range in grain size and substantial amounts of all intermediate sizes, not enough fines to bind coarse grains, no dry strength	≤ 5% fines	$C_u > 4$ $1 < C_c < 3$
		GP	Gravel and gravel-sand mixtures, little or no fines, uniform gravels	Predominantly one size or range of sizes with some intermediate sizes missing, not enough fines to bind coarse grains, no dry strength	≤ 5% fines	Fails to comply with above
		GM	Gravel-silt mixtures and gravel-sand-silt mixtures	'Dirty' materials with excess of non-plastic fines, zero to medium dry strength	≥ 12% fines, fines are silty	Fines behave as silt
		GC	Gravel-clay mixtures and gravel-sand-clay mixtures	'Dirty' materials with excess of plastic fines, medium to high dry strength	≥ 12% fines, fines are clayey	Fines behave as clay
	SAND (more than half of coarse fraction is smaller than 2.36mm)	SW	Sand and gravel-sand mixtures, little or no fines	Wide range in grain size and substantial amounts of all intermediate sizes, not enough fines to bind coarse grains, no dry strength	≤ 5% fines	$C_u > 6$ $1 < C_c < 3$
		SP	Sand and gravel-sand mixtures, little or no fines	Predominantly one size or range of sizes with some intermediate sizes missing, not enough fines to bind coarse grains, no dry strength	≤ 5% fines	Fails to comply with above
		SM	Sand-silt mixtures	'Dirty' materials with excess of non-plastic fines, zero to medium dry strength	≥ 12% fines, fines are silty	N/A
		SC	Sand-clay mixtures	'Dirty' materials with excess of plastic fines, medium to high dry strength	≥ 12% fines, fines are clayey	

### Laboratory Classification Criteria

A well graded coarse grained soil is one for which the coefficient of uniformity  $C_u > 4$  and the coefficient of curvature  $1 < C_c < 3$ . Otherwise, the soil is poorly graded. These coefficients are given by:

$$C_u = \frac{D_{60}}{D_{10}} \quad \text{and} \quad C_c = \frac{(D_{30})^2}{D_{10} D_{60}}$$


Where  $D_{10}$ ,  $D_{30}$  and  $D_{60}$  are those grain sizes for which 10%, 30% and 60% of the soil grains, respectively, are smaller.

#### NOTES:

- For a coarse grained soil with a fines content between 5% and 12%, the soil is given a dual classification comprising the two group symbols separated by a dash; for example, for a poorly graded gravel with between 5% and 12% silt fines, the classification is GP-GM.
- Where the grading is determined from laboratory tests, it is defined by coefficients of curvature ( $C_c$ ) and uniformity ( $C_u$ ) derived from the particle size distribution curve.
- Clay soils with liquid limits  $> 35\%$  and  $\leq 50\%$  may be classified as being of medium plasticity.
- The U line on the Modified Casagrande Chart is an approximate upper bound for most natural soils.

Major Divisions	Group Symbol	Typical Names	Field Classification of Silt and Clay			Laboratory Classification	
			Dry Strength	Dilatancy	Toughness		
fine grained soils (more than 35% of soil excluding oversize fraction is less than 0.075mm)	SILT and CLAY (low to medium plasticity)	ML	Inorganic silt and very fine sand, rock flour, silty or clayey fine sand or silt with low plasticity	None to low	Slow to rapid	Low	Below A line
		CL, CI	Inorganic clay of low to medium plasticity, gravelly clay, sandy clay	Medium to high	None to slow	Medium	Above A line
		OL	Organic silt	Low to medium	Slow	Low	Below A line
	SILT and CLAY (high plasticity)	MH	Inorganic silt	Low to medium	None to slow	Low to medium	Below A line
		CH	Inorganic clay of high plasticity	High to very high	None	High	Above A line
		OH	Organic clay of medium to high plasticity, organic silt	Medium to high	None to very slow	Low to medium	Below A line
	Highly organic soil	Pt	Peat, highly organic soil	–	–	–	–

**Modified Casagrande Chart for Classifying Silts and Clays according to their Behaviour**





## LOG SYMBOLS

Log Column	Symbol	Definition		
Groundwater Record	▼	Standing water level. Time delay following completion of drilling/excavation may be shown.		
	⊖	Extent of borehole/test pit collapse shortly after drilling/excavation.		
	▶	Groundwater seepage into borehole or test pit noted during drilling or excavation.		
Samples	ES	Sample taken over depth indicated, for environmental analysis.		
	U50	Undisturbed 50mm diameter tube sample taken over depth indicated.		
	DB	Bulk disturbed sample taken over depth indicated.		
	DS	Small disturbed bag sample taken over depth indicated.		
	ASB	Soil sample taken over depth indicated, for asbestos analysis.		
	ASS	Soil sample taken over depth indicated, for acid sulfate soil analysis.		
	SAL	Soil sample taken over depth indicated, for salinity analysis.		
PFAS	Soil sample taken over depth indicated, for analysis of Per- and Polyfluoroalkyl Substances.			
Field Tests	N = 17 4, 7, 10	Standard Penetration Test (SPT) performed between depths indicated by lines. Individual figures show blows per 150mm penetration. 'Refusal' refers to apparent hammer refusal within the corresponding 150mm depth increment.		
	N <sub>c</sub> =	5	Solid Cone Penetration Test (SCPT) performed between depths indicated by lines. Individual figures show blows per 150mm penetration for 60° solid cone driven by SPT hammer. 'R' refers to apparent hammer refusal within the corresponding 150mm depth increment.	
		7		
		3R		
VNS = 25 PID = 100	Vane shear reading in kPa of undrained shear strength. Photoionisation detector reading in ppm (soil sample headspace test).			
Moisture Condition (Fine Grained Soils)	w > PL	Moisture content estimated to be greater than plastic limit.		
	w ≈ PL	Moisture content estimated to be approximately equal to plastic limit.		
	w < PL	Moisture content estimated to be less than plastic limit.		
	w ≈ LL	Moisture content estimated to be near liquid limit.		
	w > LL	Moisture content estimated to be wet of liquid limit.		
	(Coarse Grained Soils)	D	DRY – runs freely through fingers.	
M		MOIST – does not run freely but no free water visible on soil surface.		
W		WET – free water visible on soil surface.		
Strength (Consistency) Cohesive Soils	VS	VERY SOFT – unconfined compressive strength ≤ 25kPa.		
	S	SOFT – unconfined compressive strength > 25kPa and ≤ 50kPa.		
	F	FIRM – unconfined compressive strength > 50kPa and ≤ 100kPa.		
	St	STIFF – unconfined compressive strength > 100kPa and ≤ 200kPa.		
	VSt	VERY STIFF – unconfined compressive strength > 200kPa and ≤ 400kPa.		
	Hd	HARD – unconfined compressive strength > 400kPa.		
	Fr	FRIABLE – strength not attainable, soil crumbles.		
	( )	Bracketed symbol indicates estimated consistency based on tactile examination or other assessment.		
Density Index/ Relative Density (Cohesionless Soils)	VL	VERY LOOSE	Density Index (I <sub>D</sub> ) Range (%)	SPT 'N' Value Range (Blows/300mm)
	L	LOOSE	≤ 15	0 – 4
	MD	MEDIUM DENSE	> 15 and ≤ 35	4 – 10
	D	DENSE	> 35 and ≤ 65	10 – 30
	VD	VERY DENSE	> 65 and ≤ 85	30 – 50
			> 85	> 50
	( )			Bracketed symbol indicates estimated density based on ease of drilling or other assessment.



Log Column	Symbol	Definition
Hand Penetrometer Readings	300 250	Measures reading in kPa of unconfined compressive strength. Numbers indicate individual test results on representative undisturbed material unless noted otherwise.
Remarks	'V' bit 'TC' bit <b>T</b> <sub>60</sub> Soil Origin	<p>Hardened steel 'V' shaped bit.</p> <p>Twin pronged tungsten carbide bit.</p> <p>Penetration of auger string in mm under static load of rig applied by drill head hydraulics without rotation of augers.</p> <p>The geological origin of the soil can generally be described as:</p> <p><b>RESIDUAL</b> – soil formed directly from insitu weathering of the underlying rock. No visible structure or fabric of the parent rock.</p> <p><b>EXTREMELY WEATHERED</b> – soil formed directly from insitu weathering of the underlying rock. Material is of soil strength but retains the structure and/or fabric of the parent rock.</p> <p><b>ALLUVIAL</b> – soil deposited by creeks and rivers.</p> <p><b>ESTUARINE</b> – soil deposited in coastal estuaries, including sediments caused by inflowing creeks and rivers, and tidal currents.</p> <p><b>MARINE</b> – soil deposited in a marine environment.</p> <p><b>AEOLIAN</b> – soil carried and deposited by wind.</p> <p><b>COLLUVIAL</b> – soil and rock debris transported downslope by gravity, with or without the assistance of flowing water. Colluvium is usually a thick deposit formed from a landslide. The description 'slopewash' is used for thinner surficial deposits.</p> <p><b>LITTORAL</b> – beach deposited soil.</p>



## Classification of Material Weathering

Term	Abbreviation	Definition
Residual Soil	RS	Material is weathered to such an extent that it has soil properties. Mass structure and material texture and fabric of original rock are no longer visible, but the soil has not been significantly transported.
Extremely Weathered	XW	Material is weathered to such an extent that it has soil properties. Mass structure and material texture and fabric of original rock are still visible.
Highly Weathered	Distinctly Weathered (Note 1)	The whole of the rock material is discoloured, usually by iron staining or bleaching to the extent that the colour of the original rock is not recognisable. Rock strength is significantly changed by weathering. Some primary minerals have weathered to clay minerals. Porosity may be increased by leaching, or may be decreased due to deposition of weathering products in pores.
Moderately Weathered		
Slightly Weathered	SW	Rock is partially discoloured with staining or bleaching along joints but shows little or no change of strength from fresh rock.
Fresh	FR	Rock shows no sign of decomposition of individual minerals or colour changes.

**NOTE 1:** The term 'Distinctly Weathered' is used where it is not practicable to distinguish between 'Highly Weathered' and 'Moderately Weathered' rock. 'Distinctly Weathered' is defined as follows: 'Rock strength usually changed by weathering. The rock may be highly discoloured, usually by iron staining. Porosity may be increased by leaching, or may be decreased due to deposition of weathering products in pores'. There is some change in rock strength.

## Rock Material Strength Classification

Term	Abbreviation	Uniaxial Compressive Strength (MPa)	Guide to Strength	
			Point Load Strength Index $I_{s(50)}$ (MPa)	Field Assessment
Very Low Strength	VL	0.6 to 2	0.03 to 0.1	Material crumbles under firm blows with sharp end of pick; can be peeled with knife; too hard to cut a triaxial sample by hand. Pieces up to 30mm thick can be broken by finger pressure.
Low Strength	L	2 to 6	0.1 to 0.3	Easily scored with a knife; indentations 1mm to 3mm show in the specimen with firm blows of the pick point; has dull sound under hammer. A piece of core 150mm long by 50mm diameter may be broken by hand. Sharp edges of core may be friable and break during handling.
Medium Strength	M	6 to 20	0.3 to 1	Scored with a knife; a piece of core 150mm long by 50mm diameter can be broken by hand with difficulty.
High Strength	H	20 to 60	1 to 3	A piece of core 150mm long by 50mm diameter cannot be broken by hand but can be broken by a pick with a single firm blow; rock rings under hammer.
Very High Strength	VH	60 to 200	3 to 10	Hand specimen breaks with pick after more than one blow; rock rings under hammer.
Extremely High Strength	EH	> 200	> 10	Specimen requires many blows with geological pick to break through intact material; rock rings under hammer.





---

## **Appendix E: Laboratory Reports & COC Documents**

## CERTIFICATE OF ANALYSIS 322581

### Client Details

<b>Client</b>	JK Environments
<b>Attention</b>	C Ridley
<b>Address</b>	PO Box 976, North Ryde BC, NSW, 1670

### Sample Details

<b>Your Reference</b>	<b><u>E35822PR, Temora</u></b>
<b>Number of Samples</b>	44 Soil, 1 Water, 2 Material
<b>Date samples received</b>	08/05/2023
<b>Date completed instructions received</b>	08/05/2023

### Analysis Details

Please refer to the following pages for results, methodology summary and quality control data.  
 Samples were analysed as received from the client. Results relate specifically to the samples as received.  
 Results are reported on a dry weight basis for solids and on an as received basis for other matrices.  
**Please refer to the last page of this report for any comments relating to the results.**

### Report Details

<b>Date results requested by</b>	15/05/2023
<b>Date of Issue</b>	15/05/2023
NATA Accreditation Number 2901. This document shall not be reproduced except in full.	
Accredited for compliance with ISO/IEC 17025 - Testing. <b>Tests not covered by NATA are denoted with *</b>	


#### **Asbestos Approved By**

Analysed by Asbestos Approved Analyst: Nyovan Moonean, Anthony Clark  
 Authorised by Asbestos Approved Signatory: Lucy Zhu

#### **Results Approved By**

Dragana Tomas, Senior Chemist  
 Greta Petzold, Operation Manager  
 Hannah Nguyen, Metals Supervisor  
 Kyle Gavriyl, Senior Chemist  
 Liam Timmins, Organics Supervisor  
 Loren Bardwell, Development Chemist  
 Lucy Zhu, Asbestos Supervisor

#### **Authorised By**



Nancy Zhang, Laboratory Manager

vTRH(C6-C10)/BTEXN in Soil						
Our Reference		322581-1	322581-3	322581-4	322581-5	322581-6
Your Reference	UNITS	BH1	BH1	BH2	BH2	BH2
Depth		0-0.3	0.8-1.0	0-0.2	0.3-0.5	0.8-1.0
Date Sampled		4/05/2023	4/05/2023	3/05/2023	3/05/2023	3/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
TRH C <sub>6</sub> - C <sub>9</sub>	mg/kg	<25	<25	<25	<25	<25
TRH C <sub>6</sub> - C <sub>10</sub>	mg/kg	<25	<25	<25	<25	<25
vTPH C <sub>6</sub> - C <sub>10</sub> less BTEX (F1)	mg/kg	<25	<25	<25	<25	<25
Benzene	mg/kg	<0.2	<0.2	<0.2	<0.2	<0.2
Toluene	mg/kg	<0.5	<0.5	<0.5	<0.5	<0.5
Ethylbenzene	mg/kg	<1	<1	<1	<1	<1
m+p-xylene	mg/kg	<2	<2	<2	<2	<2
o-Xylene	mg/kg	<1	<1	<1	<1	<1
Naphthalene	mg/kg	<1	<1	<1	<1	<1
Total +ve Xylenes	mg/kg	<1	<1	<1	<1	<1
Surrogate aaa-Trifluorotoluene	%	111	108	109	105	107

vTRH(C6-C10)/BTEXN in Soil						
Our Reference		322581-7	322581-8	322581-10	322581-11	322581-12
Your Reference	UNITS	BH3	BH3	BH3	BH4	BH4
Depth		0-0.1	0.3-0.5	1.3-1.5	0-0.1	0.3-0.5
Date Sampled		4/05/2023	4/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
TRH C <sub>6</sub> - C <sub>9</sub>	mg/kg	<25	<25	<25	<25	<25
TRH C <sub>6</sub> - C <sub>10</sub>	mg/kg	<25	<25	<25	<25	<25
vTPH C <sub>6</sub> - C <sub>10</sub> less BTEX (F1)	mg/kg	<25	<25	<25	<25	<25
Benzene	mg/kg	<0.2	<0.2	<0.2	<0.2	<0.2
Toluene	mg/kg	<0.5	<0.5	<0.5	<0.5	<0.5
Ethylbenzene	mg/kg	<1	<1	<1	<1	<1
m+p-xylene	mg/kg	<2	<2	<2	<2	<2
o-Xylene	mg/kg	<1	<1	<1	<1	<1
Naphthalene	mg/kg	<1	2	<1	<1	<1
Total +ve Xylenes	mg/kg	<1	<1	<1	<1	<1
Surrogate aaa-Trifluorotoluene	%	110	113	107	107	110

vTRH(C6-C10)/BTEXN in Soil						
Our Reference		322581-13	322581-14	322581-16	322581-17	322581-18
Your Reference	UNITS	BH4	BH5	BH5	BH6	BH6
Depth		0.8-1.0	0-0.1	0.8-1.0	0.02-0.3	0.3-0.5
Date Sampled		4/05/2023	3/05/2023	3/05/2023	02/05/2023	02/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
TRH C <sub>6</sub> - C <sub>9</sub>	mg/kg	<25	<25	<25	<25	<25
TRH C <sub>6</sub> - C <sub>10</sub>	mg/kg	<25	<25	<25	<25	<25
vTPH C <sub>6</sub> - C <sub>10</sub> less BTEX (F1)	mg/kg	<25	<25	<25	<25	<25
Benzene	mg/kg	<0.2	<0.2	<0.2	<0.2	<0.2
Toluene	mg/kg	<0.5	<0.5	<0.5	<0.5	<0.5
Ethylbenzene	mg/kg	<1	<1	<1	<1	<1
m+p-xylene	mg/kg	<2	<2	<2	<2	<2
o-Xylene	mg/kg	<1	<1	<1	<1	<1
Naphthalene	mg/kg	<1	<1	<1	<1	<1
Total +ve Xylenes	mg/kg	<1	<1	<1	<1	<1
Surrogate aaa-Trifluorotoluene	%	112	105	109	108	114

vTRH(C6-C10)/BTEXN in Soil						
Our Reference		322581-19	322581-20	322581-21	322581-23	322581-24
Your Reference	UNITS	BH6	BH7	BH7	BH8	BH8
Depth		0.8-1.0	0-0.1	0.3-0.5	0.02-0.2	0.3-0.5
Date Sampled		02/05/2023	02/05/2023	02/05/2023	05/05/2023	05/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
TRH C <sub>6</sub> - C <sub>9</sub>	mg/kg	<25	<25	<25	<25	<25
TRH C <sub>6</sub> - C <sub>10</sub>	mg/kg	<25	<25	<25	<25	<25
vTPH C <sub>6</sub> - C <sub>10</sub> less BTEX (F1)	mg/kg	<25	<25	<25	<25	<25
Benzene	mg/kg	<0.2	<0.2	<0.2	<0.2	<0.2
Toluene	mg/kg	<0.5	<0.5	<0.5	<0.5	<0.5
Ethylbenzene	mg/kg	<1	<1	<1	<1	<1
m+p-xylene	mg/kg	<2	<2	<2	<2	<2
o-Xylene	mg/kg	<1	<1	<1	<1	<1
Naphthalene	mg/kg	<1	<1	<1	<1	<1
Total +ve Xylenes	mg/kg	<1	<1	<1	<1	<1
Surrogate aaa-Trifluorotoluene	%	114	115	116	115	115

vTRH(C6-C10)/BTEXN in Soil						
Our Reference		322581-27	322581-28	322581-30	322581-31	322581-32
Your Reference	UNITS	TP13	TP13	TP14	TP14	TP14
Depth		0-0.1	0.5-0.6	0-0.1	0.4-0.5	0.9-1.0
Date Sampled		4/05/2023	4/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
TRH C <sub>6</sub> - C <sub>9</sub>	mg/kg	<25	<25	<25	<25	<25
TRH C <sub>6</sub> - C <sub>10</sub>	mg/kg	<25	<25	<25	<25	<25
vTPH C <sub>6</sub> - C <sub>10</sub> less BTEX (F1)	mg/kg	<25	<25	<25	<25	<25
Benzene	mg/kg	<0.2	<0.2	<0.2	<0.2	<0.2
Toluene	mg/kg	<0.5	<0.5	<0.5	<0.5	<0.5
Ethylbenzene	mg/kg	<1	<1	<1	<1	<1
m+p-xylene	mg/kg	<2	<2	<2	<2	<2
o-Xylene	mg/kg	<1	<1	<1	<1	<1
Naphthalene	mg/kg	<1	<1	<1	<1	<1
Total +ve Xylenes	mg/kg	<1	<1	<1	<1	<1
Surrogate aaa-Trifluorotoluene	%	106	114	117	113	112

vTRH(C6-C10)/BTEXN in Soil						
Our Reference		322581-33	322581-35	322581-36	322581-37	322581-38
Your Reference	UNITS	TP15	TP15	TP15	TP16	TP16
Depth		0-0.1	0.9-1.0	1.3-1.5	0-0.1	0.4-0.5
Date Sampled		4/05/2023	4/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
TRH C <sub>6</sub> - C <sub>9</sub>	mg/kg	<25	<25	<25	<25	<25
TRH C <sub>6</sub> - C <sub>10</sub>	mg/kg	<25	<25	<25	<25	<25
vTPH C <sub>6</sub> - C <sub>10</sub> less BTEX (F1)	mg/kg	<25	<25	<25	<25	<25
Benzene	mg/kg	<0.2	<0.2	<0.2	<0.2	<0.2
Toluene	mg/kg	<0.5	<0.5	<0.5	<0.5	<0.5
Ethylbenzene	mg/kg	<1	<1	<1	<1	<1
m+p-xylene	mg/kg	<2	<2	<2	<2	<2
o-Xylene	mg/kg	<1	<1	<1	<1	<1
Naphthalene	mg/kg	<1	<1	<1	<1	<1
Total +ve Xylenes	mg/kg	<1	<1	<1	<1	<1
Surrogate aaa-Trifluorotoluene	%	105	112	101	109	112

vTRH(C6-C10)/BTEXN in Soil					
Our Reference		322581-40	322581-41	322581-42	322581-43
Your Reference	UNITS	SDUP1	SDUP2	TB-S1	TS-S1
Depth		-	-	-	-
Date Sampled		4/05/2023	4/05/2023	02/05/2023	02/05/2023
Type of sample		Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023
TRH C <sub>6</sub> - C <sub>9</sub>	mg/kg	<25	<25	<25	[NA]
TRH C <sub>6</sub> - C <sub>10</sub>	mg/kg	<25	<25	<25	[NA]
vTPH C <sub>6</sub> - C <sub>10</sub> less BTEX (F1)	mg/kg	<25	<25	<25	[NA]
Benzene	mg/kg	<0.2	<0.2	<0.2	97%
Toluene	mg/kg	<0.5	<0.5	<0.5	97%
Ethylbenzene	mg/kg	<1	<1	<1	97%
m+p-xylene	mg/kg	<2	<2	<2	97%
o-Xylene	mg/kg	<1	<1	<1	98%
Naphthalene	mg/kg	<1	<1	<1	[NA]
Total +ve Xylenes	mg/kg	<1	<1	<1	[NA]
Surrogate aaa-Trifluorotoluene	%	113	105	118	95

svTRH (C10-C40) in Soil						
Our Reference		322581-1	322581-3	322581-4	322581-5	322581-6
Your Reference	UNITS	BH1	BH1	BH2	BH2	BH2
Depth		0-0.3	0.8-1.0	0-0.2	0.3-0.5	0.8-1.0
Date Sampled		4/05/2023	4/05/2023	3/05/2023	3/05/2023	3/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	12/05/2023	15/05/2023	12/05/2023	12/05/2023	12/05/2023
TRH C <sub>10</sub> - C <sub>14</sub>	mg/kg	<50	<50	<50	<50	<50
TRH C <sub>15</sub> - C <sub>28</sub>	mg/kg	<100	<100	<100	<100	<100
TRH C <sub>29</sub> - C <sub>36</sub>	mg/kg	<100	<100	<100	<100	<100
Total +ve TRH (C10-C36)	mg/kg	<50	<50	<50	<50	<50
TRH >C <sub>10</sub> -C <sub>16</sub>	mg/kg	<50	<50	<50	<50	<50
TRH >C <sub>10</sub> - C <sub>16</sub> less Naphthalene (F2)	mg/kg	<50	<50	<50	<50	<50
TRH >C <sub>16</sub> -C <sub>34</sub>	mg/kg	<100	<100	<100	<100	<100
TRH >C <sub>34</sub> -C <sub>40</sub>	mg/kg	<100	<100	<100	<100	<100
Total +ve TRH (>C10-C40)	mg/kg	<50	<50	<50	<50	<50
Surrogate o-Terphenyl	%	84	76	85	84	83

svTRH (C10-C40) in Soil						
Our Reference		322581-7	322581-8	322581-10	322581-11	322581-12
Your Reference	UNITS	BH3	BH3	BH3	BH4	BH4
Depth		0-0.1	0.3-0.5	1.3-1.5	0-0.1	0.3-0.5
Date Sampled		4/05/2023	4/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	13/05/2023	13/05/2023	12/05/2023	12/05/2023	12/05/2023
TRH C <sub>10</sub> - C <sub>14</sub>	mg/kg	<50	<50	<50	<50	<50
TRH C <sub>15</sub> - C <sub>28</sub>	mg/kg	<100	170	<100	<100	<100
TRH C <sub>29</sub> - C <sub>36</sub>	mg/kg	180	200	<100	<100	<100
Total +ve TRH (C10-C36)	mg/kg	180	370	<50	<50	<50
TRH >C <sub>10</sub> -C <sub>16</sub>	mg/kg	<50	<50	<50	<50	<50
TRH >C <sub>10</sub> - C <sub>16</sub> less Naphthalene (F2)	mg/kg	<50	<50	<50	<50	<50
TRH >C <sub>16</sub> -C <sub>34</sub>	mg/kg	130	320	<100	<100	<100
TRH >C <sub>34</sub> -C <sub>40</sub>	mg/kg	230	120	<100	<100	<100
Total +ve TRH (>C10-C40)	mg/kg	360	440	<50	<50	<50
Surrogate o-Terphenyl	%	78	104	84	85	89

svTRH (C10-C40) in Soil						
Our Reference		322581-13	322581-14	322581-16	322581-17	322581-18
Your Reference	UNITS	BH4	BH5	BH5	BH6	BH6
Depth		0.8-1.0	0-0.1	0.8-1.0	0.02-0.3	0.3-0.5
Date Sampled		4/05/2023	3/05/2023	3/05/2023	02/05/2023	02/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	12/05/2023	12/05/2023	12/05/2023	12/05/2023	12/05/2023
TRH C <sub>10</sub> - C <sub>14</sub>	mg/kg	<50	<50	<50	<50	<50
TRH C <sub>15</sub> - C <sub>28</sub>	mg/kg	<100	<100	<100	<100	<100
TRH C <sub>29</sub> - C <sub>36</sub>	mg/kg	<100	<100	<100	<100	<100
Total +ve TRH (C10-C36)	mg/kg	<50	<50	<50	<50	<50
TRH >C <sub>10</sub> -C <sub>16</sub>	mg/kg	<50	<50	<50	<50	<50
TRH >C <sub>10</sub> - C <sub>16</sub> less Naphthalene (F2)	mg/kg	<50	<50	<50	<50	<50
TRH >C <sub>16</sub> -C <sub>34</sub>	mg/kg	<100	<100	<100	<100	<100
TRH >C <sub>34</sub> -C <sub>40</sub>	mg/kg	<100	<100	<100	<100	<100
Total +ve TRH (>C10-C40)	mg/kg	<50	<50	<50	<50	<50
Surrogate o-Terphenyl	%	85	84	83	85	83

svTRH (C10-C40) in Soil						
Our Reference		322581-19	322581-20	322581-21	322581-23	322581-24
Your Reference	UNITS	BH6	BH7	BH7	BH8	BH8
Depth		0.8-1.0	0-0.1	0.3-0.5	0.02-0.2	0.3-0.5
Date Sampled		02/05/2023	02/05/2023	02/05/2023	05/05/2023	05/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	12/05/2023	12/05/2023	12/05/2023	12/05/2023	12/05/2023
TRH C <sub>10</sub> - C <sub>14</sub>	mg/kg	<50	<50	<50	<50	<50
TRH C <sub>15</sub> - C <sub>28</sub>	mg/kg	<100	<100	<100	<100	<100
TRH C <sub>29</sub> - C <sub>36</sub>	mg/kg	<100	<100	<100	<100	<100
Total +ve TRH (C10-C36)	mg/kg	<50	<50	<50	<50	<50
TRH >C <sub>10</sub> -C <sub>16</sub>	mg/kg	<50	<50	<50	<50	<50
TRH >C <sub>10</sub> - C <sub>16</sub> less Naphthalene (F2)	mg/kg	<50	<50	<50	<50	<50
TRH >C <sub>16</sub> -C <sub>34</sub>	mg/kg	<100	<100	<100	<100	<100
TRH >C <sub>34</sub> -C <sub>40</sub>	mg/kg	<100	<100	<100	<100	<100
Total +ve TRH (>C10-C40)	mg/kg	<50	<50	<50	<50	<50
Surrogate o-Terphenyl	%	84	87	85	87	77



svTRH (C10-C40) in Soil						
Our Reference		322581-27	322581-28	322581-30	322581-31	322581-32
Your Reference	UNITS	TP13	TP13	TP14	TP14	TP14
Depth		0-0.1	0.5-0.6	0-0.1	0.4-0.5	0.9-1.0
Date Sampled		4/05/2023	4/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	12/05/2023	12/05/2023	12/05/2023	12/05/2023	12/05/2023
TRH C <sub>10</sub> - C <sub>14</sub>	mg/kg	<50	<50	<50	<50	<50
TRH C <sub>15</sub> - C <sub>28</sub>	mg/kg	<100	<100	<100	<100	<100
TRH C <sub>29</sub> - C <sub>36</sub>	mg/kg	<100	<100	<100	<100	<100
Total +ve TRH (C10-C36)	mg/kg	<50	<50	<50	<50	<50
TRH >C <sub>10</sub> -C <sub>16</sub>	mg/kg	<50	<50	<50	<50	<50
TRH >C <sub>10</sub> - C <sub>16</sub> less Naphthalene (F2)	mg/kg	<50	<50	<50	<50	<50
TRH >C <sub>16</sub> -C <sub>34</sub>	mg/kg	<100	<100	<100	<100	<100
TRH >C <sub>34</sub> -C <sub>40</sub>	mg/kg	<100	<100	<100	<100	<100
Total +ve TRH (>C10-C40)	mg/kg	<50	<50	<50	<50	<50
Surrogate o-Terphenyl	%	76	78	78	78	70

svTRH (C10-C40) in Soil						
Our Reference		322581-33	322581-35	322581-36	322581-37	322581-38
Your Reference	UNITS	TP15	TP15	TP15	TP16	TP16
Depth		0-0.1	0.9-1.0	1.3-1.5	0-0.1	0.4-0.5
Date Sampled		4/05/2023	4/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	12/05/2023	12/05/2023	12/05/2023	12/05/2023	12/05/2023
TRH C <sub>10</sub> - C <sub>14</sub>	mg/kg	<50	<50	<50	<50	<50
TRH C <sub>15</sub> - C <sub>28</sub>	mg/kg	<100	<100	<100	<100	<100
TRH C <sub>29</sub> - C <sub>36</sub>	mg/kg	<100	<100	<100	<100	<100
Total +ve TRH (C10-C36)	mg/kg	<50	<50	<50	<50	<50
TRH >C <sub>10</sub> -C <sub>16</sub>	mg/kg	<50	<50	<50	<50	<50
TRH >C <sub>10</sub> - C <sub>16</sub> less Naphthalene (F2)	mg/kg	<50	<50	<50	<50	<50
TRH >C <sub>16</sub> -C <sub>34</sub>	mg/kg	<100	<100	<100	<100	<100
TRH >C <sub>34</sub> -C <sub>40</sub>	mg/kg	<100	<100	<100	<100	<100
Total +ve TRH (>C10-C40)	mg/kg	<50	<50	<50	<50	<50
Surrogate o-Terphenyl	%	82	87	83	77	77

svTRH (C10-C40) in Soil				
Our Reference		322581-40	322581-41	322581-42
Your Reference	UNITS	SDUP1	SDUP2	TB-S1
Depth		-	-	-
Date Sampled		4/05/2023	4/05/2023	02/05/2023
Type of sample		Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	12/05/2023
Date analysed	-	13/05/2023	13/05/2023	13/05/2023
TRH C <sub>10</sub> - C <sub>14</sub>	mg/kg	<50	<50	<50
TRH C <sub>15</sub> - C <sub>28</sub>	mg/kg	<100	<100	<100
TRH C <sub>29</sub> - C <sub>36</sub>	mg/kg	<100	<100	<100
Total +ve TRH (C10-C36)	mg/kg	<50	<50	<50
TRH >C <sub>10</sub> -C <sub>16</sub>	mg/kg	<50	<50	<50
TRH >C <sub>10</sub> - C <sub>16</sub> less Naphthalene (F2)	mg/kg	<50	<50	<50
TRH >C <sub>16</sub> -C <sub>34</sub>	mg/kg	<100	<100	<100
TRH >C <sub>34</sub> -C <sub>40</sub>	mg/kg	<100	<100	<100
Total +ve TRH (>C10-C40)	mg/kg	<50	<50	<50
Surrogate o-Terphenyl	%	79	82	81

PAHs in Soil						
Our Reference		322581-1	322581-3	322581-4	322581-5	322581-6
Your Reference	UNITS	BH1	BH1	BH2	BH2	BH2
Depth		0-0.3	0.8-1.0	0-0.2	0.3-0.5	0.8-1.0
Date Sampled		4/05/2023	4/05/2023	3/05/2023	3/05/2023	3/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Naphthalene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Acenaphthylene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Acenaphthene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Fluorene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Phenanthrene	mg/kg	<0.1	<0.1	0.3	<0.1	<0.1
Anthracene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Fluoranthene	mg/kg	0.1	<0.1	1.3	<0.1	<0.1
Pyrene	mg/kg	0.1	<0.1	1.4	<0.1	<0.1
Benzo(a)anthracene	mg/kg	<0.1	<0.1	0.4	<0.1	<0.1
Chrysene	mg/kg	<0.1	<0.1	0.5	<0.1	<0.1
Benzo(b,j+k)fluoranthene	mg/kg	<0.2	<0.2	1	<0.2	<0.2
Benzo(a)pyrene	mg/kg	<0.05	<0.05	0.69	<0.05	<0.05
Indeno(1,2,3-c,d)pyrene	mg/kg	<0.1	<0.1	0.5	<0.1	<0.1
Dibenzo(a,h)anthracene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Benzo(g,h,i)perylene	mg/kg	<0.1	<0.1	0.8	<0.1	<0.1
Total +ve PAH's	mg/kg	0.2	<0.05	6.9	<0.05	<0.05
Benzo(a)pyrene TEQ calc (zero)	mg/kg	<0.5	<0.5	0.9	<0.5	<0.5
Benzo(a)pyrene TEQ calc(half)	mg/kg	<0.5	<0.5	1	<0.5	<0.5
Benzo(a)pyrene TEQ calc(PQL)	mg/kg	<0.5	<0.5	1.0	<0.5	<0.5
Surrogate p-Terphenyl-d14	%	87	101	91	99	89

PAHs in Soil						
Our Reference		322581-7	322581-8	322581-10	322581-11	322581-12
Your Reference	UNITS	BH3	BH3	BH3	BH4	BH4
Depth		0-0.1	0.3-0.5	1.3-1.5	0-0.1	0.3-0.5
Date Sampled		4/05/2023	4/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Naphthalene	mg/kg	<0.1	1.9	<0.1	<0.1	<0.1
Acenaphthylene	mg/kg	<0.1	0.2	<0.1	<0.1	<0.1
Acenaphthene	mg/kg	<0.1	1.5	<0.1	<0.1	<0.1
Fluorene	mg/kg	<0.1	1.9	<0.1	<0.1	<0.1
Phenanthrene	mg/kg	<0.1	14	0.6	<0.1	<0.1
Anthracene	mg/kg	<0.1	3.6	0.2	<0.1	<0.1
Fluoranthene	mg/kg	0.1	16	0.7	0.2	<0.1
Pyrene	mg/kg	0.3	15	0.6	0.2	<0.1
Benzo(a)anthracene	mg/kg	<0.1	5.4	0.2	<0.1	<0.1
Chrysene	mg/kg	0.1	5.2	0.2	<0.1	<0.1
Benzo(b,j+k)fluoranthene	mg/kg	<0.2	7.8	0.3	<0.2	<0.2
Benzo(a)pyrene	mg/kg	0.09	5.4	0.2	0.1	<0.05
Indeno(1,2,3-c,d)pyrene	mg/kg	<0.1	2.7	0.1	<0.1	<0.1
Dibenzo(a,h)anthracene	mg/kg	<0.1	0.6	<0.1	<0.1	<0.1
Benzo(g,h,i)perylene	mg/kg	<0.1	3.7	0.2	0.1	<0.1
Total +ve PAH's	mg/kg	0.64	85	3.3	0.66	<0.05
Benzo(a)pyrene TEQ calc (zero)	mg/kg	<0.5	7.7	<0.5	<0.5	<0.5
Benzo(a)pyrene TEQ calc(half)	mg/kg	<0.5	7.7	<0.5	<0.5	<0.5
Benzo(a)pyrene TEQ calc(PQL)	mg/kg	<0.5	7.7	<0.5	<0.5	<0.5
Surrogate p-Terphenyl-d14	%	98	92	98	100	100

PAHs in Soil						
Our Reference		322581-13	322581-14	322581-16	322581-17	322581-18
Your Reference	UNITS	BH4	BH5	BH5	BH6	BH6
Depth		0.8-1.0	0-0.1	0.8-1.0	0.02-0.3	0.3-0.5
Date Sampled		4/05/2023	3/05/2023	3/05/2023	02/05/2023	02/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Naphthalene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Acenaphthylene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Acenaphthene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Fluorene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Phenanthrene	mg/kg	<0.1	0.2	<0.1	<0.1	<0.1
Anthracene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Fluoranthene	mg/kg	<0.1	0.6	<0.1	<0.1	<0.1
Pyrene	mg/kg	<0.1	0.6	<0.1	<0.1	<0.1
Benzo(a)anthracene	mg/kg	<0.1	0.2	<0.1	<0.1	<0.1
Chrysene	mg/kg	<0.1	0.2	<0.1	<0.1	<0.1
Benzo(b,j+k)fluoranthene	mg/kg	<0.2	0.4	<0.2	<0.2	<0.2
Benzo(a)pyrene	mg/kg	<0.05	0.3	<0.05	<0.05	<0.05
Indeno(1,2,3-c,d)pyrene	mg/kg	<0.1	0.2	<0.1	<0.1	<0.1
Dibenzo(a,h)anthracene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Benzo(g,h,i)perylene	mg/kg	<0.1	0.3	<0.1	<0.1	<0.1
Total +ve PAH's	mg/kg	<0.05	2.9	<0.05	<0.05	<0.05
Benzo(a)pyrene TEQ calc (zero)	mg/kg	<0.5	<0.5	<0.5	<0.5	<0.5
Benzo(a)pyrene TEQ calc(half)	mg/kg	<0.5	<0.5	<0.5	<0.5	<0.5
Benzo(a)pyrene TEQ calc(PQL)	mg/kg	<0.5	<0.5	<0.5	<0.5	<0.5
Surrogate <i>p</i> -Terphenyl-d14	%	83	90	96	96	79

PAHs in Soil						
Our Reference		322581-19	322581-20	322581-21	322581-23	322581-24
Your Reference	UNITS	BH6	BH7	BH7	BH8	BH8
Depth		0.8-1.0	0-0.1	0.3-0.5	0.02-0.2	0.3-0.5
Date Sampled		02/05/2023	02/05/2023	02/05/2023	05/05/2023	05/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Naphthalene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Acenaphthylene	mg/kg	<0.1	<0.1	<0.1	0.2	<0.1
Acenaphthene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Fluorene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Phenanthrene	mg/kg	<0.1	<0.1	<0.1	1.1	0.3
Anthracene	mg/kg	<0.1	<0.1	<0.1	0.3	<0.1
Fluoranthene	mg/kg	<0.1	<0.1	<0.1	4.6	0.8
Pyrene	mg/kg	<0.1	<0.1	<0.1	5.4	0.7
Benzo(a)anthracene	mg/kg	<0.1	<0.1	<0.1	2.2	0.2
Chrysene	mg/kg	<0.1	<0.1	<0.1	2.0	0.3
Benzo(b,j+k)fluoranthene	mg/kg	<0.2	<0.2	<0.2	3.9	0.4
Benzo(a)pyrene	mg/kg	<0.05	<0.05	<0.05	2.6	0.3
Indeno(1,2,3-c,d)pyrene	mg/kg	<0.1	<0.1	<0.1	1.7	0.2
Dibenzo(a,h)anthracene	mg/kg	<0.1	<0.1	<0.1	0.3	<0.1
Benzo(g,h,i)perylene	mg/kg	<0.1	<0.1	<0.1	2.5	0.3
Total +ve PAH's	mg/kg	<0.05	<0.05	<0.05	27	3.3
Benzo(a)pyrene TEQ calc (zero)	mg/kg	<0.5	<0.5	<0.5	3.6	<0.5
Benzo(a)pyrene TEQ calc(half)	mg/kg	<0.5	<0.5	<0.5	3.6	<0.5
Benzo(a)pyrene TEQ calc(PQL)	mg/kg	<0.5	<0.5	<0.5	3.6	<0.5
Surrogate p-Terphenyl-d14	%	92	86	100	93	98

PAHs in Soil						
Our Reference		322581-27	322581-28	322581-30	322581-31	322581-32
Your Reference	UNITS	TP13	TP13	TP14	TP14	TP14
Depth		0-0.1	0.5-0.6	0-0.1	0.4-0.5	0.9-1.0
Date Sampled		4/05/2023	4/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Naphthalene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Acenaphthylene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Acenaphthene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Fluorene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Phenanthrene	mg/kg	<0.1	<0.1	0.1	0.1	<0.1
Anthracene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Fluoranthene	mg/kg	<0.1	<0.1	0.3	0.2	<0.1
Pyrene	mg/kg	0.1	<0.1	0.3	0.1	<0.1
Benzo(a)anthracene	mg/kg	<0.1	<0.1	0.1	<0.1	<0.1
Chrysene	mg/kg	<0.1	<0.1	0.1	<0.1	<0.1
Benzo(b,j+k)fluoranthene	mg/kg	<0.2	<0.2	<0.2	<0.2	<0.2
Benzo(a)pyrene	mg/kg	0.05	<0.05	0.1	0.06	<0.05
Indeno(1,2,3-c,d)pyrene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Dibenzo(a,h)anthracene	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Benzo(g,h,i)perylene	mg/kg	<0.1	<0.1	0.1	<0.1	<0.1
Total +ve PAH's	mg/kg	0.2	<0.05	1.1	0.5	<0.05
Benzo(a)pyrene TEQ calc (zero)	mg/kg	<0.5	<0.5	<0.5	<0.5	<0.5
Benzo(a)pyrene TEQ calc(half)	mg/kg	<0.5	<0.5	<0.5	<0.5	<0.5
Benzo(a)pyrene TEQ calc(PQL)	mg/kg	<0.5	<0.5	<0.5	<0.5	<0.5
Surrogate p-Terphenyl-d14	%	96	94	99	93	88

PAHs in Soil						
Our Reference		322581-33	322581-35	322581-36	322581-37	322581-38
Your Reference	UNITS	TP15	TP15	TP15	TP16	TP16
Depth		0-0.1	0.9-1.0	1.3-1.5	0-0.1	0.4-0.5
Date Sampled		4/05/2023	4/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Naphthalene	mg/kg	<0.1	0.2	<0.1	<0.1	<0.1
Acenaphthylene	mg/kg	<0.1	0.1	<0.1	<0.1	<0.1
Acenaphthene	mg/kg	<0.1	0.3	<0.1	<0.1	<0.1
Fluorene	mg/kg	<0.1	0.2	<0.1	<0.1	<0.1
Phenanthrene	mg/kg	<0.1	4.9	<0.1	<0.1	<0.1
Anthracene	mg/kg	<0.1	1.1	<0.1	<0.1	<0.1
Fluoranthene	mg/kg	0.1	8.7	<0.1	0.3	<0.1
Pyrene	mg/kg	0.1	7.2	<0.1	0.3	<0.1
Benzo(a)anthracene	mg/kg	<0.1	3.7	<0.1	<0.1	<0.1
Chrysene	mg/kg	<0.1	3.0	<0.1	0.1	<0.1
Benzo(b,j+k)fluoranthene	mg/kg	<0.2	5.3	<0.2	0.2	<0.2
Benzo(a)pyrene	mg/kg	0.05	3.4	<0.05	0.1	<0.05
Indeno(1,2,3-c,d)pyrene	mg/kg	<0.1	1.8	<0.1	0.1	<0.1
Dibenzo(a,h)anthracene	mg/kg	<0.1	0.4	<0.1	<0.1	<0.1
Benzo(g,h,i)perylene	mg/kg	<0.1	2.4	<0.1	0.1	<0.1
Total +ve PAH's	mg/kg	0.3	43	<0.05	1.4	<0.05
Benzo(a)pyrene TEQ calc (zero)	mg/kg	<0.5	4.9	<0.5	<0.5	<0.5
Benzo(a)pyrene TEQ calc(half)	mg/kg	<0.5	4.9	<0.5	<0.5	<0.5
Benzo(a)pyrene TEQ calc(PQL)	mg/kg	<0.5	4.9	<0.5	<0.5	<0.5
Surrogate p-Terphenyl-d14	%	102	92	98	96	97



PAHs in Soil				
Our Reference		322581-40	322581-41	322581-42
Your Reference	UNITS	SDUP1	SDUP2	TB-S1
Depth		-	-	-
Date Sampled		4/05/2023	4/05/2023	02/05/2023
Type of sample		Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	12/05/2023
Naphthalene	mg/kg	<0.1	<0.1	<0.1
Acenaphthylene	mg/kg	<0.1	<0.1	<0.1
Acenaphthene	mg/kg	<0.1	<0.1	<0.1
Fluorene	mg/kg	<0.1	<0.1	<0.1
Phenanthrene	mg/kg	<0.1	<0.1	<0.1
Anthracene	mg/kg	<0.1	<0.1	<0.1
Fluoranthene	mg/kg	0.4	0.1	<0.1
Pyrene	mg/kg	0.4	<0.1	<0.1
Benzo(a)anthracene	mg/kg	0.1	<0.1	<0.1
Chrysene	mg/kg	0.1	<0.1	<0.1
Benzo(b,j+k)fluoranthene	mg/kg	0.3	<0.2	<0.2
Benzo(a)pyrene	mg/kg	0.2	<0.05	<0.05
Indeno(1,2,3-c,d)pyrene	mg/kg	0.1	<0.1	<0.1
Dibenzo(a,h)anthracene	mg/kg	<0.1	<0.1	<0.1
Benzo(g,h,i)perylene	mg/kg	0.2	<0.1	<0.1
Total +ve PAH's	mg/kg	1.7	0.1	<0.05
Benzo(a)pyrene TEQ calc (zero)	mg/kg	<0.5	<0.5	<0.5
Benzo(a)pyrene TEQ calc(half)	mg/kg	<0.5	<0.5	<0.5
Benzo(a)pyrene TEQ calc(PQL)	mg/kg	<0.5	<0.5	<0.5
Surrogate <i>p</i> -Terphenyl-d14	%	90	107	102

Organochlorine Pesticides in soil						
Our Reference		322581-1	322581-4	322581-7	322581-8	322581-11
Your Reference	UNITS	BH1	BH2	BH3	BH3	BH4
Depth		0-0.3	0-0.2	0-0.1	0.3-0.5	0-0.1
Date Sampled		4/05/2023	3/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
alpha-BHC	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
HCB	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
beta-BHC	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
gamma-BHC	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Heptachlor	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
delta-BHC	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aldrin	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Heptachlor Epoxide	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
gamma-Chlordane	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
alpha-chlordane	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Endosulfan I	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
pp-DDE	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Dieldrin	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Endrin	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Endosulfan II	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
pp-DDD	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Endrin Aldehyde	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
pp-DDT	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Endosulfan Sulphate	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Methoxychlor	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Total +ve DDT+DDD+DDE	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Surrogate TCMX	%	100	112	101	100	104

Organochlorine Pesticides in soil						
Our Reference		322581-14	322581-17	322581-20	322581-23	322581-27
Your Reference	UNITS	BH5	BH6	BH7	BH8	TP13
Depth		0-0.1	0.02-0.3	0-0.1	0.02-0.2	0-0.1
Date Sampled		3/05/2023	02/05/2023	02/05/2023	05/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
alpha-BHC	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
HCB	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
beta-BHC	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
gamma-BHC	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Heptachlor	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
delta-BHC	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aldrin	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Heptachlor Epoxide	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
gamma-Chlordane	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
alpha-chlordane	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Endosulfan I	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
pp-DDE	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Dieldrin	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Endrin	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Endosulfan II	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
pp-DDD	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Endrin Aldehyde	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
pp-DDT	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Endosulfan Sulphate	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Methoxychlor	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Total +ve DDT+DDD+DDE	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Surrogate TCMX	%	109	103	101	103	104

Organochlorine Pesticides in soil						
Our Reference		322581-30	322581-33	322581-35	322581-37	322581-40
Your Reference	UNITS	TP14	TP15	TP15	TP16	SDUP1
Depth		0-0.1	0-0.1	0.9-1.0	0-0.1	-
Date Sampled		4/05/2023	4/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
alpha-BHC	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
HCB	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
beta-BHC	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
gamma-BHC	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Heptachlor	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
delta-BHC	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aldrin	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Heptachlor Epoxide	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
gamma-Chlordane	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
alpha-chlordane	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Endosulfan I	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
pp-DDE	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Dieldrin	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Endrin	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Endosulfan II	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
pp-DDD	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Endrin Aldehyde	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
pp-DDT	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Endosulfan Sulphate	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Methoxychlor	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Total +ve DDT+DDD+DDE	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Surrogate TCMX	%	101	103	101	97	104

Organophosphorus Pesticides						
Our Reference		322581-1	322581-4	322581-7	322581-8	322581-11
Your Reference	UNITS	BH1	BH2	BH3	BH3	BH4
Depth		0-0.3	0-0.2	0-0.1	0.3-0.5	0-0.1
Date Sampled		4/05/2023	3/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Azinphos-methyl (Guthion)	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Bromophos-ethyl	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Chlorpyrifos	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Chlorpyrifos-methyl	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Diazinon	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Dichlorvos	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Dimethoate	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Ethion	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Fenitrothion	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Malathion	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Parathion	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Ronnel	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Coumaphos	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Disulfoton	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Fenamiphos	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Fenthion	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Methidathion	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Mevinphos	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Parathion (Methyl)	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Phorate	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Phosalone	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Surrogate TCMX	%	100	112	101	100	104

Organophosphorus Pesticides						
Our Reference		322581-14	322581-17	322581-20	322581-23	322581-27
Your Reference	UNITS	BH5	BH6	BH7	BH8	TP13
Depth		0-0.1	0.02-0.3	0-0.1	0.02-0.2	0-0.1
Date Sampled		3/05/2023	02/05/2023	02/05/2023	05/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Azinphos-methyl (Guthion)	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Bromophos-ethyl	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Chlorpyrifos	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Chlorpyrifos-methyl	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Diazinon	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Dichlorvos	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Dimethoate	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Ethion	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Fenitrothion	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Malathion	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Parathion	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Ronnel	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Coumaphos	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Disulfoton	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Fenamiphos	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Fenthion	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Methidathion	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Mevinphos	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Parathion (Methyl)	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Phorate	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Phosalone	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Surrogate TCMX	%	109	103	101	103	104

Organophosphorus Pesticides						
Our Reference		322581-30	322581-33	322581-35	322581-37	322581-40
Your Reference	UNITS	TP14	TP15	TP15	TP16	SDUP1
Depth		0-0.1	0-0.1	0.9-1.0	0-0.1	-
Date Sampled		4/05/2023	4/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Azinphos-methyl (Guthion)	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Bromophos-ethyl	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Chlorpyrifos	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Chlorpyrifos-methyl	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Diazinon	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Dichlorvos	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Dimethoate	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Ethion	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Fenitrothion	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Malathion	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Parathion	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Ronnel	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Coumaphos	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Disulfoton	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Fenamiphos	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Fenthion	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Methidathion	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Mevinphos	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Parathion (Methyl)	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Phorate	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Phosalone	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Surrogate TCMX	%	101	103	101	97	104

PCBs in Soil						
Our Reference		322581-1	322581-4	322581-7	322581-8	322581-11
Your Reference	UNITS	BH1	BH2	BH3	BH3	BH4
Depth		0-0.3	0-0.2	0-0.1	0.3-0.5	0-0.1
Date Sampled		4/05/2023	3/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Aroclor 1016	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aroclor 1221	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aroclor 1232	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aroclor 1242	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aroclor 1248	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aroclor 1254	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aroclor 1260	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Total +ve PCBs (1016-1260)	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Surrogate TCMX	%	100	112	101	100	104

PCBs in Soil						
Our Reference		322581-14	322581-17	322581-20	322581-23	322581-27
Your Reference	UNITS	BH5	BH6	BH7	BH8	TP13
Depth		0-0.1	0.02-0.3	0-0.1	0.02-0.2	0-0.1
Date Sampled		3/05/2023	02/05/2023	02/05/2023	05/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Aroclor 1016	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aroclor 1221	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aroclor 1232	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aroclor 1242	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aroclor 1248	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aroclor 1254	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aroclor 1260	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Total +ve PCBs (1016-1260)	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Surrogate TCMX	%	109	103	101	103	104



PCBs in Soil						
Our Reference		322581-30	322581-33	322581-35	322581-37	322581-40
Your Reference	UNITS	TP14	TP15	TP15	TP16	SDUP1
Depth		0-0.1	0-0.1	0.9-1.0	0-0.1	-
Date Sampled		4/05/2023	4/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date extracted	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Aroclor 1016	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aroclor 1221	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aroclor 1232	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aroclor 1242	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aroclor 1248	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aroclor 1254	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Aroclor 1260	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Total +ve PCBs (1016-1260)	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Surrogate TCMX	%	101	103	101	97	104

Acid Extractable metals in soil						
Our Reference		322581-1	322581-3	322581-4	322581-5	322581-6
Your Reference	UNITS	BH1	BH1	BH2	BH2	BH2
Depth		0-0.3	0.8-1.0	0-0.2	0.3-0.5	0.8-1.0
Date Sampled		4/05/2023	4/05/2023	3/05/2023	3/05/2023	3/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date prepared	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Date analysed	-	12/05/2023	12/05/2023	12/05/2023	12/05/2023	12/05/2023
Arsenic	mg/kg	<4	<4	6	6	6
Cadmium	mg/kg	<0.4	<0.4	<0.4	<0.4	<0.4
Chromium	mg/kg	37	62	38	91	63
Copper	mg/kg	70	130	200	280	200
Lead	mg/kg	7	9	8	5	6
Mercury	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Nickel	mg/kg	10	14	11	18	13
Zinc	mg/kg	22	31	36	37	30

Acid Extractable metals in soil						
Our Reference		322581-7	322581-8	322581-10	322581-11	322581-12
Your Reference	UNITS	BH3	BH3	BH3	BH4	BH4
Depth		0-0.1	0.3-0.5	1.3-1.5	0-0.1	0.3-0.5
Date Sampled		4/05/2023	4/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date prepared	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Date analysed	-	12/05/2023	12/05/2023	12/05/2023	12/05/2023	12/05/2023
Arsenic	mg/kg	7	8	4	5	7
Cadmium	mg/kg	<0.4	<0.4	<0.4	<0.4	<0.4
Chromium	mg/kg	23	47	72	30	18
Copper	mg/kg	57	86	120	82	300
Lead	mg/kg	12	15	9	28	3
Mercury	mg/kg	<0.1	0.2	<0.1	<0.1	<0.1
Nickel	mg/kg	9	11	12	7	11
Zinc	mg/kg	24	33	22	53	31

Acid Extractable metals in soil						
Our Reference		322581-13	322581-14	322581-16	322581-17	322581-18
Your Reference	UNITS	BH4	BH5	BH5	BH6	BH6
Depth		0.8-1.0	0-0.1	0.8-1.0	0.02-0.3	0.3-0.5
Date Sampled		4/05/2023	3/05/2023	3/05/2023	02/05/2023	02/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date prepared	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Date analysed	-	12/05/2023	12/05/2023	12/05/2023	12/05/2023	12/05/2023
Arsenic	mg/kg	6	9	4	<4	<4
Cadmium	mg/kg	<0.4	<0.4	<0.4	<0.4	<0.4
Chromium	mg/kg	16	26	52	22	19
Copper	mg/kg	210	230	180	220	440
Lead	mg/kg	2	13	7	17	3
Mercury	mg/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Nickel	mg/kg	9	9	12	9	10
Zinc	mg/kg	24	30	20	54	51

Acid Extractable metals in soil						
Our Reference		322581-19	322581-20	322581-21	322581-23	322581-24
Your Reference	UNITS	BH6	BH7	BH7	BH8	BH8
Depth		0.8-1.0	0-0.1	0.3-0.5	0.02-0.2	0.3-0.5
Date Sampled		02/05/2023	02/05/2023	02/05/2023	05/05/2023	05/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date prepared	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Date analysed	-	12/05/2023	12/05/2023	12/05/2023	12/05/2023	12/05/2023
Arsenic	mg/kg	<4	7	7	<4	<4
Cadmium	mg/kg	<0.4	<0.4	<0.4	<0.4	<0.4
Chromium	mg/kg	16	36	66	13	53
Copper	mg/kg	400	94	120	12	170
Lead	mg/kg	1	24	10	7	7
Mercury	mg/kg	<0.1	<0.1	0.6	<0.1	<0.1
Nickel	mg/kg	9	9	13	2	15
Zinc	mg/kg	55	36	29	7	42

Acid Extractable metals in soil						
Our Reference		322581-27	322581-28	322581-30	322581-31	322581-32
Your Reference	UNITS	TP13	TP13	TP14	TP14	TP14
Depth		0-0.1	0.5-0.6	0-0.1	0.4-0.5	0.9-1.0
Date Sampled		4/05/2023	4/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date prepared	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Date analysed	-	12/05/2023	12/05/2023	12/05/2023	12/05/2023	12/05/2023
Arsenic	mg/kg	5	7	15	<4	<4
Cadmium	mg/kg	<0.4	<0.4	<0.4	<0.4	<0.4
Chromium	mg/kg	20	24	31	17	10
Copper	mg/kg	210	490	99	420	470
Lead	mg/kg	22	4	120	6	2
Mercury	mg/kg	0.1	<0.1	0.1	<0.1	<0.1
Nickel	mg/kg	8	11	3	10	10
Zinc	mg/kg	59	28	88	57	47

Acid Extractable metals in soil						
Our Reference		322581-33	322581-35	322581-36	322581-37	322581-38
Your Reference	UNITS	TP15	TP15	TP15	TP16	TP16
Depth		0-0.1	0.9-1.0	1.3-1.5	0-0.1	0.4-0.5
Date Sampled		4/05/2023	4/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date prepared	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Date analysed	-	12/05/2023	12/05/2023	12/05/2023	12/05/2023	12/05/2023
Arsenic	mg/kg	6	7	<4	10	5
Cadmium	mg/kg	<0.4	<0.4	<0.4	<0.4	<0.4
Chromium	mg/kg	21	24	52	56	74
Copper	mg/kg	34	32	110	190	180
Lead	mg/kg	12	14	7	25	4
Mercury	mg/kg	<0.1	<0.1	0.7	<0.1	<0.1
Nickel	mg/kg	7	5	9	14	15
Zinc	mg/kg	30	11	18	61	27

Acid Extractable metals in soil				
Our Reference		322581-40	322581-41	322581-42
Your Reference	UNITS	SDUP1	SDUP2	TB-S1
Depth		-	-	-
Date Sampled		4/05/2023	4/05/2023	02/05/2023
Type of sample		Soil	Soil	Soil
Date prepared	-	11/05/2023	11/05/2023	11/05/2023
Date analysed	-	12/05/2023	12/05/2023	12/05/2023
Arsenic	mg/kg	10	6	<4
Cadmium	mg/kg	<0.4	<0.4	<0.4
Chromium	mg/kg	55	20	7
Copper	mg/kg	190	31	1
Lead	mg/kg	25	12	3
Mercury	mg/kg	<0.1	<0.1	<0.1
Nickel	mg/kg	14	7	5
Zinc	mg/kg	66	29	12

Moisture						
Our Reference		322581-1	322581-3	322581-4	322581-5	322581-6
Your Reference	UNITS	BH1	BH1	BH2	BH2	BH2
Depth		0-0.3	0.8-1.0	0-0.2	0.3-0.5	0.8-1.0
Date Sampled		4/05/2023	4/05/2023	3/05/2023	3/05/2023	3/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date prepared	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Moisture	%	13	11	9.8	15	12

Moisture						
Our Reference		322581-7	322581-8	322581-10	322581-11	322581-12
Your Reference	UNITS	BH3	BH3	BH3	BH4	BH4
Depth		0-0.1	0.3-0.5	1.3-1.5	0-0.1	0.3-0.5
Date Sampled		4/05/2023	4/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date prepared	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Moisture	%	15	12	13	16	13

Moisture						
Our Reference		322581-13	322581-14	322581-16	322581-17	322581-18
Your Reference	UNITS	BH4	BH5	BH5	BH6	BH6
Depth		0.8-1.0	0-0.1	0.8-1.0	0.02-0.3	0.3-0.5
Date Sampled		4/05/2023	3/05/2023	3/05/2023	02/05/2023	02/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date prepared	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Moisture	%	6.6	16	17	18	14

Moisture						
Our Reference		322581-19	322581-20	322581-21	322581-23	322581-24
Your Reference	UNITS	BH6	BH7	BH7	BH8	BH8
Depth		0.8-1.0	0-0.1	0.3-0.5	0.02-0.2	0.3-0.5
Date Sampled		02/05/2023	02/05/2023	02/05/2023	05/05/2023	05/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date prepared	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Moisture	%	5.6	3.5	5.9	2.5	5.5

Moisture						
Our Reference		322581-27	322581-28	322581-30	322581-31	322581-32
Your Reference	UNITS	TP13	TP13	TP14	TP14	TP14
Depth		0-0.1	0.5-0.6	0-0.1	0.4-0.5	0.9-1.0
Date Sampled		4/05/2023	4/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date prepared	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Moisture	%	26	19	11	12	8.3

Moisture						
Our Reference		322581-33	322581-35	322581-36	322581-37	322581-38
Your Reference	UNITS	TP15	TP15	TP15	TP16	TP16
Depth		0-0.1	0.9-1.0	1.3-1.5	0-0.1	0.4-0.5
Date Sampled		4/05/2023	4/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date prepared	-	10/05/2023	10/05/2023	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023	11/05/2023	11/05/2023
Moisture	%	29	9.6	2.5	18	14

Moisture				
Our Reference		322581-40	322581-41	322581-42
Your Reference	UNITS	SDUP1	SDUP2	TB-S1
Depth		-	-	-
Date Sampled		4/05/2023	4/05/2023	02/05/2023
Type of sample		Soil	Soil	Soil
Date prepared	-	10/05/2023	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023	11/05/2023
Moisture	%	19	29	0.1

Asbestos ID - soils NEPM - ASB-001						
Our Reference		322581-1	322581-4	322581-7	322581-8	322581-11
Your Reference	UNITS	BH1	BH2	BH3	BH3	BH4
Depth		0-0.3	0-0.2	0-0.1	0.3-0.5	0-0.1
Date Sampled		4/05/2023	3/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date analysed	-	15/05/2023	15/05/2023	15/05/2023	15/05/2023	15/05/2023
Sample mass tested	g	577.15	862.12	754.89	390.48	574.85
Sample Description	-	Brown fine-grained soil & rocks	Brown coarse-grained soil & rocks	Brown fine-grained soil & rocks	Brown fine-grained soil & rocks	Brown fine-grained soil & rocks
Asbestos ID in soil (AS4964) >0.1g/kg	-	No asbestos detected at reporting limit of 0.1g/kg Organic fibres detected	No asbestos detected at reporting limit of 0.1g/kg Organic fibres detected	No asbestos detected at reporting limit of 0.1g/kg Organic fibres detected	No asbestos detected at reporting limit of 0.1g/kg Organic fibres detected	No asbestos detected at reporting limit of 0.1g/kg Organic fibres detected
Trace Analysis	-	No asbestos detected	No asbestos detected	No asbestos detected	No asbestos detected	No asbestos detected
Total Asbestos <sup>#1</sup>	g/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Asbestos ID in soil <0.1g/kg*	-	No visible asbestos detected	No visible asbestos detected	No visible asbestos detected	No visible asbestos detected	No visible asbestos detected
ACM >7mm Estimation*	g	-	-	-	-	-
FA and AF Estimation*	g	-	-	-	-	-
ACM >7mm Estimation*	%(w/w)	<0.01	<0.01	<0.01	<0.01	<0.01
FA and AF Estimation*#2	%(w/w)	<0.001	<0.001	<0.001	<0.001	<0.001



Asbestos ID - soils NEPM - ASB-001						
Our Reference		322581-14	322581-17	322581-20	322581-23	322581-27
Your Reference	UNITS	BH5	BH6	BH7	BH8	TP13
Depth		0-0.1	0.02-0.3	0-0.1	0.02-0.2	0-0.1
Date Sampled		3/05/2023	02/05/2023	02/05/2023	05/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil	Soil
Date analysed	-	15/05/2023	15/05/2023	15/05/2023	15/05/2023	15/05/2023
Sample mass tested	g	667.13	599.31	1,198.85	891.69	558.56
Sample Description	-	Brown fine-grained soil & rocks	Brown fine-grained soil & rocks	Beige coarse-grained soil & rocks	Brown fine-grained soil & rocks	Brown coarse-grained soil & rocks
Asbestos ID in soil (AS4964) >0.1g/kg	-	No asbestos detected at reporting limit of 0.1g/kg	No asbestos detected at reporting limit of 0.1g/kg	No asbestos detected at reporting limit of 0.1g/kg	No asbestos detected at reporting limit of 0.1g/kg	No asbestos detected at reporting limit of 0.1g/kg
		Organic fibres detected	Organic fibres detected	Organic fibres detected	Organic fibres detected	Organic fibres detected
Trace Analysis	-	No asbestos detected	No asbestos detected	No asbestos detected	No asbestos detected	No asbestos detected
Total Asbestos#1	g/kg	<0.1	<0.1	<0.1	<0.1	<0.1
Asbestos ID in soil <0.1g/kg*	-	No visible asbestos detected	No visible asbestos detected	No visible asbestos detected	No visible asbestos detected	No visible asbestos detected
ACM >7mm Estimation*	g	-	-	-	-	-
FA and AF Estimation*	g	-	-	-	-	-
ACM >7mm Estimation*	%(w/w)	<0.01	<0.01	<0.01	<0.01	<0.01
FA and AF Estimation*#2	%(w/w)	<0.001	<0.001	<0.001	<0.001	<0.001

Asbestos ID - soils NEPM - ASB-001					
Our Reference		322581-30	322581-33	322581-35	322581-37
Your Reference	UNITS	TP14	TP15	TP15	TP16
Depth		0-0.1	0-0.1	0.9-1.0	0-0.1
Date Sampled		4/05/2023	4/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil
Date analysed	-	15/05/2023	15/05/2023	15/05/2023	15/05/2023
Sample mass tested	g	820.02	482.11	920.77	601.76
Sample Description	-	Brown coarse-grained soil & rocks	Brown coarse-grained soil & rocks	Brown fine-grained soil & rocks	Brown fine-grained soil & rocks
Asbestos ID in soil (AS4964) >0.1g/kg	-	No asbestos detected at reporting limit of 0.1g/kg Organic fibres detected	No asbestos detected at reporting limit of 0.1g/kg Organic fibres detected	No asbestos detected at reporting limit of 0.1g/kg Organic fibres detected	No asbestos detected at reporting limit of 0.1g/kg Organic fibres detected
Trace Analysis	-	No asbestos detected	No asbestos detected	No asbestos detected	No asbestos detected
Total Asbestos <sup>#1</sup>	g/kg	<0.1	<0.1	<0.1	<0.1
Asbestos ID in soil <0.1g/kg*	-	No visible asbestos detected	No visible asbestos detected	No visible asbestos detected	No visible asbestos detected
ACM >7mm Estimation*	g	-	-	-	-
FA and AF Estimation*	g	-	-	-	-
ACM >7mm Estimation*	%(w/w)	<0.01	<0.01	<0.01	<0.01
FA and AF Estimation*#2	%(w/w)	<0.001	<0.001	<0.001	<0.001

Asbestos ID - materials			
Our Reference		322581-45	322581-46
Your Reference	UNITS	BH4-FCF1	BH4-FCF2
Depth		-	-
Date Sampled		4/05/2023	4/05/2023
Type of sample		Material	Material
Date analysed	-	11/05/2023	11/05/2023
Mass / Dimension of Sample	-	110x82x5mm	30x20x5mm
Sample Description	-	Grey fibre cement material	Grey fibre cement material
Asbestos ID in materials	-	Chrysotile asbestos detected Amosite asbestos detected Crocidolite asbestos detected	Chrysotile asbestos detected
Trace Analysis	-	[NT]	[NT]

vTRH(C6-C10)/BTEXN in Water		
Our Reference		322581-44
Your Reference	UNITS	FR-SPT
Depth		-
Date Sampled		03/05/2023
Type of sample		Water
Date extracted	-	09/05/2023
Date analysed	-	10/05/2023
TRH C <sub>6</sub> - C <sub>9</sub>	µg/L	23
TRH C <sub>6</sub> - C <sub>10</sub>	µg/L	26
TRH C <sub>6</sub> - C <sub>10</sub> less BTEX (F1)	µg/L	26
Benzene	µg/L	<1
Toluene	µg/L	<1
Ethylbenzene	µg/L	<1
m+p-xylene	µg/L	<2
o-xylene	µg/L	<1
Naphthalene	µg/L	<1
Surrogate Dibromofluoromethane	%	99
Surrogate toluene-d8	%	99
Surrogate 4-BFB	%	107

svTRH (C10-C40) in Water		
Our Reference		322581-44
Your Reference	UNITS	FR-SPT
Depth		-
Date Sampled		03/05/2023
Type of sample		Water
Date extracted	-	12/05/2023
Date analysed	-	12/05/2023
TRH C <sub>10</sub> - C <sub>14</sub>	µg/L	<50
TRH C <sub>15</sub> - C <sub>28</sub>	µg/L	<100
TRH C <sub>29</sub> - C <sub>36</sub>	µg/L	<100
Total +ve TRH (C10-C36)	µg/L	<50
TRH >C <sub>10</sub> - C <sub>16</sub>	µg/L	<50
TRH >C <sub>10</sub> - C <sub>16</sub> less Naphthalene (F2)	µg/L	<50
TRH >C <sub>16</sub> - C <sub>34</sub>	µg/L	<100
TRH >C <sub>34</sub> - C <sub>40</sub>	µg/L	<100
Total +ve TRH (>C10-C40)	µg/L	<50
Surrogate o-Terphenyl	%	95

PAHs in Water		
Our Reference		322581-44
Your Reference	UNITS	FR-SPT
Depth		-
Date Sampled		03/05/2023
Type of sample		Water
Date extracted	-	12/05/2023
Date analysed	-	12/05/2023
Naphthalene	µg/L	<2
Acenaphthylene	µg/L	<1
Acenaphthene	µg/L	<1
Fluorene	µg/L	<1
Phenanthrene	µg/L	<1
Anthracene	µg/L	<1
Fluoranthene	µg/L	<1
Pyrene	µg/L	<1
Benzo(a)anthracene	µg/L	<1
Chrysene	µg/L	<1
Benzo(b,j+k)fluoranthene	µg/L	<2
Benzo(a)pyrene	µg/L	<1
Indeno(1,2,3-c,d)pyrene	µg/L	<1
Dibenzo(a,h)anthracene	µg/L	<1
Benzo(g,h,i)perylene	µg/L	<1
Benzo(a)pyrene TEQ	µg/L	<5
Total +ve PAH's	µg/L	NIL (+)VE
Surrogate <i>p</i> -Terphenyl-d14	%	82

Metals in Waters - Acid extractable		
Our Reference		322581-44
Your Reference	UNITS	FR-SPT
Depth		-
Date Sampled		03/05/2023
Type of sample		Water
Date prepared	-	11/05/2023
Date analysed	-	12/05/2023
Arsenic - Total	mg/L	<0.05
Cadmium - Total	mg/L	<0.01
Chromium - Total	mg/L	<0.01
Copper - Total	mg/L	0.3
Lead - Total	mg/L	<0.03
Mercury - Total	mg/L	<0.0005
Nickel - Total	mg/L	<0.02
Zinc - Total	mg/L	0.2

Method ID	Methodology Summary
<b>ASB-001</b>	Asbestos ID - Qualitative identification of asbestos in bulk samples using Polarised Light Microscopy and Dispersion Staining Techniques including Synthetic Mineral Fibre and Organic Fibre as per Australian Standard 4964-2004.
<b>ASB-001</b>	<p>Asbestos ID - Identification of asbestos in soil samples using Polarised Light Microscopy and Dispersion Staining Techniques. Minimum 500mL soil sample was analysed as recommended by "National Environment Protection (Assessment of site contamination) Measure, Schedule B1 and "The Guidelines from the Assessment, Remediation and Management of Asbestos-Contaminated Sites in Western Australia - May 2009" with a reporting limit of 0.1g/kg (0.01% w/w) as per Australian Standard AS4964-2004.</p> <p>Results reported denoted with * are outside our scope of NATA accreditation.</p> <p><b>NOTE #1</b> Total Asbestos g/kg was analysed and reported as per Australian Standard AS4964 (This is the sum of ACM &gt;7mm, &lt;7mm and FA/AF)</p> <p><b>NOTE #2</b> The screening level of 0.001% w/w asbestos in soil for FA and AF only applies where the FA and AF are able to be quantified by gravimetric procedures. This screening level is not applicable to free fibres.</p> <p>Estimation = Estimated asbestos weight</p> <p>Results reported with "--" is equivalent to no visible asbestos identified using Polarised Light microscopy and Dispersion Staining Techniques.</p>
<b>Inorg-008</b>	Moisture content determined by heating at 105+/-5 °C for a minimum of 12 hours.
<b>Metals-020</b>	Determination of various metals by ICP-AES.
<b>Metals-021</b>	Determination of Mercury by Cold Vapour AAS.
<b>Org-020</b>	<p>Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-FID.</p> <p>F2 = (&gt;C10-C16)-Naphthalene as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater (HSLs Tables 1A (3, 4)). Note Naphthalene is determined from the VOC analysis.</p>
<b>Org-020</b>	<p>Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-FID.</p> <p>F2 = (&gt;C10-C16)-Naphthalene as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater (HSLs Tables 1A (3, 4)). Note Naphthalene is determined from the VOC analysis.</p> <p>Note, the Total +ve TRH PQL is reflective of the lowest individual PQL and is therefore "Total +ve TRH" is simply a sum of the positive individual TRH fractions (&gt;C10-C40).</p>
<b>Org-021</b>	Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC-ECD.



Method ID	Methodology Summary
Org-021	Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC-ECD. Note, the Total +ve PCBs PQL is reflective of the lowest individual PQL and is therefore "Total +ve PCBs" is simply a sum of the positive individual PCBs.
Org-021	Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC with dual ECD's.
Org-022/025	Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS/GC-MSMS.
Org-022/025	Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS/GC-MSMS.
Org-022/025	Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC-MS/GC-MSMS.  Note, the Total +ve reported DDD+DDE+DDT PQL is reflective of the lowest individual PQL and is therefore simply a sum of the positive individually report DDD+DDE+DDT.
Org-022/025	Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS/GC-MSMS. Benzo(a)pyrene TEQ as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater - 2013.
Org-022/025	Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS and/or GC-MS/MS. Benzo(a)pyrene TEQ as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater - 2013. For soil results:- 1. 'EQ PQL' values are assuming all contributing PAHs reported as <PQL are actually at the PQL. This is the most conservative approach and can give false positive TEQs given that PAHs that contribute to the TEQ calculation may not be present. 2. 'EQ zero' values are assuming all contributing PAHs reported as <PQL are zero. This is the least conservative approach and is more susceptible to false negative TEQs when PAHs that contribute to the TEQ calculation are present but below PQL. 3. 'EQ half PQL' values are assuming all contributing PAHs reported as <PQL are half the stipulated PQL. Hence a mid-point between the most and least conservative approaches above. Note, the Total +ve PAHs PQL is reflective of the lowest individual PQL and is therefore "Total +ve PAHs" is simply a sum of the positive individual PAHs.
Org-023	Water samples are analysed directly by purge and trap GC-MS.
Org-023	Soil samples are extracted with methanol and spiked into water prior to analysing by purge and trap GC-MS.
Org-023	Soil samples are extracted with methanol and spiked into water prior to analysing by purge and trap GC-MS. Water samples are analysed directly by purge and trap GC-MS. F1 = (C6-C10)-BTEX as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater.
Org-023	Soil samples are extracted with methanol and spiked into water prior to analysing by purge and trap GC-MS. Water samples are analysed directly by purge and trap GC-MS. F1 = (C6-C10)-BTEX as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater. Note, the Total +ve Xylene PQL is reflective of the lowest individual PQL and is therefore "Total +ve Xylenes" is simply a sum of the positive individual Xylenes.

Client Reference: E35822PR, Temora

QUALITY CONTROL: vTRH(C6-C10)/BTEXN in Soil				Duplicate				Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-6	322581-4
Date extracted	-			10/05/2023	1	10/05/2023	10/05/2023		10/05/2023	10/05/2023
Date analysed	-			11/05/2023	1	11/05/2023	11/05/2023		11/05/2023	11/05/2023
TRH C <sub>6</sub> - C <sub>9</sub>	mg/kg	25	Org-023	<25	1	<25	<25	0	125	126
TRH C <sub>6</sub> - C <sub>10</sub>	mg/kg	25	Org-023	<25	1	<25	<25	0	125	126
Benzene	mg/kg	0.2	Org-023	<0.2	1	<0.2	<0.2	0	114	114
Toluene	mg/kg	0.5	Org-023	<0.5	1	<0.5	<0.5	0	125	126
Ethylbenzene	mg/kg	1	Org-023	<1	1	<1	<1	0	123	123
m+p-xylene	mg/kg	2	Org-023	<2	1	<2	<2	0	132	133
o-Xylene	mg/kg	1	Org-023	<1	1	<1	<1	0	135	137
Naphthalene	mg/kg	1	Org-023	<1	1	<1	<1	0	[NT]	[NT]
Surrogate aaa-Trifluorotoluene	%		Org-023	117	1	111	111	0	114	107

QUALITY CONTROL: vTRH(C6-C10)/BTEXN in Soil				Duplicate				Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-7	322581-23
Date extracted	-			[NT]	11	10/05/2023	10/05/2023		10/05/2023	10/05/2023
Date analysed	-			[NT]	11	11/05/2023	11/05/2023		11/05/2023	11/05/2023
TRH C <sub>6</sub> - C <sub>9</sub>	mg/kg	25	Org-023	[NT]	11	<25	<25	0	123	124
TRH C <sub>6</sub> - C <sub>10</sub>	mg/kg	25	Org-023	[NT]	11	<25	<25	0	123	124
Benzene	mg/kg	0.2	Org-023	[NT]	11	<0.2	<0.2	0	109	115
Toluene	mg/kg	0.5	Org-023	[NT]	11	<0.5	<0.5	0	128	127
Ethylbenzene	mg/kg	1	Org-023	[NT]	11	<1	<1	0	118	119
m+p-xylene	mg/kg	2	Org-023	[NT]	11	<2	<2	0	129	130
o-Xylene	mg/kg	1	Org-023	[NT]	11	<1	<1	0	129	130
Naphthalene	mg/kg	1	Org-023	[NT]	11	<1	<1	0	[NT]	[NT]
Surrogate aaa-Trifluorotoluene	%		Org-023	[NT]	11	107	106	1	114	112

QUALITY CONTROL: vTRH(C6-C10)/BTEXN in Soil				Duplicate				Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	[NT]	[NT]
Date extracted	-			[NT]	20	10/05/2023	10/05/2023		[NT]	[NT]
Date analysed	-			[NT]	20	11/05/2023	11/05/2023		[NT]	[NT]
TRH C <sub>6</sub> - C <sub>9</sub>	mg/kg	25	Org-023	[NT]	20	<25	<25	0	[NT]	[NT]
TRH C <sub>6</sub> - C <sub>10</sub>	mg/kg	25	Org-023	[NT]	20	<25	<25	0	[NT]	[NT]
Benzene	mg/kg	0.2	Org-023	[NT]	20	<0.2	<0.2	0	[NT]	[NT]
Toluene	mg/kg	0.5	Org-023	[NT]	20	<0.5	<0.5	0	[NT]	[NT]
Ethylbenzene	mg/kg	1	Org-023	[NT]	20	<1	<1	0	[NT]	[NT]
m+p-xylene	mg/kg	2	Org-023	[NT]	20	<2	<2	0	[NT]	[NT]
o-Xylene	mg/kg	1	Org-023	[NT]	20	<1	<1	0	[NT]	[NT]
Naphthalene	mg/kg	1	Org-023	[NT]	20	<1	<1	0	[NT]	[NT]
Surrogate aaa-Trifluorotoluene	%		Org-023	[NT]	20	115	115	0	[NT]	[NT]

QUALITY CONTROL: vTRH(C6-C10)/BTEXN in Soil					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	[NT]	[NT]
Date extracted	-			[NT]	33	10/05/2023	10/05/2023		[NT]	[NT]
Date analysed	-			[NT]	33	11/05/2023	11/05/2023		[NT]	[NT]
TRH C <sub>6</sub> - C <sub>9</sub>	mg/kg	25	Org-023	[NT]	33	<25	<25	0	[NT]	[NT]
TRH C <sub>6</sub> - C <sub>10</sub>	mg/kg	25	Org-023	[NT]	33	<25	<25	0	[NT]	[NT]
Benzene	mg/kg	0.2	Org-023	[NT]	33	<0.2	<0.2	0	[NT]	[NT]
Toluene	mg/kg	0.5	Org-023	[NT]	33	<0.5	<0.5	0	[NT]	[NT]
Ethylbenzene	mg/kg	1	Org-023	[NT]	33	<1	<1	0	[NT]	[NT]
m+p-xylene	mg/kg	2	Org-023	[NT]	33	<2	<2	0	[NT]	[NT]
o-Xylene	mg/kg	1	Org-023	[NT]	33	<1	<1	0	[NT]	[NT]
Naphthalene	mg/kg	1	Org-023	[NT]	33	<1	<1	0	[NT]	[NT]
Surrogate aaa-Trifluorotoluene	%		Org-023	[NT]	33	105	104	1	[NT]	[NT]

Client Reference: E35822PR, Temora

QUALITY CONTROL: svTRH (C10-C40) in Soil					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-6	322581-4
Date extracted	-			10/05/2023	1	10/05/2023	10/05/2023		10/05/2023	10/05/2023
Date analysed	-			12/05/2023	1	12/05/2023	12/05/2023		12/05/2023	12/05/2023
TRH C <sub>10</sub> - C <sub>14</sub>	mg/kg	50	Org-020	<50	1	<50	<50	0	103	107
TRH C <sub>15</sub> - C <sub>28</sub>	mg/kg	100	Org-020	<100	1	<100	<100	0	87	87
TRH C <sub>29</sub> - C <sub>36</sub>	mg/kg	100	Org-020	<100	1	<100	<100	0	100	118
TRH >C <sub>10</sub> -C <sub>16</sub>	mg/kg	50	Org-020	<50	1	<50	<50	0	103	107
TRH >C <sub>16</sub> -C <sub>34</sub>	mg/kg	100	Org-020	<100	1	<100	<100	0	87	87
TRH >C <sub>34</sub> -C <sub>40</sub>	mg/kg	100	Org-020	<100	1	<100	<100	0	100	118
Surrogate o-Terphenyl	%		Org-020	83	1	84	85	1	93	85

QUALITY CONTROL: svTRH (C10-C40) in Soil					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-7	322581-23
Date extracted	-			[NT]	11	10/05/2023	10/05/2023		10/05/2023	10/05/2023
Date analysed	-			[NT]	11	12/05/2023	12/05/2023		12/05/2023	12/05/2023
TRH C <sub>10</sub> - C <sub>14</sub>	mg/kg	50	Org-020	[NT]	11	<50	<50	0	130	121
TRH C <sub>15</sub> - C <sub>28</sub>	mg/kg	100	Org-020	[NT]	11	<100	<100	0	101	114
TRH C <sub>29</sub> - C <sub>36</sub>	mg/kg	100	Org-020	[NT]	11	<100	<100	0	100	126
TRH >C <sub>10</sub> -C <sub>16</sub>	mg/kg	50	Org-020	[NT]	11	<50	<50	0	130	121
TRH >C <sub>16</sub> -C <sub>34</sub>	mg/kg	100	Org-020	[NT]	11	<100	<100	0	101	114
TRH >C <sub>34</sub> -C <sub>40</sub>	mg/kg	100	Org-020	[NT]	11	<100	<100	0	100	126
Surrogate o-Terphenyl	%		Org-020	[NT]	11	85	90	6	94	87

QUALITY CONTROL: svTRH (C10-C40) in Soil					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	[NT]	[NT]
Date extracted	-			[NT]	20	10/05/2023	10/05/2023		[NT]	[NT]
Date analysed	-			[NT]	20	12/05/2023	12/05/2023		[NT]	[NT]
TRH C <sub>10</sub> - C <sub>14</sub>	mg/kg	50	Org-020	[NT]	20	<50	<50	0	[NT]	[NT]
TRH C <sub>15</sub> - C <sub>28</sub>	mg/kg	100	Org-020	[NT]	20	<100	<100	0	[NT]	[NT]
TRH C <sub>29</sub> - C <sub>36</sub>	mg/kg	100	Org-020	[NT]	20	<100	<100	0	[NT]	[NT]
TRH >C <sub>10</sub> -C <sub>16</sub>	mg/kg	50	Org-020	[NT]	20	<50	<50	0	[NT]	[NT]
TRH >C <sub>16</sub> -C <sub>34</sub>	mg/kg	100	Org-020	[NT]	20	<100	<100	0	[NT]	[NT]
TRH >C <sub>34</sub> -C <sub>40</sub>	mg/kg	100	Org-020	[NT]	20	<100	<100	0	[NT]	[NT]
Surrogate o-Terphenyl	%		Org-020	[NT]	20	87	87	0	[NT]	[NT]

QUALITY CONTROL: svTRH (C10-C40) in Soil					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	[NT]	[NT]
Date extracted	-			[NT]	33	10/05/2023	10/05/2023		[NT]	[NT]
Date analysed	-			[NT]	33	12/05/2023	12/05/2023		[NT]	[NT]
TRH C <sub>10</sub> - C <sub>14</sub>	mg/kg	50	Org-020	[NT]	33	<50	<50	0	[NT]	[NT]
TRH C <sub>15</sub> - C <sub>28</sub>	mg/kg	100	Org-020	[NT]	33	<100	<100	0	[NT]	[NT]
TRH C <sub>29</sub> - C <sub>36</sub>	mg/kg	100	Org-020	[NT]	33	<100	<100	0	[NT]	[NT]
TRH >C <sub>10</sub> -C <sub>16</sub>	mg/kg	50	Org-020	[NT]	33	<50	<50	0	[NT]	[NT]
TRH >C <sub>16</sub> -C <sub>34</sub>	mg/kg	100	Org-020	[NT]	33	<100	<100	0	[NT]	[NT]
TRH >C <sub>34</sub> -C <sub>40</sub>	mg/kg	100	Org-020	[NT]	33	<100	<100	0	[NT]	[NT]
Surrogate o-Terphenyl	%		Org-020	[NT]	33	82	83	1	[NT]	[NT]

Client Reference: E35822PR, Temora

QUALITY CONTROL: PAHs in Soil				Duplicate				Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-6	322581-4
Date extracted	-			10/05/2023	1	10/05/2023	10/05/2023		10/05/2023	10/05/2023
Date analysed	-			11/05/2023	1	11/05/2023	11/05/2023		11/05/2023	11/05/2023
Naphthalene	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	93	93
Acenaphthylene	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Acenaphthene	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	101	97
Fluorene	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	101	101
Phenanthrene	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	100	83
Anthracene	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Fluoranthene	mg/kg	0.1	Org-022/025	<0.1	1	0.1	0.2	67	102	#
Pyrene	mg/kg	0.1	Org-022/025	<0.1	1	0.1	0.2	67	105	#
Benzo(a)anthracene	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Chrysene	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	93	67
Benzo(b,j+k)fluoranthene	mg/kg	0.2	Org-022/025	<0.2	1	<0.2	<0.2	0	[NT]	[NT]
Benzo(a)pyrene	mg/kg	0.05	Org-022/025	<0.05	1	<0.05	0.1	67	102	69
Indeno(1,2,3-c,d)pyrene	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Dibenzo(a,h)anthracene	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Benzo(g,h,i)perylene	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Surrogate p-Terphenyl-d14	%		Org-022/025	115	1	87	90	3	101	88

QUALITY CONTROL: PAHs in Soil				Duplicate				Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-7	322581-23
Date extracted	-			[NT]	11	10/05/2023	10/05/2023		10/05/2023	10/05/2023
Date analysed	-			[NT]	11	11/05/2023	11/05/2023		12/05/2023	11/05/2023
Naphthalene	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	93	96
Acenaphthylene	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Acenaphthene	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	93	95
Fluorene	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	92	92
Phenanthrene	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	98	64
Anthracene	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Fluoranthene	mg/kg	0.1	Org-022/025	[NT]	11	0.2	0.2	0	114	#
Pyrene	mg/kg	0.1	Org-022/025	[NT]	11	0.2	0.2	0	117	#
Benzo(a)anthracene	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Chrysene	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	101	#
Benzo(b,j+k)fluoranthene	mg/kg	0.2	Org-022/025	[NT]	11	<0.2	<0.2	0	[NT]	[NT]
Benzo(a)pyrene	mg/kg	0.05	Org-022/025	[NT]	11	0.1	0.09	11	114	#
Indeno(1,2,3-c,d)pyrene	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Dibenzo(a,h)anthracene	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Benzo(g,h,i)perylene	mg/kg	0.1	Org-022/025	[NT]	11	0.1	<0.1	0	[NT]	[NT]
Surrogate p-Terphenyl-d14	%		Org-022/025	[NT]	11	100	95	5	96	99

Client Reference: E35822PR, Temora

QUALITY CONTROL: PAHs in Soil				Duplicate				Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	[NT]	[NT]
Date extracted	-			[NT]	20	10/05/2023	10/05/2023		[NT]	[NT]
Date analysed	-			[NT]	20	11/05/2023	11/05/2023		[NT]	[NT]
Naphthalene	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Acenaphthylene	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Acenaphthene	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Fluorene	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Phenanthrene	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Anthracene	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Fluoranthene	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Pyrene	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Benzo(a)anthracene	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Chrysene	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Benzo(b,j+k)fluoranthene	mg/kg	0.2	Org-022/025	[NT]	20	<0.2	<0.2	0	[NT]	[NT]
Benzo(a)pyrene	mg/kg	0.05	Org-022/025	[NT]	20	<0.05	<0.05	0	[NT]	[NT]
Indeno(1,2,3-c,d)pyrene	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Dibenzo(a,h)anthracene	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Benzo(g,h,i)perylene	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Surrogate p-Terphenyl-d14	%		Org-022/025	[NT]	20	86	97	12	[NT]	[NT]

QUALITY CONTROL: PAHs in Soil				Duplicate				Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	[NT]	[NT]
Date extracted	-			[NT]	33	10/05/2023	10/05/2023		[NT]	[NT]
Date analysed	-			[NT]	33	11/05/2023	11/05/2023		[NT]	[NT]
Naphthalene	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Acenaphthylene	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Acenaphthene	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Fluorene	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Phenanthrene	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Anthracene	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Fluoranthene	mg/kg	0.1	Org-022/025	[NT]	33	0.1	0.1	0	[NT]	[NT]
Pyrene	mg/kg	0.1	Org-022/025	[NT]	33	0.1	<0.1	0	[NT]	[NT]
Benzo(a)anthracene	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Chrysene	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Benzo(b,j+k)fluoranthene	mg/kg	0.2	Org-022/025	[NT]	33	<0.2	<0.2	0	[NT]	[NT]
Benzo(a)pyrene	mg/kg	0.05	Org-022/025	[NT]	33	0.05	0.05	0	[NT]	[NT]
Indeno(1,2,3-c,d)pyrene	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Dibenzo(a,h)anthracene	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Benzo(g,h,i)perylene	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Surrogate p-Terphenyl-d14	%		Org-022/025	[NT]	33	102	94	8	[NT]	[NT]

Client Reference: E35822PR, Temora

QUALITY CONTROL: Organochlorine Pesticides in soil					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-6	322581-4
Date extracted	-			10/05/2023	1	10/05/2023	10/05/2023		10/05/2023	10/05/2023
Date analysed	-			11/05/2023	1	11/05/2023	11/05/2023		11/05/2023	11/05/2023
alpha-BHC	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	82	82
HCB	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
beta-BHC	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	108	102
gamma-BHC	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Heptachlor	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	107	103
delta-BHC	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Aldrin	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	103	97
Heptachlor Epoxide	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	98	92
gamma-Chlordane	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
alpha-chlordane	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Endosulfan I	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
pp-DDE	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	115	107
Dieldrin	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	112	110
Endrin	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	103	98
Endosulfan II	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
pp-DDD	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	102	100
Endrin Aldehyde	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
pp-DDT	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Endosulfan Sulphate	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	95	95
Methoxychlor	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Surrogate TCMX	%		Org-022/025	105	1	100	100	0	110	103



Client Reference: E35822PR, Temora

QUALITY CONTROL: Organochlorine Pesticides in soil				Duplicate			Spike Recovery %			
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-7	322581-23
Date extracted	-			[NT]	11	10/05/2023	10/05/2023		10/05/2023	10/05/2023
Date analysed	-			[NT]	11	11/05/2023	11/05/2023		11/05/2023	11/05/2023
alpha-BHC	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	80	98
HCB	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
beta-BHC	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	106	98
gamma-BHC	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Heptachlor	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	103	105
delta-BHC	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Aldrin	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	101	101
Heptachlor Epoxide	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	94	92
gamma-Chlordane	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
alpha-chlordane	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Endosulfan I	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
pp-DDE	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	107	111
Dieldrin	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	112	114
Endrin	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	100	103
Endosulfan II	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
pp-DDD	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	98	102
Endrin Aldehyde	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
pp-DDT	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Endosulfan Sulphate	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	85	89
Methoxychlor	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Surrogate TCMX	%		Org-022/025	[NT]	11	104	115	10	105	102

QUALITY CONTROL: Organochlorine Pesticides in soil				Duplicate			Spike Recovery %			
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	[NT]	[NT]
Date extracted	-			[NT]	20	10/05/2023	10/05/2023		[NT]	[NT]
Date analysed	-			[NT]	20	11/05/2023	11/05/2023		[NT]	[NT]
alpha-BHC	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
HCB	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
beta-BHC	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
gamma-BHC	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Heptachlor	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
delta-BHC	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Aldrin	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Heptachlor Epoxide	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
gamma-Chlordane	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
alpha-chlordane	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Endosulfan I	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
pp-DDE	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Dieldrin	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Endrin	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Endosulfan II	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
pp-DDD	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Endrin Aldehyde	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
pp-DDT	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Endosulfan Sulphate	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Methoxychlor	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Surrogate TCMX	%		Org-022/025	[NT]	20	101	101	0	[NT]	[NT]

QUALITY CONTROL: Organochlorine Pesticides in soil					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	[NT]	[NT]
Date extracted	-			[NT]	33	10/05/2023	10/05/2023		[NT]	[NT]
Date analysed	-			[NT]	33	11/05/2023	11/05/2023		[NT]	[NT]
alpha-BHC	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
HCB	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
beta-BHC	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
gamma-BHC	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Heptachlor	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
delta-BHC	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Aldrin	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Heptachlor Epoxide	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
gamma-Chlordane	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
alpha-chlordane	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Endosulfan I	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
pp-DDE	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Dieldrin	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Endrin	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Endosulfan II	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
pp-DDD	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Endrin Aldehyde	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
pp-DDT	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Endosulfan Sulphate	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Methoxychlor	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Surrogate TCMX	%		Org-022/025	[NT]	33	103	115	11	[NT]	[NT]

Client Reference: E35822PR, Temora

QUALITY CONTROL: Organophosphorus Pesticides				Duplicate			Spike Recovery %			
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-6	322581-4
Date extracted	-			10/05/2023	1	10/05/2023	10/05/2023		10/05/2023	10/05/2023
Date analysed	-			11/05/2023	1	11/05/2023	11/05/2023		11/05/2023	11/05/2023
Azinphos-methyl (Guthion)	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Bromophos-ethyl	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Chlorpyrifos	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	108	104
Chlorpyrifos-methyl	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Diazinon	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Dichlorvos	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	99	113
Dimethoate	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Ethion	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	96	104
Fenitrothion	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	115	113
Malathion	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	108	103
Parathion	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	111	111
Ronnel	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	104	95
Coumaphos	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Disulfoton	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Fenamiphos	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Fenthion	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Methidathion	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Mevinphos	mg/kg	0.1	Org-022/025	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Parathion (Methyl)	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Phorate	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Phosalone	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Surrogate TCMX	%		Org-021	105	1	100	100	0	110	103

QUALITY CONTROL: Organophosphorus Pesticides				Duplicate			Spike Recovery %			
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-7	322581-23
Date extracted	-			[NT]	11	10/05/2023	10/05/2023		10/05/2023	10/05/2023
Date analysed	-			[NT]	11	11/05/2023	11/05/2023		11/05/2023	11/05/2023
Azinphos-methyl (Guthion)	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Bromophos-ethyl	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Chlorpyriphos	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	108	106
Chlorpyriphos-methyl	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Diazinon	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Dichlorvos	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	107	113
Dimethoate	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Ethion	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	106	113
Fenitrothion	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	111	119
Malathion	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	105	108
Parathion	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	113	121
Ronnel	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	97	101
Coumaphos	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Disulfoton	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Fenamiphos	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Fenthion	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Methidathion	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Mevinphos	mg/kg	0.1	Org-022/025	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Parathion (Methyl)	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Phorate	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Phosalone	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Surrogate TCMX	%		Org-021	[NT]	11	104	115	10	105	102

QUALITY CONTROL: Organophosphorus Pesticides				Duplicate			Spike Recovery %			
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	[NT]	[NT]
Date extracted	-			[NT]	20	10/05/2023	10/05/2023		[NT]	[NT]
Date analysed	-			[NT]	20	11/05/2023	11/05/2023		[NT]	[NT]
Azinphos-methyl (Guthion)	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Bromophos-ethyl	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Chlorpyrifos	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Chlorpyrifos-methyl	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Diazinon	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Dichlorvos	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Dimethoate	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Ethion	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Fenitrothion	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Malathion	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Parathion	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Ronnel	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Coumaphos	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Disulfoton	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Fenamiphos	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Fenthion	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Methidathion	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Mevinphos	mg/kg	0.1	Org-022/025	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Parathion (Methyl)	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Phorate	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Phosalone	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Surrogate TCMX	%		Org-021	[NT]	20	101	101	0	[NT]	[NT]

QUALITY CONTROL: Organophosphorus Pesticides					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	[NT]	[NT]
Date extracted	-			[NT]	33	10/05/2023	10/05/2023		[NT]	[NT]
Date analysed	-			[NT]	33	11/05/2023	11/05/2023		[NT]	[NT]
Azinphos-methyl (Guthion)	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Bromophos-ethyl	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Chlorpyrifos	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Chlorpyrifos-methyl	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Diazinon	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Dichlorvos	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Dimethoate	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Ethion	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Fenitrothion	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Malathion	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Parathion	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Ronnel	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Coumaphos	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Disulfoton	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Fenamiphos	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Fenthion	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Methidathion	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Mevinphos	mg/kg	0.1	Org-022/025	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Parathion (Methyl)	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Phorate	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Phosalone	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Surrogate TCMX	%		Org-021	[NT]	33	103	115	11	[NT]	[NT]

Client Reference: E35822PR, Temora

QUALITY CONTROL: PCBs in Soil					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-6	322581-4
Date extracted	-			10/05/2023	1	10/05/2023	10/05/2023		10/05/2023	10/05/2023
Date analysed	-			11/05/2023	1	11/05/2023	11/05/2023		11/05/2023	11/05/2023
Aroclor 1016	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1221	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1232	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1242	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1248	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1254	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	122	100
Aroclor 1260	mg/kg	0.1	Org-021	<0.1	1	<0.1	<0.1	0	[NT]	[NT]
Surrogate TCMX	%		Org-021	105	1	100	100	0	110	103

QUALITY CONTROL: PCBs in Soil					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-7	322581-23
Date extracted	-			[NT]	11	10/05/2023	10/05/2023		10/05/2023	10/05/2023
Date analysed	-			[NT]	11	11/05/2023	11/05/2023		11/05/2023	11/05/2023
Aroclor 1016	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1221	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1232	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1242	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1248	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1254	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	116	120
Aroclor 1260	mg/kg	0.1	Org-021	[NT]	11	<0.1	<0.1	0	[NT]	[NT]
Surrogate TCMX	%		Org-021	[NT]	11	104	115	10	105	102

QUALITY CONTROL: PCBs in Soil					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	[NT]	[NT]
Date extracted	-			[NT]	20	10/05/2023	10/05/2023		[NT]	[NT]
Date analysed	-			[NT]	20	11/05/2023	11/05/2023		[NT]	[NT]
Aroclor 1016	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1221	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1232	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1242	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1248	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1254	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1260	mg/kg	0.1	Org-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Surrogate TCMX	%		Org-021	[NT]	20	101	101	0	[NT]	[NT]



QUALITY CONTROL: PCBs in Soil				Duplicate			Spike Recovery %			
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	[NT]	[NT]
Date extracted	-			[NT]	33	10/05/2023	10/05/2023		[NT]	[NT]
Date analysed	-			[NT]	33	11/05/2023	11/05/2023		[NT]	[NT]
Aroclor 1016	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1221	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1232	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1242	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1248	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1254	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Aroclor 1260	mg/kg	0.1	Org-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Surrogate TCMX	%		Org-021	[NT]	33	103	115	11	[NT]	[NT]

Client Reference: E35822PR, Temora

QUALITY CONTROL: Acid Extractable metals in soil				Duplicate				Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-6	322581-4
Date prepared	-			11/05/2023	1	11/05/2023	11/05/2023		11/05/2023	11/05/2023
Date analysed	-			12/05/2023	1	12/05/2023	12/05/2023		12/05/2023	12/05/2023
Arsenic	mg/kg	4	Metals-020	<4	1	<4	<4	0	106	82
Cadmium	mg/kg	0.4	Metals-020	<0.4	1	<0.4	<0.4	0	101	75
Chromium	mg/kg	1	Metals-020	<1	1	37	38	3	105	92
Copper	mg/kg	1	Metals-020	<1	1	70	70	0	107	##
Lead	mg/kg	1	Metals-020	<1	1	7	9	25	104	82
Mercury	mg/kg	0.1	Metals-021	<0.1	1	<0.1	<0.1	0	113	113
Nickel	mg/kg	1	Metals-020	<1	1	10	10	0	104	81
Zinc	mg/kg	1	Metals-020	<1	1	22	25	13	98	#

QUALITY CONTROL: Acid Extractable metals in soil				Duplicate				Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-7	322581-23
Date prepared	-			[NT]	11	11/05/2023	11/05/2023		11/05/2023	11/05/2023
Date analysed	-			[NT]	11	12/05/2023	12/05/2023		12/05/2023	12/05/2023
Arsenic	mg/kg	4	Metals-020	[NT]	11	5	5	0	101	105
Cadmium	mg/kg	0.4	Metals-020	[NT]	11	<0.4	<0.4	0	97	95
Chromium	mg/kg	1	Metals-020	[NT]	11	30	28	7	99	99
Copper	mg/kg	1	Metals-020	[NT]	11	82	80	2	100	100
Lead	mg/kg	1	Metals-020	[NT]	11	28	26	7	99	97
Mercury	mg/kg	0.1	Metals-021	[NT]	11	<0.1	<0.1	0	113	129
Nickel	mg/kg	1	Metals-020	[NT]	11	7	6	15	100	99
Zinc	mg/kg	1	Metals-020	[NT]	11	53	53	0	94	86

QUALITY CONTROL: Acid Extractable metals in soil				Duplicate				Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	[NT]	[NT]
Date prepared	-			[NT]	20	11/05/2023	11/05/2023		[NT]	[NT]
Date analysed	-			[NT]	20	12/05/2023	12/05/2023		[NT]	[NT]
Arsenic	mg/kg	4	Metals-020	[NT]	20	7	6	15	[NT]	[NT]
Cadmium	mg/kg	0.4	Metals-020	[NT]	20	<0.4	<0.4	0	[NT]	[NT]
Chromium	mg/kg	1	Metals-020	[NT]	20	36	51	34	[NT]	[NT]
Copper	mg/kg	1	Metals-020	[NT]	20	94	100	6	[NT]	[NT]
Lead	mg/kg	1	Metals-020	[NT]	20	24	20	18	[NT]	[NT]
Mercury	mg/kg	0.1	Metals-021	[NT]	20	<0.1	<0.1	0	[NT]	[NT]
Nickel	mg/kg	1	Metals-020	[NT]	20	9	11	20	[NT]	[NT]
Zinc	mg/kg	1	Metals-020	[NT]	20	36	34	6	[NT]	[NT]

QUALITY CONTROL: Acid Extractable metals in soil					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	[NT]	[NT]
Date prepared	-			[NT]	33	11/05/2023	11/05/2023		[NT]	[NT]
Date analysed	-			[NT]	33	12/05/2023	12/05/2023		[NT]	[NT]
Arsenic	mg/kg	4	Metals-020	[NT]	33	6	5	18	[NT]	[NT]
Cadmium	mg/kg	0.4	Metals-020	[NT]	33	<0.4	<0.4	0	[NT]	[NT]
Chromium	mg/kg	1	Metals-020	[NT]	33	21	19	10	[NT]	[NT]
Copper	mg/kg	1	Metals-020	[NT]	33	34	29	16	[NT]	[NT]
Lead	mg/kg	1	Metals-020	[NT]	33	12	12	0	[NT]	[NT]
Mercury	mg/kg	0.1	Metals-021	[NT]	33	<0.1	<0.1	0	[NT]	[NT]
Nickel	mg/kg	1	Metals-020	[NT]	33	7	7	0	[NT]	[NT]
Zinc	mg/kg	1	Metals-020	[NT]	33	30	30	0	[NT]	[NT]

QUALITY CONTROL: vTRH(C6-C10)/BTEXN in Water					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-W3	[NT]
Date extracted	-			09/05/2023	[NT]	[NT]	[NT]	[NT]	09/05/2023	[NT]
Date analysed	-			10/05/2023	[NT]	[NT]	[NT]	[NT]	10/05/2023	[NT]
TRH C <sub>6</sub> - C <sub>9</sub>	µg/L	10	Org-023	<10	[NT]	[NT]	[NT]	[NT]	114	[NT]
TRH C <sub>6</sub> - C <sub>10</sub>	µg/L	10	Org-023	<10	[NT]	[NT]	[NT]	[NT]	114	[NT]
Benzene	µg/L	1	Org-023	<1	[NT]	[NT]	[NT]	[NT]	119	[NT]
Toluene	µg/L	1	Org-023	<1	[NT]	[NT]	[NT]	[NT]	111	[NT]
Ethylbenzene	µg/L	1	Org-023	<1	[NT]	[NT]	[NT]	[NT]	114	[NT]
m+p-xylene	µg/L	2	Org-023	<2	[NT]	[NT]	[NT]	[NT]	118	[NT]
o-xylene	µg/L	1	Org-023	<1	[NT]	[NT]	[NT]	[NT]	116	[NT]
Naphthalene	µg/L	1	Org-023	<1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Surrogate Dibromofluoromethane	%		Org-023	99	[NT]	[NT]	[NT]	[NT]	100	[NT]
Surrogate toluene-d8	%		Org-023	98	[NT]	[NT]	[NT]	[NT]	100	[NT]
Surrogate 4-BFB	%		Org-023	106	[NT]	[NT]	[NT]	[NT]	104	[NT]

QUALITY CONTROL: svTRH (C10-C40) in Water					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-W1	[NT]
Date extracted	-			12/05/2023	[NT]	[NT]	[NT]	[NT]	12/05/2023	[NT]
Date analysed	-			12/05/2023	[NT]	[NT]	[NT]	[NT]	12/05/2023	[NT]
TRH C <sub>10</sub> - C <sub>14</sub>	µg/L	50	Org-020	<50	[NT]	[NT]	[NT]	[NT]	95	[NT]
TRH C <sub>15</sub> - C <sub>28</sub>	µg/L	100	Org-020	<100	[NT]	[NT]	[NT]	[NT]	100	[NT]
TRH C <sub>29</sub> - C <sub>36</sub>	µg/L	100	Org-020	<100	[NT]	[NT]	[NT]	[NT]	114	[NT]
TRH >C <sub>10</sub> - C <sub>16</sub>	µg/L	50	Org-020	<50	[NT]	[NT]	[NT]	[NT]	95	[NT]
TRH >C <sub>16</sub> - C <sub>34</sub>	µg/L	100	Org-020	<100	[NT]	[NT]	[NT]	[NT]	100	[NT]
TRH >C <sub>34</sub> - C <sub>40</sub>	µg/L	100	Org-020	<100	[NT]	[NT]	[NT]	[NT]	114	[NT]
Surrogate o-Terphenyl	%		Org-020	73	[NT]	[NT]	[NT]	[NT]	90	[NT]

Client Reference: E35822PR, Temora

QUALITY CONTROL: PAHs in Water				Duplicate				Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-W3	[NT]
Date extracted	-			12/05/2023	[NT]	[NT]	[NT]	[NT]	12/05/2023	[NT]
Date analysed	-			12/05/2023	[NT]	[NT]	[NT]	[NT]	12/05/2023	[NT]
Naphthalene	µg/L	2	Org-022/025	<2	[NT]	[NT]	[NT]	[NT]	117	[NT]
Acenaphthylene	µg/L	1	Org-022/025	<1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Acenaphthene	µg/L	1	Org-022/025	<1	[NT]	[NT]	[NT]	[NT]	113	[NT]
Fluorene	µg/L	1	Org-022/025	<1	[NT]	[NT]	[NT]	[NT]	123	[NT]
Phenanthrene	µg/L	1	Org-022/025	<1	[NT]	[NT]	[NT]	[NT]	103	[NT]
Anthracene	µg/L	1	Org-022/025	<1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Fluoranthene	µg/L	1	Org-022/025	<1	[NT]	[NT]	[NT]	[NT]	108	[NT]
Pyrene	µg/L	1	Org-022/025	<1	[NT]	[NT]	[NT]	[NT]	115	[NT]
Benzo(a)anthracene	µg/L	1	Org-022/025	<1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Chrysene	µg/L	1	Org-022/025	<1	[NT]	[NT]	[NT]	[NT]	84	[NT]
Benzo(b,j+k)fluoranthene	µg/L	2	Org-022/025	<2	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Benzo(a)pyrene	µg/L	1	Org-022/025	<1	[NT]	[NT]	[NT]	[NT]	106	[NT]
Indeno(1,2,3-c,d)pyrene	µg/L	1	Org-022/025	<1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Dibenzo(a,h)anthracene	µg/L	1	Org-022/025	<1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Benzo(g,h,i)perylene	µg/L	1	Org-022/025	<1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Surrogate p-Terphenyl-d14	%		Org-022/025	75	[NT]	[NT]	[NT]	[NT]	121	[NT]

QUALITY CONTROL: Metals in Waters - Acid extractable					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-W1	[NT]
Date prepared	-			11/05/2023	[NT]	[NT]	[NT]	[NT]	11/05/2023	[NT]
Date analysed	-			12/05/2023	[NT]	[NT]	[NT]	[NT]	12/05/2023	[NT]
Arsenic - Total	mg/L	0.05	Metals-020	<0.05	[NT]	[NT]	[NT]	[NT]	118	[NT]
Cadmium - Total	mg/L	0.01	Metals-020	<0.01	[NT]	[NT]	[NT]	[NT]	108	[NT]
Chromium - Total	mg/L	0.01	Metals-020	<0.01	[NT]	[NT]	[NT]	[NT]	113	[NT]
Copper - Total	mg/L	0.01	Metals-020	<0.01	[NT]	[NT]	[NT]	[NT]	118	[NT]
Lead - Total	mg/L	0.03	Metals-020	<0.03	[NT]	[NT]	[NT]	[NT]	110	[NT]
Mercury - Total	mg/L	0.0005	Metals-021	<0.0005	[NT]	[NT]	[NT]	[NT]	108	[NT]
Nickel - Total	mg/L	0.02	Metals-020	<0.02	[NT]	[NT]	[NT]	[NT]	112	[NT]
Zinc - Total	mg/L	0.02	Metals-020	<0.02	[NT]	[NT]	[NT]	[NT]	104	[NT]

**Result Definitions**

<b>NT</b>	Not tested
<b>NA</b>	Test not required
<b>INS</b>	Insufficient sample for this test
<b>PQL</b>	Practical Quantitation Limit
<b>&lt;</b>	Less than
<b>&gt;</b>	Greater than
<b>RPD</b>	Relative Percent Difference
<b>LCS</b>	Laboratory Control Sample
<b>NS</b>	Not specified
<b>NEPM</b>	National Environmental Protection Measure
<b>NR</b>	Not Reported



## Quality Control Definitions

<b>Blank</b>	This is the component of the analytical signal which is not derived from the sample but from reagents, glassware etc, can be determined by processing solvents and reagents in exactly the same manner as for samples.
<b>Duplicate</b>	This is the complete duplicate analysis of a sample from the process batch. If possible, the sample selected should be one where the analyte concentration is easily measurable.
<b>Matrix Spike</b>	A portion of the sample is spiked with a known concentration of target analyte. The purpose of the matrix spike is to monitor the performance of the analytical method used and to determine whether matrix interferences exist.
<b>LCS (Laboratory Control Sample)</b>	This comprises either a standard reference material or a control matrix (such as a blank sand or water) fortified with analytes representative of the analyte class. It is simply a check sample.
<b>Surrogate Spike</b>	Surrogates are known additions to each sample, blank, matrix spike and LCS in a batch, of compounds which are similar to the analyte of interest, however are not expected to be found in real samples.
Australian Drinking Water Guidelines recommend that Thermotolerant Coliform, Faecal Enterococci, & E.Coli levels are less than 1cfu/100mL. The recommended maximums are taken from "Australian Drinking Water Guidelines", published by NHMRC & ARMC 2011.	
The recommended maximums for analytes in urine are taken from "2018 TLVs and BEIs", as published by ACGIH (where available). Limit provided for Nickel is a precautionary guideline as per Position Paper prepared by AIOH Exposure Standards Committee, 2016.	
Guideline limits for Rinse Water Quality reported as per analytical requirements and specifications of AS 4187, Amdt 2 2019, Table 7.2	

## Laboratory Acceptance Criteria

Duplicate sample and matrix spike recoveries may not be reported on smaller jobs, however, were analysed at a frequency to meet or exceed NEPM requirements. All samples are tested in batches of 20. The duplicate sample RPD and matrix spike recoveries for the batch were within the laboratory acceptance criteria.

Filters, swabs, wipes, tubes and badges will not have duplicate data as the whole sample is generally extracted during sample extraction.

Spikes for Physical and Aggregate Tests are not applicable.

For VOCs in water samples, three vials are required for duplicate or spike analysis.

Duplicates: >10xPQL - RPD acceptance criteria will vary depending on the analytes and the analytical techniques but is typically in the range 20%-50% – see ELN-P05 QA/QC tables for details; <10xPQL - RPD are higher as the results approach PQL and the estimated measurement uncertainty will statistically increase.

Matrix Spikes, LCS and Surrogate recoveries: Generally 70-130% for inorganics/metals (not SPOCAS); 60-140% for organics/SPOCAS (+/-50% surrogates) and 10-140% for labile SVOCs (including labile surrogates), ultra trace organics and speciated phenols is acceptable.

In circumstances where no duplicate and/or sample spike has been reported at 1 in 10 and/or 1 in 20 samples respectively, the sample volume submitted was insufficient in order to satisfy laboratory QA/QC protocols.

When samples are received where certain analytes are outside of recommended technical holding times (THTs), the analysis has proceeded. Where analytes are on the verge of breaching THTs, every effort will be made to analyse within the THT or as soon as practicable.

Where sampling dates are not provided, Envirolab are not in a position to comment on the validity of the analysis where recommended technical holding times may have been breached.

Where matrix spike recoveries fall below the lower limit of the acceptance criteria (e.g. for non-labile or standard Organics <60%), positive result(s) in the parent sample will subsequently have a higher than typical estimated uncertainty (MU estimates supplied on request) and in these circumstances the sample result is likely biased significantly low.

Measurement Uncertainty estimates are available for most tests upon request.

Analysis of aqueous samples typically involves the extraction/digestion and/or analysis of the liquid phase only (i.e. NOT any settled sediment phase but inclusive of suspended particles if present), unless stipulated on the Envirolab COC and/or by correspondence. Notable exceptions include certain Physical Tests (pH/EC/BOD/COD/Apparent Colour etc.), Solids testing, total recoverable metals and PFAS where solids are included by default.

Samples for Microbiological analysis (not Amoeba forms) received outside of the 2-8°C temperature range do not meet the ideal cooling conditions as stated in AS2031-2012.

## Report Comments

### PAH\_S:

# Percent recovery for the matrix spike is not possible to report as the high concentration of analytes in samples 322581-4ms, 23ms have caused interference.

### Asbestos-ID in soil: NEPM

This report is consistent with the reporting recommendations in the National Environment Protection (Assessment of Site Contamination) Measure, Schedule B1, May 2013. This is reported outside our scope of NATA accreditation.

Note: All samples analysed as received. However, sample 322581-8 is below the minimum recommended 500mL sample volume as per National Environment Protection (Assessment of Site Contamination) Measure, Schedule B1, May 2013.

### 8 metals in soil :

- # Percent recovery is not possible to report due to the inhomogeneous nature of the element/s in the sample/s. However an acceptable recovery was obtained for the LCS.

-## Percent recovery is not applicable due to the high concentration of the element/s in the sample/s. However an acceptable recovery was obtained for the LCS.

## SAMPLE RECEIPT ADVICE

### Client Details

<b>Client</b>	JK Environments
<b>Attention</b>	C Ridley

### Sample Login Details

<b>Your reference</b>	E35822PR, Temora
<b>Envirolab Reference</b>	322581
<b>Date Sample Received</b>	08/05/2023
<b>Date Instructions Received</b>	08/05/2023
<b>Date Results Expected to be Reported</b>	15/05/2023

### Sample Condition

<b>Samples received in appropriate condition for analysis</b>	Yes
<b>No. of Samples Provided</b>	44 Soil, 1 Water, 2 Material
<b>Turnaround Time Requested</b>	Standard
<b>Temperature on Receipt (°C)</b>	8
<b>Cooling Method</b>	Ice
<b>Sampling Date Provided</b>	YES

### Comments

Nil

Please direct any queries to:

#### Aileen Hie

**Phone:** 02 9910 6200  
**Fax:** 02 9910 6201  
**Email:** ahie@envirolab.com.au

#### Jacinta Hurst

**Phone:** 02 9910 6200  
**Fax:** 02 9910 6201  
**Email:** jhurst@envirolab.com.au

*Analysis Underway, details on the following page:*



Sample ID	VTRH(C6-C10)/BTEXN in Soil	svTRH (C10-C40) in Soil	PAHs in Soil	Organochlorine Pesticides in soil	Organophosphorus Pesticides	PCBs in Soil	Acid Extractable metals in soil	Asbestos ID - soils NEPM - ASB-001	Asbestos ID - materials	VTRH(C6-C10)/BTEXN in Water	svTRH (C10-C40) in Water	PAHs in Water	Metals in Waters -Acid extractable	On Hold
BH1-0-0.3	✓	✓	✓	✓	✓	✓	✓	✓						
BH1-0.3-0.5														✓
BH1-0.8-1.0	✓	✓	✓				✓							
BH2-0-0.2	✓	✓	✓	✓	✓	✓	✓	✓						
BH2-0.3-0.5	✓	✓	✓				✓							
BH2-0.8-1.0	✓	✓	✓				✓							
BH3-0-0.1	✓	✓	✓	✓	✓	✓	✓	✓						
BH3-0.3-0.5	✓	✓	✓	✓	✓	✓	✓	✓						
BH3-0.8-1.0														✓
BH3-1.3-1.5	✓	✓	✓				✓							
BH4-0-0.1	✓	✓	✓	✓	✓	✓	✓	✓						
BH4-0.3-0.5	✓	✓	✓				✓							
BH4-0.8-1.0	✓	✓	✓				✓							
BH5-0-0.1	✓	✓	✓	✓	✓	✓	✓	✓						
BH5-0.3-0.5														✓
BH5-0.8-1.0	✓	✓	✓				✓							
BH6-0.02-0.3	✓	✓	✓	✓	✓	✓	✓	✓						
BH6-0.3-0.5	✓	✓	✓				✓							
BH6-0.8-1.0	✓	✓	✓				✓							
BH7-0-0.1	✓	✓	✓	✓	✓	✓	✓	✓						
BH7-0.3-0.5	✓	✓	✓				✓							
BH7-0.8-1.0														✓
BH8-0.02-0.2	✓	✓	✓	✓	✓	✓	✓	✓						
BH8-0.3-0.5	✓	✓	✓				✓							
BH8-0.8-1.0														✓
BH8-1.3-1.5														✓
TP13-0-0.1	✓	✓	✓	✓	✓	✓	✓	✓						
TP13-0.5-0.6	✓	✓	✓				✓							
TP13-0.9-1.0														✓
TP14-0-0.1	✓	✓	✓	✓	✓	✓	✓	✓						
TP14-0.4-0.5	✓	✓	✓				✓							
TP14-0.9-1.0	✓	✓	✓				✓							

Sample ID	VTRH(C6-C10)/BTEXN in Soil	svTRH (C10-C40) in Soil	PAHs in Soil	Organochlorine Pesticides in soil	Organophosphorus Pesticides	PCBs in Soil	Acid Extractable metals in soil	Asbestos ID - soils NEPM - ASB-001	Asbestos ID - materials	VTRH(C6-C10)/BTEXN in Water	svTRH (C10-C40) in Water	PAHs in Water	Metals in Waters -Acid extractable	On Hold
TP15-0-0.1	✓	✓	✓	✓	✓	✓	✓	✓						
TP15-0.4-0.5														✓
TP15-0.9-1.0	✓	✓	✓	✓	✓	✓	✓	✓						
TP15-1.3-1.5	✓	✓	✓				✓							
TP16-0-0.1	✓	✓	✓	✓	✓	✓	✓	✓						
TP16-0.4-0.5	✓	✓	✓				✓							
TP16-0.9-1.0														✓
SDUP1	✓	✓	✓	✓	✓	✓	✓							
SDUP2	✓	✓	✓				✓							
TB-S1	✓	✓	✓				✓							
TS-S1	✓													
FR-SPT										✓	✓	✓	✓	
BH4-FCF1									✓					
BH4-FCF2									✓					
TP3-0.4-0.5														✓

The '✓' indicates the testing you have requested. **THIS IS NOT A REPORT OF THE RESULTS.**

### Additional Info

Sample storage - Waters are routinely disposed of approximately 1 month and soils approximately 2 months from receipt.

Requests for longer term sample storage must be received in writing.

Please contact the laboratory immediately if observed settled sediment present in water samples is to be included in the extraction and/or analysis (exceptions include certain Physical Tests (pH/EC/BOD/COD/Apparent Colour etc.), Solids testing, Total Recoverable metals and PFAS analysis where solids are included by default.

TAT for Micro is dependent on incubation. This varies from 3 to 6 days.

**SAMPLE AND CHAIN OF CUSTODY FORM**

<b>TO:</b> ENVIROLAB SERVICES PTY LTD 12 ASHLEY STREET CHATSWOOD NSW 2067 P: (02) 99106200 F: (02) 99106201 Attention: Aileen	<b>JKE Job Number:</b> E35822PR <b>Date Results Required:</b> STANDARD Page: 1 of 2	<b>FROM:</b>  REAR OF 115 WICKS ROAD MACQUARIE PARK, NSW 2113 P: 02-9888 5000 F: 02-9888 5001 Attention: Craig Ridley cridley@jkenvironments.com.au
---	---	---

<b>Location:</b>	Temora	<b>Sample Preserved in Esky on Ice</b>
------------------	--------	--

<b>Sampler:</b>	AD	<b>Tests Required</b>
-----------------	----	-----------------------

Date Sampled	Lab Ref:	Sample Number	Depth (m)	Sample Container	PID	Sample Description	Combo 1an	Combo 2an	Combo 6	Combo 3	Asbestos [NEPM]	Asbestos ID	TRH/BTEX	BTEX
4/05/2023	1	BH1	0-0.3	G, A	0.5	Silty Clay	X							
4/05/2023	2	BH1	0.3-0.5	G, A	0.4	Silty Clay								
4/05/2023	3	BH1	0.8-1.0	G, A	0.3	XW Andesite				X				
3/05/2023	4	BH1	0-0.2	G, A	1.3	F: Gravelly Silty Clay	X							
3/05/2023	5	BH2	0.3-0.5	G, A	1.9	Sandy Silty Clay				X				
3/05/2023	6	BH2	0.8-1.0	G, A	1.8	Silty Clay				X				
4/05/2023	7	BH3	0-0.1	G, A	0.6	F: Silty Clay	X							
4/05/2023	8	BH3	0.3-0.5	G, A	0.7	F: Sandy Silty Clay	X							
4/05/2023	9	BH3	0.8-1.0	G, A	0.6	F: Sandy Silty Clay								
4/05/2023	10	BH3	1.3-1.5	G, A	1.5	Sandy Silty Clay				X				
4/05/2023	11	BH4	0-0.1	G, A	2.2	F: Silty Clay	X							
4/05/2023	12	BH4	0.3-0.5	G, A	2	Sandy Silty Clay				X				
4/05/2023	13	BH4	0.8-1.0	G, A	3.8	XW Andesite				X				
3/05/2023	14	BH5	0-0.1	G, A	0.6	Silty Clay	X							
3/05/2023	15	BH5	0.3-0.5	G, A	0.5	Silty Clay								
3/05/2023	16	BH5	0.8-1.0	G, A	0.6	Silty Clay				X				
2/05/2023	17	BH6	0-0.1 0.02-0.3	G, A	0.4	F: Silty Clay	X							
2/05/2023	18	BH6	0.3-0.5	G	0.1	Sandy Silty Clay				X				
2/05/2023	19	BH4	0.8-1.0	G	0.1	XW Andesite				X				
2/05/2023	20	BH7	0-0.3	G, A	0.8	F: Gravelly Silty Sand	X							
2/05/2023	21	BH6	0.3-0.5	G, A	2	Sandy Silt				X				
2/05/2023	22	BH7	0.8-1.0	G	0	XW Andesite								
5/05/2023	23	BH8	0.02-0.2	G, A	0	F: Silty Sand	X							
5/05/2023	24	BH8	0.3-0.5	G, A	0.3	Sandy Silty Clay				X				
5/05/2023	25	BH8	0.8-1.0	G, A	0.4	Sandy Silty Clay								
5/05/2023	26	BH8	1.3-1.5	G, A	0.4	Sandy Silty Clay								

<b>Remarks (comments/detection limits required):</b>	Sample Containers: G - 250mg Glass Jar A - Ziplock Asbestos Bag P - Plastic Bag	Received By: SP Temp: Cool/Ambient Cooling: Ice/Icepack Security: Intact/Broken/None
--	--	---

Relinquished By: AD	Date: 08/05/23	Time: 10:30am	Received By: ELS SYD Sarah P	Date: 08/05/23
---------------------	----------------	---------------	------------------------------	----------------

EnviroLab Services  
 12 Ashley St  
 Chatswood NSW 2067  
 Ph: (02) 9910 6200  
 Job No: 322581  
 Date Received: 08/05/23  
 Time Received: 1:30

updated

**SAMPLE AND CHAIN OF CUSTODY FORM**

<b>TO:</b> ENVIROLAB SERVICES PTY LTD 12 ASHLEY STREET CHATSWOOD NSW 2067 P: (02) 99106200 F: (02) 99106201 Attention: Aileen	<b>JKE Job</b> <u>E35822PR</u> <b>Number:</b>  <b>Date Results</b> <u>STANDARD</u> <b>Required:</b>  <b>Page:</b> <u>2 of 2</u>	<b>FROM:</b> <b>JK Environments</b> REAR OF 115 WICKS ROAD MACQUARIE PARK, NSW 2113 P: 02-9888 5000      F: 02-9888 5001 Attention: <u>Craig Ridley</u> cridley@jkenvironments.com.au
---	---	---

Location:		Temora					Sample Preserved in Esky on Ice													
Sampler:		AD					Tests Required													
Date Sampled	Lab Ref:	Sample Number	Depth (m)	Sample Container	PID	Sample Description	Combo 6a	Combo 3a	Combo 6	Combo 3	Asbestos (NEM)	Asbestos ID	TRH/BTEX	BTEX						
4/05/2023		TP13	0-0.1	G, A	0.6	F: Silty Clay	X													
4/05/2023		TP13	0.5-0.6	G, A	1.3	Silty Clay				X										
4/05/2023		TP13	0.9-1.0	G, A	2.4	Silty Clay														
4/05/2023		TP13	0-0.1	G, A	1	F: Silty Clay	X													
4/05/2023		TP14	0.4-0.5	G, A	0.5	Silty Clay				X										
4/05/2023		TP14	0.9-1.0	G, A	1.1	XW Andesite				X										
4/05/2023		TP13	0-0.1	G, A	0.3	F: Silty Clay	X													
4/05/2023		TP15	0.4-0.5	G, A	0.2	F: Silty Clay														
4/05/2023		TP15	0.9-1.0	G, A	0.4	F: Sandy Silty Clay	X													
4/05/2023		TP14	1.3-1.5	G, A	0.6	Silty Clay				X										
4/05/2023		TP16	0-0.1	G, A	0.2	Silty Clay	X													
4/05/2023		TP15	0.4-0.5	G, A	1.2	Silty Clay				X										
4/05/2023		TP16	0.9-1.0	G, A	0.3	XW Andesite														
4/05/2023		SDUP1	-	G	-	Soil Duplicate			X											
4/05/2023		SDUP1	-	G	-	Soil Duplicate				X										
4/05/2023		SDUP3	-	G	-	Soil Duplicate			X											
4/05/2023		SDUP4	-	G	-	Soil Duplicate				X										
2/05/2023		TB-S1	-	V	-	Trip Blank				X										
2/05/2023		TS-S1	-	V	-	Trip Spike													X	
2/05/2023		FR-SPT	-	#	-	Field Rinsate				X										
4/05/2023		BH4-FCF1	0-0.1	A	-	Fragment						X								
4/05/2023		BH4-FCF2	0-0.1	A	-	Fragment						X								

**\*\* PLEASE SEND SDUP3 AND SDUP4 FOR INTER-LAB ANALYSIS**

<b>Remarks (comments/detection limits required):</b>  	<b>Sample Containers:</b> G - 250mg Glass Jar    A - Ziplock Asbestos Bag    V-Vial # 2x BTEX, 1x HNO3, 1x amber glass			
Relinquished By: AD	Date: 08/05/23	Time: 10:30am	Received By:	Date:

**SAMPLE AND CHAIN OF CUSTODY FORM**

<b>TO:</b> ENVIROLAB SERVICES PTY LTD 12 ASHLEY STREET CHATSWOOD NSW 2067 P: (02) 99106200 F: (02) 99106201 Attention: Aileen	<b>JKE Job Number:</b> E35822PR <b>Date Results Required:</b> STANDARD <b>Page:</b> 2 of 2	<b>FROM:</b>  <b>JK Environments</b> REAR OF 115 WICKS ROAD MACQUARIE PARK, NSW 2113 P: 02-9888 5000 F: 02-9888 5001 Attention: Craig Ridley cridley@jkenvironments.com.au
---	--	---

<b>Location:</b>	Temora	<b>Sample Preserved In Esky on Ice</b>
<b>Sampler:</b>	AD	<b>Tests Required</b>

Date Sampled	Lab Ref:	Sample Number	Depth (m)	Sample Container	PID	Sample Description	Tests Required															
							Combo 1a	Combo 3a	Combo 6	Combo 6	Asbestos (NEDM)	Asbestos ID	TRH/BTEX	BTEX								
4/05/2023	27	TP9	0-0.1	G, A	0.6	F: Silty Clay	X															
4/05/2023	28	TP9	0.5-0.6	G, A	1.3	Silty Clay					X											
4/05/2023	29	TP9	0.9-1.0	G, A	2.4	Silty Clay																
4/05/2023	30	TP10	0-0.1	G, A	1	F: Silty Clay	X															
4/05/2023	31	TP10	0.4-0.5	G, A	0.5	Silty Clay					X											
4/05/2023	32	TP10	0.9-1.0	G, A	1.1	XW Andesite					X											
4/05/2023	33	TP11	0-0.1	G, A	0.3	F: Silty Clay	X															
4/05/2023	34	TP11	0.4-0.5	G, A	0.2	F: Silty Clay																
4/05/2023	35	TP11	0.9-1.0	G, A	0.4	F: Sandy Silty Clay	X															
4/05/2023	36	TP11	1.3-1.5	G, A	0.5	Silty Clay					X											
4/05/2023	37	TP12	0-0.1	G, A	0.2	Silty Clay	X															
4/05/2023	38	TP12	0.4-0.5	G, A	1.2	Silty Clay					X											
4/05/2023	39	TP12	0.9-1.0	G, A	0.5	XW Andesite																
4/05/2023	40	SDUP1	-	G	-	Soil Duplicate				X												
4/05/2023	41	SDUP2	-	G	-	Soil Duplicate					X											
4/05/2023	42	SDUP3	-	G	-	Soil Duplicate				X												
4/05/2023	43	SDUP4	-	G	-	Soil Duplicate					X											
2/05/2023	42	TB-S1	42	V	-	Trip Blank					X											
2/05/2023	43	TS-S1	43	V	-	Trip Spike															X	
3/05/2023	44	FR-SPT	44	#	-	Field Rinsate					X											
4/05/2023	45	BH4-FCF1	0-0.1 45	A	-	Fragment									X							
4/05/2023	46	BH4-FCF2	0-0.1 46	A	-	Fragment									X							
	47	TP3	0.4-0.5																			

Extra sample

EnviroLab Services  
 12 Ashley St  
 Chatswood NSW 2067  
 Ph: (02) 9910 6200

\*\* PLEASE SEND SDUP3 AND SDUP4 FOR INTER-LAB ANALYSIS

Date Received: 08/05/23  
 Time Received: 11:30  
 Received By: CF

Remarks (comments/detection limits required):	Sample Containers: G - 250mg Glass Jar A - Ziplock Asbestos Bag # 2x BTEX, 1x HNO3, 1x amber glass Temp: Cool/Ambient Cooling Ice/Leakpack Security: Intact/Broken/None
---	--

Relinquished By: AD	Date: 08/05/23	Time: 10:30am	Received By: ELS SYD Sarah P
			Date: 08/05/23



## CERTIFICATE OF ANALYSIS 322581-A

### Client Details

<b>Client</b>	JK Environments
<b>Attention</b>	C Ridley
<b>Address</b>	PO Box 976, North Ryde BC, NSW, 1670

### Sample Details

<b>Your Reference</b>	<b><u>E35822PR, Temora</u></b>
<b>Number of Samples</b>	additional analysis
<b>Date samples received</b>	08/05/2023
<b>Date completed instructions received</b>	17/05/2023

### Analysis Details

Please refer to the following pages for results, methodology summary and quality control data.  
 Samples were analysed as received from the client. Results relate specifically to the samples as received.  
 Results are reported on a dry weight basis for solids and on an as received basis for other matrices.

### Report Details

<b>Date results requested by</b>	24/05/2023
<b>Date of Issue</b>	24/05/2023
NATA Accreditation Number 2901. This document shall not be reproduced except in full.	
Accredited for compliance with ISO/IEC 17025 - Testing. <b>Tests not covered by NATA are denoted with *</b>	

#### Results Approved By

Kyle Gavrily, Senior Chemist  
 Loren Bardwell, Development Chemist

#### Authorised By

Nancy Zhang, Laboratory Manager

TCLP Preparation - Acid					
Our Reference		322581-A-8	322581-A-23	322581-A-30	322581-A-35
Your Reference	UNITS	BH3	BH8	TP14	TP15
Depth		0.3-0.5	0.02-0.2	0-0.1	0.9-1.0
Date Sampled		4/05/2023	05/05/2023	4/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil	Soil
pH of soil for fluid# determ.	pH units	8.3	8.3	8.2	8.2
pH of soil TCLP (after HCl)	pH units	1.8	1.8	1.8	1.8
Extraction fluid used		1	1	1	1
pH of final Leachate	pH units	5.0	5.0	5.0	5.0

PAHs in TCLP (USEPA 1311)				
Our Reference		322581-A-8	322581-A-23	322581-A-35
Your Reference	UNITS	BH3	BH8	TP15
Depth		0.3-0.5	0.02-0.2	0.9-1.0
Date Sampled		4/05/2023	05/05/2023	4/05/2023
Type of sample		Soil	Soil	Soil
Date extracted	-	24/05/2023	24/05/2023	24/05/2023
Date analysed	-	24/05/2023	24/05/2023	24/05/2023
Naphthalene in TCLP	mg/L	0.005	<0.001	<0.001
Acenaphthylene in TCLP	mg/L	<0.001	<0.001	<0.001
Acenaphthene in TCLP	mg/L	0.001	<0.001	<0.001
Fluorene in TCLP	mg/L	<0.001	<0.001	<0.001
Phenanthrene in TCLP	mg/L	0.002	<0.001	<0.001
Anthracene in TCLP	mg/L	<0.001	<0.001	<0.001
Fluoranthene in TCLP	mg/L	<0.001	<0.001	<0.001
Pyrene in TCLP	mg/L	<0.001	<0.001	<0.001
Benzo(a)anthracene in TCLP	mg/L	<0.001	<0.001	<0.001
Chrysene in TCLP	mg/L	<0.001	<0.001	<0.001
Benzo(b)k)fluoranthene in TCLP	mg/L	<0.002	<0.002	<0.002
Benzo(a)pyrene in TCLP	mg/L	<0.001	<0.001	<0.001
Indeno(1,2,3-c,d)pyrene - TCLP	mg/L	<0.001	<0.001	<0.001
Dibenzo(a,h)anthracene in TCLP	mg/L	<0.001	<0.001	<0.001
Benzo(g,h,i)perylene in TCLP	mg/L	<0.001	<0.001	<0.001
Total +ve PAH's	mg/L	0.0086	NIL (+)VE	NIL (+)VE
Surrogate p-Terphenyl-d14	%	84	79	80

Metals from Leaching Fluid pH 2.9 or 5		
Our Reference		322581-A-30
Your Reference	UNITS	TP14
Depth		0-0.1
Date Sampled		4/05/2023
Type of sample		Soil
Date extracted	-	24/05/2023
Date analysed	-	24/05/2023
Lead	mg/L	0.07

Method ID	Methodology Summary
<b>Inorg-004</b>	<p>Toxicity Characteristic Leaching Procedure (TCLP) using AS 4439 and USEPA 1311.</p> <p>Please note that the mass used may be scaled down from default based on sample mass available.</p> <p>Samples are stored at 2-6oC before and after leachate preparation.</p>
<b>Metals-020</b>	<p>Determination of various metals by ICP-AES following buffer determination as per USEPA 1311 and hence AS 4439.3. Extraction Fluid 1 refers to the pH 5.0 buffer and Extraction Fluid 2 is the pH 2.9 buffer.</p>
<b>Org-022/025</b>	<p>Leachates are extracted with Dichloromethane and analysed by GC-MS/GC-MSMS.</p>

Client Reference: E35822PR, Temora

QUALITY CONTROL: PAHs in TCLP (USEPA 1311)				Duplicate				Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-W1	[NT]
Date extracted	-			24/05/2023	[NT]	[NT]	[NT]	[NT]	24/05/2023	[NT]
Date analysed	-			24/05/2023	[NT]	[NT]	[NT]	[NT]	24/05/2023	[NT]
Naphthalene in TCLP	mg/L	0.001	Org-022/025	<0.001	[NT]	[NT]	[NT]	[NT]	75	[NT]
Acenaphthylene in TCLP	mg/L	0.001	Org-022/025	<0.001	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Acenaphthene in TCLP	mg/L	0.001	Org-022/025	<0.001	[NT]	[NT]	[NT]	[NT]	80	[NT]
Fluorene in TCLP	mg/L	0.001	Org-022/025	<0.001	[NT]	[NT]	[NT]	[NT]	84	[NT]
Phenanthrene in TCLP	mg/L	0.001	Org-022/025	<0.001	[NT]	[NT]	[NT]	[NT]	88	[NT]
Anthracene in TCLP	mg/L	0.001	Org-022/025	<0.001	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Fluoranthene in TCLP	mg/L	0.001	Org-022/025	<0.001	[NT]	[NT]	[NT]	[NT]	81	[NT]
Pyrene in TCLP	mg/L	0.001	Org-022/025	<0.001	[NT]	[NT]	[NT]	[NT]	86	[NT]
Benzo(a)anthracene in TCLP	mg/L	0.001	Org-022/025	<0.001	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Chrysene in TCLP	mg/L	0.001	Org-022/025	<0.001	[NT]	[NT]	[NT]	[NT]	66	[NT]
Benzo(b)k)fluoranthene in TCLP	mg/L	0.002	Org-022/025	<0.002	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Benzo(a)pyrene in TCLP	mg/L	0.001	Org-022/025	<0.001	[NT]	[NT]	[NT]	[NT]	104	[NT]
Indeno(1,2,3-c,d)pyrene - TCLP	mg/L	0.001	Org-022/025	<0.001	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Dibenzo(a,h)anthracene in TCLP	mg/L	0.001	Org-022/025	<0.001	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Benzo(g,h,i)perylene in TCLP	mg/L	0.001	Org-022/025	<0.001	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Surrogate p-Terphenyl-d14	%		Org-022/025	77	[NT]	[NT]	[NT]	[NT]	97	[NT]

Client Reference: E35822PR, Temora

QUALITY CONTROL: Metals from Leaching Fluid pH 2.9 or 5					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-W1	[NT]
Date extracted	-			24/05/2023	[NT]	[NT]	[NT]	[NT]	24/05/2023	[NT]
Date analysed	-			24/05/2023	[NT]	[NT]	[NT]	[NT]	24/05/2023	[NT]
Lead	mg/L	0.03	Metals-020	<0.03	[NT]	[NT]	[NT]	[NT]	96	[NT]

**Result Definitions**

<b>NT</b>	Not tested
<b>NA</b>	Test not required
<b>INS</b>	Insufficient sample for this test
<b>PQL</b>	Practical Quantitation Limit
<b>&lt;</b>	Less than
<b>&gt;</b>	Greater than
<b>RPD</b>	Relative Percent Difference
<b>LCS</b>	Laboratory Control Sample
<b>NS</b>	Not specified
<b>NEPM</b>	National Environmental Protection Measure
<b>NR</b>	Not Reported



## Quality Control Definitions

<b>Blank</b>	This is the component of the analytical signal which is not derived from the sample but from reagents, glassware etc, can be determined by processing solvents and reagents in exactly the same manner as for samples.
<b>Duplicate</b>	This is the complete duplicate analysis of a sample from the process batch. If possible, the sample selected should be one where the analyte concentration is easily measurable.
<b>Matrix Spike</b>	A portion of the sample is spiked with a known concentration of target analyte. The purpose of the matrix spike is to monitor the performance of the analytical method used and to determine whether matrix interferences exist.
<b>LCS (Laboratory Control Sample)</b>	This comprises either a standard reference material or a control matrix (such as a blank sand or water) fortified with analytes representative of the analyte class. It is simply a check sample.
<b>Surrogate Spike</b>	Surrogates are known additions to each sample, blank, matrix spike and LCS in a batch, of compounds which are similar to the analyte of interest, however are not expected to be found in real samples.
Australian Drinking Water Guidelines recommend that Thermotolerant Coliform, Faecal Enterococci, & E.Coli levels are less than 1cfu/100mL. The recommended maximums are taken from "Australian Drinking Water Guidelines", published by NHMRC & ARMC 2011.	
The recommended maximums for analytes in urine are taken from "2018 TLVs and BEIs", as published by ACGIH (where available). Limit provided for Nickel is a precautionary guideline as per Position Paper prepared by AIOH Exposure Standards Committee, 2016.	
Guideline limits for Rinse Water Quality reported as per analytical requirements and specifications of AS 4187, Amdt 2 2019, Table 7.2	

## Laboratory Acceptance Criteria

Duplicate sample and matrix spike recoveries may not be reported on smaller jobs, however, were analysed at a frequency to meet or exceed NEPM requirements. All samples are tested in batches of 20. The duplicate sample RPD and matrix spike recoveries for the batch were within the laboratory acceptance criteria.

Filters, swabs, wipes, tubes and badges will not have duplicate data as the whole sample is generally extracted during sample extraction.

Spikes for Physical and Aggregate Tests are not applicable.

For VOCs in water samples, three vials are required for duplicate or spike analysis.

Duplicates: >10xPQL - RPD acceptance criteria will vary depending on the analytes and the analytical techniques but is typically in the range 20%-50% – see ELN-P05 QA/QC tables for details; <10xPQL - RPD are higher as the results approach PQL and the estimated measurement uncertainty will statistically increase.

Matrix Spikes, LCS and Surrogate recoveries: Generally 70-130% for inorganics/metals (not SPOCAS); 60-140% for organics/SPOCAS (+/-50% surrogates) and 10-140% for labile SVOCs (including labile surrogates), ultra trace organics and speciated phenols is acceptable.

In circumstances where no duplicate and/or sample spike has been reported at 1 in 10 and/or 1 in 20 samples respectively, the sample volume submitted was insufficient in order to satisfy laboratory QA/QC protocols.

When samples are received where certain analytes are outside of recommended technical holding times (THTs), the analysis has proceeded. Where analytes are on the verge of breaching THTs, every effort will be made to analyse within the THT or as soon as practicable.

Where sampling dates are not provided, Envirolab are not in a position to comment on the validity of the analysis where recommended technical holding times may have been breached.

Where matrix spike recoveries fall below the lower limit of the acceptance criteria (e.g. for non-labile or standard Organics <60%), positive result(s) in the parent sample will subsequently have a higher than typical estimated uncertainty (MU estimates supplied on request) and in these circumstances the sample result is likely biased significantly low.

Measurement Uncertainty estimates are available for most tests upon request.

Analysis of aqueous samples typically involves the extraction/digestion and/or analysis of the liquid phase only (i.e. NOT any settled sediment phase but inclusive of suspended particles if present), unless stipulated on the Envirolab COC and/or by correspondence. Notable exceptions include certain Physical Tests (pH/EC/BOD/COD/Apparent Colour etc.), Solids testing, total recoverable metals and PFAS where solids are included by default.

Samples for Microbiological analysis (not Amoeba forms) received outside of the 2-8°C temperature range do not meet the ideal cooling conditions as stated in AS2031-2012.

## SAMPLE RECEIPT ADVICE

### Client Details

<b>Client</b>	JK Environments
<b>Attention</b>	C Ridley

### Sample Login Details

<b>Your reference</b>	E35822PR, Temora
<b>Envirolab Reference</b>	322581-A
<b>Date Sample Received</b>	08/05/2023
<b>Date Instructions Received</b>	17/05/2023
<b>Date Results Expected to be Reported</b>	24/05/2023

### Sample Condition

<b>Samples received in appropriate condition for analysis</b>	Yes
<b>No. of Samples Provided</b>	additional analysis
<b>Turnaround Time Requested</b>	Standard
<b>Temperature on Receipt (°C)</b>	8
<b>Cooling Method</b>	Ice
<b>Sampling Date Provided</b>	YES

### Comments

Nil

Please direct any queries to:

#### Aileen Hie

**Phone:** 02 9910 6200  
**Fax:** 02 9910 6201  
**Email:** ahie@envirolab.com.au

#### Jacinta Hurst

**Phone:** 02 9910 6200  
**Fax:** 02 9910 6201  
**Email:** jhurst@envirolab.com.au

*Analysis Underway, details on the following page:*



Sample ID	TCLP Preparation - Acid	Naphthalene in TCLP	Acenaphthylene in TCLP	Acenaphthene in TCLP	Fluorene in TCLP	Phenanthrene in TCLP	Anthracene in TCLP	Fluoranthene in TCLP	Pyrene in TCLP	Benzo(a)anthracene in TCLP	Chrysene in TCLP	Benzo(b)fluoranthene in TCLP	Benzo(a)pyrene in TCLP	Indeno(1,2,3-c,d)pyrene - TCLP	Dibenzo(a,h)anthracene in TCLP	Benzo(g,h,i)perylene in TCLP	Total +vePAH's	Surrogate p-Terphenyl-d14	Lead	On Hold	
BH1-0-0.3																				✓	
BH1-0.3-0.5																					✓
BH1-0.8-1.0																					✓
BH2-0-0.2																					✓
BH2-0.3-0.5																					✓
BH2-0.8-1.0																					✓
BH3-0-0.1																					✓
BH3-0.3-0.5	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓			
BH3-0.8-1.0																					✓
BH3-1.3-1.5																					✓
BH4-0-0.1																					✓
BH4-0.3-0.5																					✓
BH4-0.8-1.0																					✓
BH5-0-0.1																					✓
BH5-0.3-0.5																					✓
BH5-0.8-1.0																					✓
BH6-0.02-0.3																					✓
BH6-0.3-0.5																					✓
BH6-0.8-1.0																					✓
BH7-0-0.1																					✓



Sample ID	TCLP Preparation - Acid	Naphthalene in TCLP	Acenaphthylene in TCLP	Acenaphthene in TCLP	Fluorene in TCLP	Phenanthrene in TCLP	Anthracene in TCLP	Fluoranthene in TCLP	Pyrene in TCLP	Benzo(a)anthracene in TCLP	Chrysene in TCLP	Benzo(b)fluoranthene in TCLP	Benzo(a)pyrene in TCLP	Indeno(1,2,3-c,d)pyrene - TCLP	Dibenzo(a,h)anthracene in TCLP	Benzo(g,h,i)perylene in TCLP	Total +vePAH's	Surrogate p-Terphenyl-d14	Lead	On Hold	
BH7-0.3-0.5																				✓	
BH7-0.8-1.0																					✓
BH8-0.02-0.2	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓			
BH8-0.3-0.5																					✓
BH8-0.8-1.0																					✓
BH8-1.3-1.5																					✓
TP13-0-0.1																					✓
TP13-0.5-0.6																					✓
TP13-0.9-1.0																					✓
TP14-0-0.1	✓																		✓		
TP14-0.4-0.5																					✓
TP14-0.9-1.0																					✓
TP15-0-0.1																					✓
TP15-0.4-0.5																					✓
TP15-0.9-1.0	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓			
TP15-1.3-1.5																					✓
TP16-0-0.1																					✓
TP16-0.4-0.5																					✓
TP16-0.9-1.0																					✓
SDUP1																					✓



Sample ID	TCLP Preparation - Acid	Naphthalene in TCLP	Acenaphthylene in TCLP	Acenaphthene in TCLP	Fluorene in TCLP	Phenanthrene in TCLP	Anthracene in TCLP	Fluoranthene in TCLP	Pyrene in TCLP	Benzo(a)anthracene in TCLP	Chrysene in TCLP	Benzo(b)fluoranthene in TCLP	Benzo(a)pyrene in TCLP	Indeno(1,2,3-c,d)pyrene - TCLP	Dibenzo(a,h)anthracene in TCLP	Benzo(g,h,i)perylene in TCLP	Total +vePAH's	Surrogate p-Terphenyl-d14	Lead	On Hold		
SDUP2																					✓	
TB-S1																						✓
TS-S1																						✓
FR-SPT																						✓
BH4-FCF1																						✓
BH4-FCF2																						✓
TP3-0.4-0.5																						✓

The '✓' indicates the testing you have requested. **THIS IS NOT A REPORT OF THE RESULTS.**

### Additional Info

Sample storage - Waters are routinely disposed of approximately 1 month and soils approximately 2 months from receipt.

Requests for longer term sample storage must be received in writing.

Please contact the laboratory immediately if observed settled sediment present in water samples is to be included in the extraction and/or analysis (exceptions include certain Physical Tests (pH/EC/BOD/COD/Apparent Colour etc.), Solids testing, Total Recoverable metals and PFAS analysis where solids are included by default.

TAT for Micro is dependent on incubation. This varies from 3 to 6 days.

## Ming To

---

**From:** Craig Ridley <CRidley@jkenvironments.com.au>  
**Sent:** Wednesday, 17 May 2023 10:57 AM  
**To:** Nancy Zhang  
**Cc:** Samplereceipt  
**Subject:** RE: Results for Registration 322581 E35822PR, Temora  
**Categories:** Additional

Ref: 322581-A  
TAT: Standard  
Due: 24/05/2023  
M

**CAUTION:** This email originated from outside of the organisation. Do not act on instructions, click links or open attachments unless you recognise the sender and know the content is authentic and safe.

Hi Nancy, can we please arrange the following additional tests on standard turnaround:

Sample Number and Depth	Lab Reference	Test Required
BH3 (0.3-0.5) 8	322581-8	TCLP PAH
BH8 (0.02-0.3) 23	322581-23	TCLP PAH
TP14 (0-0.1) 30	322581-30	TCLP Lead
TP15 (0.9-1.0) 35	322581-35	TCLP PAH

Any issues, please call

Regards  
Craig Ridley  
Associate | Environmental Scientist



T: +612 9888 5000  
D: 0421 856 992  
E: [CRidley@jkenvironments.com.au](mailto:CRidley@jkenvironments.com.au)  
[www.jkenvironments.com.au](http://www.jkenvironments.com.au)

PO Box 976  
NORTH RYDE BC NSW 1670  
115 Wicks Road  
MACQUARIE PARK NSW 2113

## JK Environments

This email and any attachments are confidential and may be privileged in which case neither is intended to be waived. If you have received this message in error, please notify us and remove it from your system. It is your responsibility to check any attachments for viruses and defects before opening or sending them on. At the Company's discretion we may send a paper copy for confirmation. In the event of any discrepancy between paper and electronic versions the paper version is to take precedence.

**From:** Nancy Zhang <NZhang@envirolab.com.au>  
**Sent:** Monday, 15 May 2023 7:21 PM  
**To:** Craig Ridley <CRidley@jkenvironments.com.au>  
**Subject:** Results for Registration 322581 E35822PR, Temora

This message originated outside the JKG network. If this looks to be from a staff member, it is likely to be malicious (spam/phish attack). Do not click links or open attachments unless you recognise the sender and know the content is safe.

---

Please refer to attached for:  
a copy of the Certificate of Analysis  
a copy of the COC/paperwork received from you  
an Excel or .csv file containing the results

Please note that a hard copy will not be posted.

Enquiries should be made directly to:  
[customerservice@envirolab.com.au](mailto:customerservice@envirolab.com.au)

## CERTIFICATE OF ANALYSIS 37227

### Client Details

<b>Client</b>	JK Environments
<b>Attention</b>	Craig Ridley
<b>Address</b>	PO Box 976, North Ryde BC, NSW, 1670

### Sample Details

<b>Your Reference</b>	<u>E35822PR</u>
<b>Number of Samples</b>	2 Soil
<b>Date samples received</b>	10/05/2023
<b>Date completed instructions received</b>	10/05/2023

### Analysis Details

Please refer to the following pages for results, methodology summary and quality control data.  
 Samples were analysed as received from the client. Results relate specifically to the samples as received.  
 Results are reported on a dry weight basis for solids and on an as received basis for other matrices.

### Report Details

<b>Date results requested by</b>	16/05/2023
<b>Date of Issue</b>	15/05/2023

NATA Accreditation Number 2901. This document shall not be reproduced except in full.

Accredited for compliance with ISO/IEC 17025 - Testing. **Tests not covered by NATA are denoted with \***

#### Results Approved By

Chris De Luca, Assistant Lab Manager  
 Suk Lee, Organic Supervisor  
 Tianna Milburn, Chemist (FAS)

#### Authorised By

*P. Adams*

Pamela Adams, Laboratory Manager

vTRH(C6-C10)/BTEXN in Soil			
Our Reference		37227-1	37227-2
Your Reference	UNITS	SDUP3	SDUP4
Date Sampled		04/05/2023	04/05/2023
Type of sample		Soil	Soil
Date extracted	-	12/05/2023	12/05/2023
Date analysed	-	13/05/2023	13/05/2023
vTRH C <sub>6</sub> - C <sub>9</sub>	mg/kg	<25	<25
vTRH C <sub>6</sub> - C <sub>10</sub>	mg/kg	<25	<25
TRH C <sub>6</sub> - C <sub>10</sub> less BTEX (F1)	mg/kg	<25	<25
Benzene	mg/kg	<0.2	<0.2
Toluene	mg/kg	<0.5	<0.5
Ethylbenzene	mg/kg	<1	<1
m+p-xylene	mg/kg	<2	<2
o-Xylene	mg/kg	<1	<1
Naphthalene	mg/kg	<1	<1
Total BTEX	mg/kg	<1	<1
Total +ve Xylenes	mg/kg	<1	<1
Surrogate aaa-Trifluorotoluene	%	82	74



TRH Soil C10-C40 NEPM			
Our Reference		37227-1	37227-2
Your Reference	UNITS	SDUP3	SDUP4
Date Sampled		04/05/2023	04/05/2023
Type of sample		Soil	Soil
Date extracted	-	10/05/2023	10/05/2023
Date analysed	-	12/05/2023	12/05/2023
TRH C <sub>10</sub> - C <sub>14</sub>	mg/kg	<50	<50
TRH C <sub>15</sub> - C <sub>28</sub>	mg/kg	<100	<100
TRH C <sub>29</sub> - C <sub>36</sub>	mg/kg	<100	<100
Total +ve TRH (C10-C36)	mg/kg	<50	<50
TRH >C <sub>10</sub> -C <sub>16</sub>	mg/kg	<50	<50
TRH >C <sub>10</sub> - C <sub>16</sub> less Naphthalene (F2)	mg/kg	<50	<50
TRH >C <sub>16</sub> -C <sub>34</sub>	mg/kg	<100	<100
TRH >C <sub>34</sub> -C <sub>40</sub>	mg/kg	<100	<100
Total +ve TRH (>C10-C40)	mg/kg	<50	<50
Surrogate o-Terphenyl	%	82	82

PAHs in Soil			
Our Reference		37227-1	37227-2
Your Reference	UNITS	SDUP3	SDUP4
Date Sampled		04/05/2023	04/05/2023
Type of sample		Soil	Soil
Date extracted	-	10/05/2023	10/05/2023
Date analysed	-	12/05/2023	12/05/2023
Naphthalene	mg/kg	<0.1	<0.1
Acenaphthylene	mg/kg	<0.1	<0.1
Acenaphthene	mg/kg	<0.1	<0.1
Fluorene	mg/kg	<0.1	<0.1
Phenanthrene	mg/kg	0.1	<0.1
Anthracene	mg/kg	<0.1	<0.1
Fluoranthene	mg/kg	0.2	0.1
Pyrene	mg/kg	0.2	0.1
Benzo(a)anthracene	mg/kg	<0.1	<0.1
Chrysene	mg/kg	<0.1	<0.1
Benzo(b,j&k)fluoranthene	mg/kg	<0.2	<0.2
Benzo(a)pyrene	mg/kg	0.08	0.05
Indeno(1,2,3-c,d)pyrene	mg/kg	0.1	<0.1
Dibenzo(a,h)anthracene	mg/kg	<0.1	<0.1
Benzo(g,h,i)perylene	mg/kg	0.1	<0.1
Total +ve PAH's	mg/kg	0.86	0.3
Benzo(a)pyrene TEQ calc (Zero)	mg/kg	<0.5	<0.5
Benzo(a)pyrene TEQ calc (Half)	mg/kg	<0.5	<0.5
Benzo(a)pyrene TEQ calc (PQL)	mg/kg	<0.5	<0.5
Surrogate <i>p</i> -Terphenyl-d <sub>14</sub>	%	76	84

OCP in Soil		
Our Reference		37227-1
Your Reference	UNITS	SDUP3
Date Sampled		04/05/2023
Type of sample		Soil
Date extracted	-	10/05/2023
Date analysed	-	12/05/2023
alpha-BHC	mg/kg	<0.1
Hexachlorobenzene	mg/kg	<0.1
beta-BHC	mg/kg	<0.1
gamma-BHC	mg/kg	<0.1
Heptachlor	mg/kg	<0.1
delta-BHC	mg/kg	<0.1
Aldrin	mg/kg	<0.1
Heptachlor Epoxide	mg/kg	<0.1
gamma-Chlordane	mg/kg	<0.1
alpha-chlordane	mg/kg	<0.1
Endosulfan I	mg/kg	<0.1
pp-DDE	mg/kg	<0.1
Dieldrin	mg/kg	<0.1
Endrin	mg/kg	<0.1
Endosulfan II	mg/kg	<0.1
pp-DDD	mg/kg	<0.1
Endrin Aldehyde	mg/kg	<0.1
pp-DDT	mg/kg	<0.1
Endosulfan Sulphate	mg/kg	<0.1
Methoxychlor	mg/kg	<0.1
Total +ve reported Aldrin + Dieldrin	mg/kg	<0.1
Total +ve reported DDT+DDD+DDE	mg/kg	<0.1
Surrogate 2-chlorophenol-d4	%	80

OP in Soil		
Our Reference		37227-1
Your Reference	UNITS	SDUP3
Date Sampled		04/05/2023
Type of sample		Soil
Date extracted	-	10/05/2023
Date analysed	-	12/05/2023
Azinphos-methyl	mg/kg	<0.1
Bromophos-ethyl	mg/kg	<0.1
Chlorpyrifos	mg/kg	<0.1
Chlorpyrifos-methyl	mg/kg	<0.1
Diazinon	mg/kg	<0.1
Dichlorovos	mg/kg	<0.1
Dimethoate	mg/kg	<0.1
Ethion	mg/kg	<0.1
Fenitrothion	mg/kg	<0.1
Malathion	mg/kg	<0.1
Parathion	mg/kg	<0.1
Ronnel	mg/kg	<0.1
Surrogate 2-chlorophenol-d4	%	80

PCBs in Soil		
Our Reference		37227-1
Your Reference	UNITS	SDUP3
Date Sampled		04/05/2023
Type of sample		Soil
Date extracted	-	10/05/2023
Date analysed	-	12/05/2023
Aroclor 1016	mg/kg	<0.1
Aroclor 1221	mg/kg	<0.1
Aroclor 1232	mg/kg	<0.1
Aroclor 1242	mg/kg	<0.1
Aroclor 1248	mg/kg	<0.1
Aroclor 1254	mg/kg	<0.1
Aroclor 1260	mg/kg	<0.1
Total +ve PCBs (1016-1260)	mg/kg	<0.1
Surrogate 2-fluorobiphenyl	%	82

Acid Extractable metals in soil			
Our Reference		37227-1	37227-2
Your Reference	UNITS	SDUP3	SDUP4
Date Sampled		04/05/2023	04/05/2023
Type of sample		Soil	Soil
Date digested	-	11/05/2023	11/05/2023
Date analysed	-	12/05/2023	12/05/2023
Arsenic	mg/kg	11	5
Cadmium	mg/kg	<0.4	<0.4
Chromium	mg/kg	22	16
Copper	mg/kg	130	160
Lead	mg/kg	170	24
Mercury	mg/kg	<0.1	<0.1
Nickel	mg/kg	6	7
Zinc	mg/kg	140	67

Moisture			
Our Reference		37227-1	37227-2
Your Reference	UNITS	SDUP3	SDUP4
Date Sampled		04/05/2023	04/05/2023
Type of sample		Soil	Soil
Date prepared	-	10/05/2023	10/05/2023
Date analysed	-	11/05/2023	11/05/2023
Moisture	%	9.1	24

Method ID	Methodology Summary
<b>Inorg-008</b>	Moisture content determined by heating at 105°C for a minimum of 12 hours.
<b>Metals-020 ICP-AES</b>	Determination of various metals by ICP-AES.
<b>Metals-021 CV-AAS</b>	Determination of Mercury by Cold Vapour AAS.
<b>Org-020</b>	Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-FID.  F2 = (>C10-C16)-Naphthalene as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater (HSLs Tables 1A (3, 4)). Note Naphthalene is determined from the VOC analysis.  Note, the Total +ve TRH PQL is reflective of the lowest individual PQL and is therefore "Total +ve TRH" is simply a sum of the positive individual TRH fractions (>C10-C40).
<b>Org-021/022</b>	Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC-ECD or GC-MS. Note, the Total +ve PCBs PQL is reflective of the lowest individual PQL and is therefore "Total +ve PCBs" is simply a sum of the positive individual PCBs.
<b>Org-022</b>	Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS.
<b>Org-022/025</b>	Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS/GC-MSMS.
<b>Org-022/025</b>	Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS/GC-MSMS.  Note, For OCs the Total +ve reported DDD+DDE+DDT PQL is reflective of the lowest individual PQL and is therefore simply a sum of the positive individually report DDD+DDE+DDT.



Method ID	Methodology Summary
<p><b>Org-022/025</b></p>	<p>Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS/GC-MSMS. Benzo(a)pyrene TEQ as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater - 2013.</p> <p>For soil results:-</p> <ol style="list-style-type: none"> <li>1. 'EQ PQL' values are assuming all contributing PAHs reported as &lt;PQL are actually at the PQL. This is the most conservative approach and can give false positive TEQs given that PAHs that contribute to the TEQ calculation may not be present.</li> <li>2. 'EQ zero' values are assuming all contributing PAHs reported as &lt;PQL are zero. This is the least conservative approach and is more susceptible to false negative TEQs when PAHs that contribute to the TEQ calculation are present but below PQL.</li> <li>3. 'EQ half PQL' values are assuming all contributing PAHs reported as &lt;PQL are half the stipulated PQL. Hence a mid-point between the most and least conservative approaches above.</li> </ol> <p>Note, the Total +ve PAHs PQL is reflective of the lowest individual PQL and is therefore "Total +ve PAHs" is simply a sum of the positive individual PAHs.</p>
<p><b>Org-023</b></p>	<p>Soil samples are extracted with methanol and spiked into water prior to analysing by purge and trap GC-MS.</p>
<p><b>Org-023</b></p>	<p>Soil samples are extracted with methanol and spiked into water prior to analysing by purge and trap GC-MS. Water samples are analysed directly by purge and trap GC-MS. F1 = (C6-C10)-BTEX as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater.</p> <p>Note, the Total +ve Xylene PQL is reflective of the lowest individual PQL and is therefore "Total +ve Xylenes" is simply a sum of the positive individual Xylenes.</p>

QUALITY CONTROL: vTRH(C6-C10)/BTEXN in Soil					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-1	[NT]
Date extracted	-			12/05/2023	[NT]	[NT]	[NT]	[NT]	12/05/2023	[NT]
Date analysed	-			13/05/2023	[NT]	[NT]	[NT]	[NT]	13/05/2023	[NT]
vTRH C <sub>6</sub> - C <sub>9</sub>	mg/kg	25	Org-023	<25	[NT]	[NT]	[NT]	[NT]	98	[NT]
vTRH C <sub>6</sub> - C <sub>10</sub>	mg/kg	25	Org-023	<25	[NT]	[NT]	[NT]	[NT]	98	[NT]
Benzene	mg/kg	0.2	Org-023	<0.2	[NT]	[NT]	[NT]	[NT]	93	[NT]
Toluene	mg/kg	0.5	Org-023	<0.5	[NT]	[NT]	[NT]	[NT]	96	[NT]
Ethylbenzene	mg/kg	1	Org-023	<1	[NT]	[NT]	[NT]	[NT]	97	[NT]
m+p-xylene	mg/kg	2	Org-023	<2	[NT]	[NT]	[NT]	[NT]	101	[NT]
o-Xylene	mg/kg	1	Org-023	<1	[NT]	[NT]	[NT]	[NT]	95	[NT]
Naphthalene	mg/kg	1	Org-023	<1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Surrogate aaa-Trifluorotoluene	%		Org-023	90	[NT]	[NT]	[NT]	[NT]	87	[NT]

QUALITY CONTROL: TRH Soil C10-C40 NEPM					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-1	[NT]
Date extracted	-			10/05/2023	[NT]	[NT]	[NT]	[NT]	10/05/2023	[NT]
Date analysed	-			11/05/2023	[NT]	[NT]	[NT]	[NT]	11/05/2023	[NT]
TRH C <sub>10</sub> - C <sub>14</sub>	mg/kg	50	Org-020	<50	[NT]	[NT]	[NT]	[NT]	88	[NT]
TRH C <sub>15</sub> - C <sub>28</sub>	mg/kg	100	Org-020	<100	[NT]	[NT]	[NT]	[NT]	95	[NT]
TRH C <sub>29</sub> - C <sub>36</sub>	mg/kg	100	Org-020	<100	[NT]	[NT]	[NT]	[NT]	107	[NT]
TRH >C <sub>10</sub> -C <sub>16</sub>	mg/kg	50	Org-020	<50	[NT]	[NT]	[NT]	[NT]	88	[NT]
TRH >C <sub>16</sub> -C <sub>34</sub>	mg/kg	100	Org-020	<100	[NT]	[NT]	[NT]	[NT]	95	[NT]
TRH >C <sub>34</sub> -C <sub>40</sub>	mg/kg	100	Org-020	<100	[NT]	[NT]	[NT]	[NT]	107	[NT]
Surrogate o-Terphenyl	%		Org-020	78	[NT]	[NT]	[NT]	[NT]	74	[NT]

QUALITY CONTROL: PAHs in Soil				Duplicate				Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-1	[NT]
Date extracted	-			10/05/2023	[NT]	[NT]	[NT]	[NT]	10/05/2023	[NT]
Date analysed	-			12/05/2023	[NT]	[NT]	[NT]	[NT]	12/05/2023	[NT]
Naphthalene	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	110	[NT]
Acenaphthylene	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Acenaphthene	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	112	[NT]
Fluorene	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	100	[NT]
Phenanthrene	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	110	[NT]
Anthracene	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Fluoranthene	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	122	[NT]
Pyrene	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	124	[NT]
Benzo(a)anthracene	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Chrysene	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	108	[NT]
Benzo(b,j&k)fluoranthene	mg/kg	0.2	Org-022/025	<0.2	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Benzo(a)pyrene	mg/kg	0.05	Org-022/025	<0.05	[NT]	[NT]	[NT]	[NT]	100	[NT]
Indeno(1,2,3-c,d)pyrene	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Dibenzo(a,h)anthracene	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Benzo(g,h,i)perylene	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Surrogate p-Terphenyl-d <sub>14</sub>	%		Org-022/025	88	[NT]	[NT]	[NT]	[NT]	94	[NT]

Client Reference: E35822PR

QUALITY CONTROL: OCP in Soil				Duplicate				Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-1	[NT]
Date extracted	-			10/05/2023	[NT]	[NT]	[NT]	[NT]	10/05/2023	[NT]
Date analysed	-			12/05/2023	[NT]	[NT]	[NT]	[NT]	12/05/2023	[NT]
alpha-BHC	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	90	[NT]
Hexachlorobenzene	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
beta-BHC	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	84	[NT]
gamma-BHC	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Heptachlor	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	104	[NT]
delta-BHC	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Aldrin	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	140	[NT]
Heptachlor Epoxide	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	98	[NT]
gamma-Chlordane	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	96	[NT]
alpha-chlordane	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Endosulfan I	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
pp-DDE	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	110	[NT]
Dieldrin	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	100	[NT]
Endrin	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Endosulfan II	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
pp-DDD	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	138	[NT]
Endrin Aldehyde	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
pp-DDT	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Endosulfan Sulphate	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	84	[NT]
Methoxychlor	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Surrogate 2-chlorophenol-d4	%		Org-022/025	84	[NT]	[NT]	[NT]	[NT]	88	[NT]

Client Reference: E35822PR

QUALITY CONTROL: OP in Soil				Duplicate				Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-1	[NT]
Date extracted	-			10/05/2023	[NT]	[NT]	[NT]	[NT]	10/05/2023	[NT]
Date analysed	-			12/05/2023	[NT]	[NT]	[NT]	[NT]	12/05/2023	[NT]
Azinphos-methyl	mg/kg	0.1	Org-022	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Bromophos-ethyl	mg/kg	0.1	Org-022	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Chlorpyrifos	mg/kg	0.1	Org-022	<0.1	[NT]	[NT]	[NT]	[NT]	96	[NT]
Chlorpyrifos-methyl	mg/kg	0.1	Org-022	<0.1	[NT]	[NT]	[NT]	[NT]	92	[NT]
Diazinon	mg/kg	0.1	Org-022	<0.1	[NT]	[NT]	[NT]	[NT]	94	[NT]
Dichlorovos	mg/kg	0.1	Org-022	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Dimethoate	mg/kg	0.1	Org-022	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Ethion	mg/kg	0.1	Org-022	<0.1	[NT]	[NT]	[NT]	[NT]	102	[NT]
Fenitrothion	mg/kg	0.1	Org-022	<0.1	[NT]	[NT]	[NT]	[NT]	92	[NT]
Malathion	mg/kg	0.1	Org-022	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Parathion	mg/kg	0.1	Org-022	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Ronnel	mg/kg	0.1	Org-022	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Surrogate 2-chlorophenol-d4	%		Org-022/025	84	[NT]	[NT]	[NT]	[NT]	88	[NT]

Client Reference: E35822PR

QUALITY CONTROL: PCBs in Soil					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-1	[NT]
Date extracted	-			10/05/2023	[NT]	[NT]	[NT]	[NT]	10/05/2023	[NT]
Date analysed	-			12/05/2023	[NT]	[NT]	[NT]	[NT]	12/05/2023	[NT]
Aroclor 1016	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Aroclor 1221	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Aroclor 1232	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Aroclor 1242	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Aroclor 1248	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Aroclor 1254	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	116	[NT]
Aroclor 1260	mg/kg	0.1	Org-022/025	<0.1	[NT]	[NT]	[NT]	[NT]	[NT]	[NT]
Surrogate 2-fluorobiphenyl	%		Org-022/025	88	[NT]	[NT]	[NT]	[NT]	94	[NT]

Client Reference: E35822PR

QUALITY CONTROL: Acid Extractable metals in soil						Duplicate		Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-1	[NT]
Date digested	-			11/05/2023	2	11/05/2023	11/05/2023		11/05/2023	[NT]
Date analysed	-			12/05/2023	2	12/05/2023	12/05/2023		12/05/2023	[NT]
Arsenic	mg/kg	4	Metals-020 ICP-AES	<4	2	5	5	0	103	[NT]
Cadmium	mg/kg	0.4	Metals-020 ICP-AES	<0.4	2	<0.4	<0.4	0	100	[NT]
Chromium	mg/kg	1	Metals-020 ICP-AES	<1	2	16	15	6	99	[NT]
Copper	mg/kg	1	Metals-020 ICP-AES	<1	2	160	170	6	99	[NT]
Lead	mg/kg	1	Metals-020 ICP-AES	<1	2	24	19	23	100	[NT]
Mercury	mg/kg	0.1	Metals-021 CV-AAS	<0.1	2	<0.1	<0.1	0	86	[NT]
Nickel	mg/kg	1	Metals-020 ICP-AES	<1	2	7	7	0	99	[NT]
Zinc	mg/kg	1	Metals-020 ICP-AES	<1	2	67	60	11	100	[NT]



**Result Definitions**

<b>NT</b>	Not tested
<b>NA</b>	Test not required
<b>INS</b>	Insufficient sample for this test
<b>PQL</b>	Practical Quantitation Limit
<b>&lt;</b>	Less than
<b>&gt;</b>	Greater than
<b>RPD</b>	Relative Percent Difference
<b>LCS</b>	Laboratory Control Sample
<b>NS</b>	Not specified
<b>NEPM</b>	National Environmental Protection Measure
<b>NR</b>	Not Reported

## Quality Control Definitions

<b>Blank</b>	This is the component of the analytical signal which is not derived from the sample but from reagents, glassware etc, can be determined by processing solvents and reagents in exactly the same manner as for samples.
<b>Duplicate</b>	This is the complete duplicate analysis of a sample from the process batch. If possible, the sample selected should be one where the analyte concentration is easily measurable.
<b>Matrix Spike</b>	A portion of the sample is spiked with a known concentration of target analyte. The purpose of the matrix spike is to monitor the performance of the analytical method used and to determine whether matrix interferences exist.
<b>LCS (Laboratory Control Sample)</b>	This comprises either a standard reference material or a control matrix (such as a blank sand or water) fortified with analytes representative of the analyte class. It is simply a check sample.
<b>Surrogate Spike</b>	Surrogates are known additions to each sample, blank, matrix spike and LCS in a batch, of compounds which are similar to the analyte of interest, however are not expected to be found in real samples.
Australian Drinking Water Guidelines recommend that Thermotolerant Coliform, Faecal Enterococci, & E.Coli levels are less than 1cfu/100mL. The recommended maximums are taken from "Australian Drinking Water Guidelines", published by NHMRC & ARMC 2011.	
The recommended maximums for analytes in urine are taken from "2018 TLVs and BEIs", as published by ACGIH (where available). Limit provided for Nickel is a precautionary guideline as per Position Paper prepared by AIOH Exposure Standards Committee, 2016.	
Guideline limits for Rinse Water Quality reported as per analytical requirements and specifications of AS 4187, Amdt 2 2019, Table 7.2	

## Laboratory Acceptance Criteria

Duplicate sample and matrix spike recoveries may not be reported on smaller jobs, however, were analysed at a frequency to meet or exceed NEPM requirements. All samples are tested in batches of 20. The duplicate sample RPD and matrix spike recoveries for the batch were within the laboratory acceptance criteria.

Filters, swabs, wipes, tubes and badges will not have duplicate data as the whole sample is generally extracted during sample extraction.

Spikes for Physical and Aggregate Tests are not applicable.

For VOCs in water samples, three vials are required for duplicate or spike analysis.

Duplicates: >10xPQL - RPD acceptance criteria will vary depending on the analytes and the analytical techniques but is typically in the range 20%-50% – see ELN-P05 QA/QC tables for details; <10xPQL - RPD are higher as the results approach PQL and the estimated measurement uncertainty will statistically increase.

Matrix Spikes, LCS and Surrogate recoveries: Generally 70-130% for inorganics/metals (not SPOCAS); 60-140% for organics/SPOCAS (+/-50% surrogates) and 10-140% for labile SVOCs (including labile surrogates), ultra trace organics and speciated phenols is acceptable.

In circumstances where no duplicate and/or sample spike has been reported at 1 in 10 and/or 1 in 20 samples respectively, the sample volume submitted was insufficient in order to satisfy laboratory QA/QC protocols.

When samples are received where certain analytes are outside of recommended technical holding times (THTs), the analysis has proceeded. Where analytes are on the verge of breaching THTs, every effort will be made to analyse within the THT or as soon as practicable.

Where sampling dates are not provided, Envirolab are not in a position to comment on the validity of the analysis where recommended technical holding times may have been breached.

Where matrix spike recoveries fall below the lower limit of the acceptance criteria (e.g. for non-labile or standard Organics <60%), positive result(s) in the parent sample will subsequently have a higher than typical estimated uncertainty (MU estimates supplied on request) and in these circumstances the sample result is likely biased significantly low.

Measurement Uncertainty estimates are available for most tests upon request.

Analysis of aqueous samples typically involves the extraction/digestion and/or analysis of the liquid phase only (i.e. NOT any settled sediment phase but inclusive of suspended particles if present), unless stipulated on the Envirolab COC and/or by correspondence. Notable exceptions include certain Physical Tests (pH/EC/BOD/COD/Apparent Colour etc.), Solids testing, total recoverable metals and PFAS where solids are included by default.

Samples for Microbiological analysis (not Amoeba forms) received outside of the 2-8°C temperature range do not meet the ideal cooling conditions as stated in AS2031-2012.

## SAMPLE RECEIPT ADVICE

### Client Details

<b>Client</b>	JK Environments
<b>Attention</b>	Craig Ridley

### Sample Login Details

<b>Your reference</b>	E35822PR
<b>Envirolab Reference</b>	37227
<b>Date Sample Received</b>	10/05/2023
<b>Date Instructions Received</b>	10/05/2023
<b>Date Results Expected to be Reported</b>	16/05/2023

### Sample Condition

<b>Samples received in appropriate condition for analysis</b>	Yes
<b>No. of Samples Provided</b>	2 Soil
<b>Turnaround Time Requested</b>	Standard
<b>Temperature on Receipt (°C)</b>	11.1
<b>Cooling Method</b>	Ice Pack
<b>Sampling Date Provided</b>	YES

### Comments

Nil

Please direct any queries to:

#### Pamela Adams

**Phone: 03 9763 2500**

**Fax: 03 9763 2633**

**Email: padams@envirolab.com.au**

#### Chris De Luca

**Phone: 03 9763 2500**

**Fax: 03 9763 2633**

**Email: cdeluca@envirolab.com.au**

*Analysis Underway, details on the following page:*



**Envirolab Services Pty Ltd**  
 ABN 37 112 535 645 - 002  
 25 Research Drive Croydon South VIC 3136  
 ph 03 9763 2500 fax 03 9763 2633  
 melbourne@envirolab.com.au  
 www.envirolab.com.au

Sample ID	VTRH(C6-C10)/BTEXN in Soil	TRH Soil C10-C40 NEPM	PAHs in Soil	OCP in Soil	OP in Soil	PCBs in Soil	Acid Extractable metals in soil
SDUP3	✓	✓	✓	✓	✓	✓	✓
SDUP4	✓	✓	✓				✓

The '✓' indicates the testing you have requested. **THIS IS NOT A REPORT OF THE RESULTS.**

### Additional Info

Sample storage - Waters are routinely disposed of approximately 1 month and soils approximately 2 months from receipt.

Requests for longer term sample storage must be received in writing.

Please contact the laboratory immediately if observed settled sediment present in water samples is to be included in the extraction and/or analysis (exceptions include certain Physical Tests (pH/EC/BOD/COD/Apparent Colour etc.), Solids testing, Total Recoverable metals and PFAS analysis where solids are included by default.

**SAMPLE AND CHAIN OF CUSTODY FORM**

<b>TO:</b> ENVIROLAB SERVICES PTY LTD 12 ASHLEY STREET CHATSWOOD NSW 2067 P: (02) 99106200 F: (02) 99106201 Attention: Aileen	<b>JKE Job Number:</b> E35822PR <b>Date Results Required:</b> STANDARD <b>Page:</b> 2 of 2	<b>FROM:</b>  REAR OF 115 WICKS ROAD MACQUARIE PARK, NSW 2113 P: 02-9888 5000 F: 02-9888 5001 Attention: Craig Ridley cridley@ikenvironments.com.au
---	--	---

<b>Location:</b> Temora	Sample Preserved in Esky on Ice
<b>Sampler:</b> AD	Tests Required

Date Sampled	Lab Ref:	Sample Number	Depth (m)	Sample Container	PID	Sample Description	Combo 1a	Combo 3a	Combo 6	Combo 3	Asbestos (NEMM)	Asbestos ID	TRH/BTEX	BTEX
4/05/2023	27	TP9	0-0.1	G, A	0.6	F: Silty Clay	X							
4/05/2023	28	TP9	0.5-0.6	G, A	1.3	Silty Clay				X				
4/05/2023	29	TP9	0.9-1.0	G, A	2.4	Silty Clay								
4/05/2023	30	TP10	0-0.1	G, A	1	F: Silty Clay	X							
4/05/2023	31	TP10	0.4-0.5	G, A	0.5	Silty Clay				X				
4/05/2023	32	TP10	0.9-1.0	G, A	1.1	XW Andesite				X				
4/05/2023	33	TP11	0-0.1	G, A	0.5	F: Silty Clay	X							
4/05/2023	34	TP11	0.4-0.5	G, A	0.2	F: Silty Clay								
4/05/2023	35	TP11	0.9-1.0	G, A	0.4	F: Sandy Silty Clay	X							
4/05/2023	36	TP11	1.3-1.5	G, A	0.5	Silty Clay				X				
4/05/2023	37	TP12	0-0.1	G, A	0.2	Silty Clay	X							
4/05/2023	38	TP12	0.4-0.5	G, A	1.2	Silty Clay				X				
4/05/2023	39	TP12	0.9-1.0	G, A	0.5	XW Andesite								
4/05/2023	40	SDUP1	-	G	-	Soil Duplicate			X					
4/05/2023	41	SDUP2	-	G	-	Soil Duplicate				X				
4/05/2023	42	SDUP3	-	G	-	Soil Duplicate			X					
4/05/2023	43	SDUP4	-	G	-	Soil Duplicate				X				
2/05/2023	42	TB-S1	42	V	-	Trip Blank				X				
2/05/2023	43	TS-S1	43	V	-	Trip Spike								X
3/05/2023	44	FR-SPT	44	#	-	Field Rinse				X				
4/05/2023	45	BH4-FCF1	0-0.1 45	A	-	Fragment					X			
4/05/2023	46	BH4-FCF2	0-0.1 46	A	-	Fragment					X			
4/05/2023	47	TP3	0.4-0.5											

EnviroLab Services  
 25 Research Drive  
 Crowdon South VIC 3136  
 Ph: (03) 9763 2500  
 Job No: 37227  
 Date Received: 08/05/23  
 Time Received: 17:20  
 Received By: AS  
 Temp: Cool/Ambient  
 Cooling: Ice/Lepack  
 Security: Intact/Broken/None

EnviroLab Servc  
 12 Ashley  
 Chatswood NSW 20  
 Ph: (02) 9910 621  
 Job No: 32258

\*\* PLEASE SEND SDUP3 AND SDUP4 FOR INTER-LAB ANALYSIS

Date Received: 08/05/23  
 Time Received: 17:20  
 Received By: AS

<b>Remarks (comments/detection limits required):</b>	<b>Sample Containers:</b> G - 250mg Glass Jar A - Ziplock Asbestos Bag # 2x BTEX, 1x HNO3, 1x amber glass
	<b>Temp:</b> Cool/Ambient <b>Cooling:</b> Ice/Lepack <b>Security:</b> Intact/Broken/None

<b>Relinquished By:</b> AD Sherry SD	<b>Date:</b> 08/05/23 9/5/23	<b>Time:</b> 10:30AM	<b>Received By:</b> ELSYD Sarah P
			<b>Date:</b> 08/05/23

Extra 2 samples

**SAMPLE AND CHAIN OF CUSTODY FORM**

<b>TO:</b> ENVIROLAB SERVICES PTY LTD 12 ASHLEY STREET CHATSWOOD NSW 2067 P: (02) 99106200 F: (02) 99106201  Attention: Aileen	<b>JKE Job Number:</b> E35822PR  <b>Date Results Required:</b> STANDARD  Page: 1 of 2	<b>FROM:</b>  <b>JKE Environments</b> REAR OF 115 WICKS ROAD MACQUARIE PARK, NSW 2113 P: 02-9888 5000 F: 02-9888 5001 Attention: Craig Ridley cridley@jkenvironments.com.au
---	---	--

Location:	Temora	Sample Preserved in Esky on Ice
-----------	--------	---------------------------------

Date Sampled	Lab Ref:	Sample Number	Depth (m)	Sample Container	PID	Sample Description	Tests Required												
							Combo 6an	Combo 6an	Combo 6	Combo 3	Asbestos (NEPM)	Asbestos ID	TRH/BTEX	BTEX					
4/05/2023	1	BH1	0-0.3	G, A	0.5	Silty Clay	X												
4/05/2023	2	BH1	0.3-0.5	G, A	0.4	Silty Clay													
4/05/2023	3	BH1	0.8-1.0	G, A	0.5	XW Andesite					X								
3/05/2023	4	BH2	0-0.2	G, A	1.3	F: Gravelly Sandy Clay	X												
3/05/2023	5	BH2	0.3-0.5	G, A	1.3	Sandy Silty Clay					X								
3/05/2023	6	BH2	0.8-1.0	G, A	1.8	Silty Clay					X								
4/05/2023	7	BH3	0-0.2	G, A	0.6	F: Silty Clay	X												
4/05/2023	8	BH3	0.3-0.5	G, A	0.7	F: Sandy Silty Clay	X												
4/05/2023	9	BH3	0.8-1.0	G, A	0.6	F: Sandy Silty Clay													
4/05/2023	10	BH3	1.3-1.5	G, A	1.5	Sandy Silty Clay					X								
4/05/2023	11	BH4	0-0.1	G, A	2.2	F: Silty Clay	X												
4/05/2023	12	BH4	0.3-0.5	G, A	2	Sandy Silty Clay					X								
4/05/2023	13	BH4	0.8-1.0	G, A	3.8	XW Andesite					X								
3/05/2023	14	BH5	0-0.1	G, A	0.6	Silty Clay	X												
3/05/2023	15	BH3	0.3-0.5	G, A	0.5	Silty Clay													
3/05/2023	16	BH5	0.8-1.0	G, A	0.6	Silty Clay					X								
2/05/2023	17	BH6	0-0.1	G, A	0.4	F: Silty Clay	X												
2/05/2023	18	BH6	0.3-0.5	G	0.1	Sandy Silty Clay					X								
2/05/2023	19	BH6	0.8-1.0	G	0.1	XW Andesite					X								
2/05/2023	20	BH7	0-0.1	G, A	0.8	F: Gravelly Silty Sand	X												
2/05/2023	21	BH7	0.3-0.5	G, A	2	Sandy Silt					X								
2/05/2023	22	BH7	0.8-1.0	G	0	XW Andesite													
5/05/2023	23	BH8	0.02-0.2	G, A	0	F: Silty Sand	X												
5/05/2023	24	BH8	0.3-0.5	G, A	0.3	Sandy Silty Clay					X								
5/05/2023	25	BH6	0.8-1.0	G, A	0.4	Sandy Silty Clay													
5/05/2023	26	BH8	1.3-1.5	G, A	0.3	Sandy Silty Clay													

Remarks (comments/detection limits required):	Sample Containers: G - 250mg Glass Jar A - Ziplock Asbestos Bag P - Plastic Bag	Received By: SP Temp: Cool/Ambient Cooling: Ice/Icepack Security: Intact/Broken/None
---	--	---

Relinquished By: AD Sherry SO	Date: 08/05/23 9/5/23	Time: 10:30am	Received By: ELS SYD Sarah P	Date: 08/05/23
-------------------------------	-----------------------	---------------	------------------------------	----------------

**Envirolab Services**  
 12 Ashley St  
 Chatswood NSW 2067  
 Ph: (02) 9910 6200  
 Job No: 322581  
 Date Received: 08/05/23  
 Time Received: 11:30

## CERTIFICATE OF ANALYSIS 37227-A

### Client Details

<b>Client</b>	JK Environments
<b>Attention</b>	Craig Ridley
<b>Address</b>	PO Box 976, North Ryde BC, NSW, 1670

### Sample Details

<b>Your Reference</b>	<u>E35822PR</u>
<b>Number of Samples</b>	2 Soil
<b>Date samples received</b>	10/05/2023
<b>Date completed instructions received</b>	17/05/2023

### Analysis Details

Please refer to the following pages for results, methodology summary and quality control data.  
 Samples were analysed as received from the client. Results relate specifically to the samples as received.  
 Results are reported on a dry weight basis for solids and on an as received basis for other matrices.

### Report Details

<b>Date results requested by</b>	24/05/2023
<b>Date of Issue</b>	18/05/2023
NATA Accreditation Number 2901. This document shall not be reproduced except in full.	
Accredited for compliance with ISO/IEC 17025 - Testing. <b>Tests not covered by NATA are denoted with *</b>	

**Results Approved By**  
 Tara White, Metals Team Leader

**Authorised By**  
 Pamela Adams, Laboratory Manager

Metals from Leachate determ. pH 2.9 or 5		
Our Reference		37227-A-1
Your Reference	UNITS	SDUP3
Date Sampled		04/05/2023
Type of sample		Soil
Date extracted	-	17/05/2023
Date analysed	-	18/05/2023
pH of soil for ASLP	pH units	6.8
pH of soil ASLP (after HCl)	pH units	2.1
Extraction fluid used	-	1
pH of final Leachate	pH units	5.1
Lead	mg/L	0.3



Method ID	Methodology Summary
<b>EXTRACT.7</b>	Toxicity Characteristic Leaching Procedure (TCLP).
<b>Inorg-001</b>	pH - Measured using pH meter and electrode in accordance with APHA latest edition, 4500-H+. Please note that the results for water analyses are indicative only as analysis outside of the APHA storage times.
<b>Inorg-004</b>	<p>Toxicity Characteristic Leaching Procedure (TCLP) using AS 4439 and USEPA 1311.</p> <p>Please note that the sample mass used may be scaled down from the default based on the sample mass available.</p> <p>Samples are stored at 2-6°C before and after leachate preparation.</p>
<b>Metals-020</b>	Determination of various metals by ICP-OES in accordance with USEPA 1311 and hence AS 4439.3. Buffer fluid determination performed only if required, otherwise leaching fluid selection should relate to the relevant landfill category from Table 3 of AS 4439.3 following information from the client. Extraction Fluid 1 refers to pH 5.0 Buffer, while Extraction Fluid 2 is the pH 2.9 Buffer.

Client Reference: E35822PR

QUALITY CONTROL: Metals from Leachate determ. pH 2.9 or 5					Duplicate			Spike Recovery %		
Test Description	Units	PQL	Method	Blank	#	Base	Dup.	RPD	LCS-1	[NT]
Date extracted	-			17/05/2023	[NT]	[NT]	[NT]	[NT]	17/05/2023	[NT]
Date analysed	-			18/05/2023	[NT]	[NT]	[NT]	[NT]	18/05/2023	[NT]
Lead	mg/L	0.03	Metals-020	<0.03	[NT]	[NT]	[NT]	[NT]	104	[NT]

**Result Definitions**

<b>NT</b>	Not tested
<b>NA</b>	Test not required
<b>INS</b>	Insufficient sample for this test
<b>PQL</b>	Practical Quantitation Limit
<b>&lt;</b>	Less than
<b>&gt;</b>	Greater than
<b>RPD</b>	Relative Percent Difference
<b>LCS</b>	Laboratory Control Sample
<b>NS</b>	Not specified
<b>NEPM</b>	National Environmental Protection Measure
<b>NR</b>	Not Reported

## Quality Control Definitions

<b>Blank</b>	This is the component of the analytical signal which is not derived from the sample but from reagents, glassware etc, can be determined by processing solvents and reagents in exactly the same manner as for samples.
<b>Duplicate</b>	This is the complete duplicate analysis of a sample from the process batch. If possible, the sample selected should be one where the analyte concentration is easily measurable.
<b>Matrix Spike</b>	A portion of the sample is spiked with a known concentration of target analyte. The purpose of the matrix spike is to monitor the performance of the analytical method used and to determine whether matrix interferences exist.
<b>LCS (Laboratory Control Sample)</b>	This comprises either a standard reference material or a control matrix (such as a blank sand or water) fortified with analytes representative of the analyte class. It is simply a check sample.
<b>Surrogate Spike</b>	Surrogates are known additions to each sample, blank, matrix spike and LCS in a batch, of compounds which are similar to the analyte of interest, however are not expected to be found in real samples.
Australian Drinking Water Guidelines recommend that Thermotolerant Coliform, Faecal Enterococci, & E.Coli levels are less than 1cfu/100mL. The recommended maximums are taken from "Australian Drinking Water Guidelines", published by NHMRC & ARMC 2011.	
The recommended maximums for analytes in urine are taken from "2018 TLVs and BEIs", as published by ACGIH (where available). Limit provided for Nickel is a precautionary guideline as per Position Paper prepared by AIOH Exposure Standards Committee, 2016.	
Guideline limits for Rinse Water Quality reported as per analytical requirements and specifications of AS 4187, Amdt 2 2019, Table 7.2	

## Laboratory Acceptance Criteria

Duplicate sample and matrix spike recoveries may not be reported on smaller jobs, however, were analysed at a frequency to meet or exceed NEPM requirements. All samples are tested in batches of 20. The duplicate sample RPD and matrix spike recoveries for the batch were within the laboratory acceptance criteria.

Filters, swabs, wipes, tubes and badges will not have duplicate data as the whole sample is generally extracted during sample extraction.

Spikes for Physical and Aggregate Tests are not applicable.

For VOCs in water samples, three vials are required for duplicate or spike analysis.

Duplicates: >10xPQL - RPD acceptance criteria will vary depending on the analytes and the analytical techniques but is typically in the range 20%-50% – see ELN-P05 QA/QC tables for details; <10xPQL - RPD are higher as the results approach PQL and the estimated measurement uncertainty will statistically increase.

Matrix Spikes, LCS and Surrogate recoveries: Generally 70-130% for inorganics/metals (not SPOCAS); 60-140% for organics/SPOCAS (+/-50% surrogates) and 10-140% for labile SVOCs (including labile surrogates), ultra trace organics and speciated phenols is acceptable.

In circumstances where no duplicate and/or sample spike has been reported at 1 in 10 and/or 1 in 20 samples respectively, the sample volume submitted was insufficient in order to satisfy laboratory QA/QC protocols.

When samples are received where certain analytes are outside of recommended technical holding times (THTs), the analysis has proceeded. Where analytes are on the verge of breaching THTs, every effort will be made to analyse within the THT or as soon as practicable.

Where sampling dates are not provided, Envirolab are not in a position to comment on the validity of the analysis where recommended technical holding times may have been breached.

Where matrix spike recoveries fall below the lower limit of the acceptance criteria (e.g. for non-labile or standard Organics <60%), positive result(s) in the parent sample will subsequently have a higher than typical estimated uncertainty (MU estimates supplied on request) and in these circumstances the sample result is likely biased significantly low.

Measurement Uncertainty estimates are available for most tests upon request.

Analysis of aqueous samples typically involves the extraction/digestion and/or analysis of the liquid phase only (i.e. NOT any settled sediment phase but inclusive of suspended particles if present), unless stipulated on the Envirolab COC and/or by correspondence. Notable exceptions include certain Physical Tests (pH/EC/BOD/COD/Apparent Colour etc.), Solids testing, total recoverable metals and PFAS where solids are included by default.

Samples for Microbiological analysis (not Amoeba forms) received outside of the 2-8°C temperature range do not meet the ideal cooling conditions as stated in AS2031-2012.



**Envirolab Services Pty Ltd**  
 ABN 37 112 535 645 - 002  
 25 Research Drive Croydon South VIC 3136  
 ph 03 9763 2500 fax 03 9763 2633  
 melbourne@envirolab.com.au  
 www.envirolab.com.au

## SAMPLE RECEIPT ADVICE

### Client Details

<b>Client</b>	JK Environments
<b>Attention</b>	Craig Ridley

### Sample Login Details

<b>Your reference</b>	E35822PR
<b>Envirolab Reference</b>	37227-A
<b>Date Sample Received</b>	10/05/2023
<b>Date Instructions Received</b>	17/05/2023
<b>Date Results Expected to be Reported</b>	24/05/2023

### Sample Condition

<b>Samples received in appropriate condition for analysis</b>	Yes
<b>No. of Samples Provided</b>	2 Soil
<b>Turnaround Time Requested</b>	Standard
<b>Temperature on Receipt (°C)</b>	11.1
<b>Cooling Method</b>	Ice Pack
<b>Sampling Date Provided</b>	YES

### Comments

Nil

Please direct any queries to:

#### Pamela Adams

**Phone: 03 9763 2500**

**Fax: 03 9763 2633**

**Email: padams@envirolab.com.au**

#### Chris De Luca

**Phone: 03 9763 2500**

**Fax: 03 9763 2633**

**Email: cdeluca@envirolab.com.au**

*Analysis Underway, details on the following page:*



**Envirolab Services Pty Ltd**

ABN 37 112 535 645 - 002

25 Research Drive Croydon South VIC 3136

ph 03 9763 2500 fax 03 9763 2633

melbourne@envirolab.com.au

www.envirolab.com.au

Sample ID	Metals from Leachate determ. pH 2.9 or 5	On Hold
SDUP3	✓	
SDUP4		✓

The '✓' indicates the testing you have requested. **THIS IS NOT A REPORT OF THE RESULTS.**

### Additional Info

Sample storage - Waters are routinely disposed of approximately 1 month and soils approximately 2 months from receipt.

Requests for longer term sample storage must be received in writing.

Please contact the laboratory immediately if observed settled sediment present in water samples is to be included in the extraction and/or analysis (exceptions include certain Physical Tests (pH/EC/BOD/COD/Apparent Colour etc.), Solids testing, Total Recoverable metals and PFAS analysis where solids are included by default.

## Chris De Luca

---

**From:** Craig Ridley <CRidley@jkenvironments.com.au>  
**Sent:** Wednesday, 17 May 2023 11:00 AM  
**To:** Chris De Luca  
**Subject:** RE: Results for Registration 37227 E35822PR

**CAUTION:** This email originated from outside of the organisation. Do not act on instructions, click links or open attachments unless you recognise the sender and know the content is authentic and safe.

Hi Chris, can we please arrange for the following additional analysis on standard turnaround:

- SDUP3 (37227-1) for TCLP Lead. — 1

Can you please use the acidic buffer solution to meet NSW EPA waste classification requirements.  
Any issues, please call.

37227-4  
Due 24/5/23  
SHD TAT

Regards  
Craig Ridley  
Associate | Environmental Scientist



T: +612 9888 5000  
D: 0421 856 992  
E: [CRidley@jkenvironments.com.au](mailto:CRidley@jkenvironments.com.au)  
[www.jkenvironments.com.au](http://www.jkenvironments.com.au)

PO Box 976  
NORTH RYDE BC NSW 1670  
115 Wicks Road  
MACQUARIE PARK NSW 2113

## JKEnvironments

This email and any attachments are confidential and may be privileged in which case neither is intended to be waived. If you have received this message in error, please notify us and remove it from your system. It is your responsibility to check any attachments for viruses and defects before opening or sending them on. At the Company's discretion we may send a paper copy for confirmation. In the event of any discrepancy between paper and electronic versions the paper version is to take precedence.

---

**From:** Chris De Luca <CDeLuca@envirolab.com.au>  
**Sent:** Monday, 15 May 2023 5:44 PM  
**To:** Craig Ridley <CRidley@jkenvironments.com.au>  
**Subject:** Results for Registration 37227 E35822PR

**This message originated outside the JKG network. If this looks to be from a staff member, it is likely to be malicious (spam/phish attack). Do not click links of open attachments unless you recognise the sender and know the content is safe.**

---

Please refer to attached for:  
a copy of the Certificate of Analysis  
a copy of the COC/paperwork received from you  
ESDAT Extracts  
an Excel or .csv file containing the results

Please note that a hard copy will not be posted.

Enquiries should be made directly to:  
[melbourne@envirolab.com.au](mailto:melbourne@envirolab.com.au)

[How did we do? Send Feedback](#)



---

## **Appendix F: Report Explanatory Notes**





## QA/QC Definitions

The QA/QC terms used in this report are defined below. The definitions are in accordance with US EPA publication SW-846, entitled *Test Methods for Evaluating Solid Waste, Physical/Chemical Methods* (1994)<sup>23</sup> methods and those described in *Environmental Sampling and Analysis, A Practical Guide*, (1991)<sup>24</sup>. The NEPM (2013) is consistent with these documents.

### A. Practical Quantitation Limit (PQL), Limit of Reporting (LOR) & Estimated Quantitation Limit (EQL)

These terms all refer to the concentration above which results can be expressed with a minimum 95% confidence level. The laboratory reporting limits are generally set at ten times the standard deviation for the Method Detection Limit for each specific analyte. For the purposes of this report the LOR, PQL, and EQL are considered to be equivalent.

When assessing laboratory data it should be borne in mind that values at or near the PQL have two important limitations: *“The uncertainty of the measurement value can approach, and even equal, the reported value. Secondly, confirmation of the analytes reported is virtually impossible unless identification uses highly selective methods. These issues diminish when reliably measurable amounts of analytes are present. Accordingly, legal and regulatory actions should be limited to data at or above the reliable detection limit”* (Keith, 1991).

### B. Precision

The degree to which data generated from repeated measurements differ from one another due to random errors. Precision is measured using the standard deviation or Relative Percent Difference (RPD).

### C. Accuracy

Accuracy is a measure of the agreement between an experimental result and the true value of the parameter being measured (i.e. the proximity of an averaged result to the true value, where all random errors have been statistically removed). The assessment of accuracy for an analysis can be achieved through the analysis of known reference materials or assessed by the analysis of surrogates, field blanks, trip spikes and matrix spikes. Accuracy is typically reported as percent recovery.

### D. Representativeness

Representativeness expresses the degree to which sample data accurately and precisely represents a characteristic of a population, parameter variations at a sampling point, or an environmental condition. Representativeness is primarily dependent upon the design and implementation of the sampling program. Representativeness of the data is partially ensured by the avoidance of contamination, adherence to sample handling and analysis protocols and use of proper chain-of-custody and documentation procedures.

### E. Completeness

Completeness is a measure of the number of valid measurements in a data set compared to the total number of measurements made and overall performance against DQIs. The following information is assessed for completeness:

- Chain-of-custody forms;
- Sample receipt form;
- All sample results reported;
- All blank data reported;

<sup>23</sup> US EPA, (1994). *SW-846: Test Methods for Evaluating Solid Waste, Physical/Chemical Methods*. (US EPA SW-846)

<sup>24</sup> Keith., H, (1991). *Environmental Sampling and Analysis, A Practical Guide*



- All laboratory duplicate and RPDs calculated;
- All surrogate spike data reported;
- All matrix spike and lab control spike (LCS) data reported and RPDs calculated;
- Spike recovery acceptable limits reported; and
- NATA stamp on reports.

**F. Comparability**

Comparability is the evaluation of the similarity of conditions (e.g. sample depth, sample homogeneity) under which separate sets of data are produced. Data comparability checks include a bias assessment that may arise from the following sources:

- Collection and analysis of samples by different personnel; Use of different techniques;
- Collection and analysis by the same personnel using the same methods but at different times; and
- Spatial and temporal changes (due to environmental dynamics).

**G. Blanks**

The purpose of laboratory and field blanks is to check for artefacts and interferences that may arise during sampling, transport and analysis.

**H. Matrix Spikes**

Samples are spiked with laboratory grade standards to detect interactive effects between the sample matrix and the analytes being measured. Matrix Spikes are reported as a percent recovery and are prepared for 1 in every 20 samples. Sample batches that contain less than 20 samples may be reported with a Matrix Spike from another batch. The percent recovery is calculated using the formula below. Acceptable recovery limits are 70% to 130%.

$$\frac{(\text{Spike Sample Result} - \text{Sample Result}) \times 100}{\text{Concentration of Spike Added}}$$

**I. Surrogate Spikes**

Samples are spiked with a known concentration of compounds that are chemically related to the analyte being investigated but unlikely to be detected in the environment. The purpose of the Surrogate Spikes is to check the accuracy of the analytical technique. Surrogate Spikes are reported as percent recovery.

**J. Duplicates**

Laboratory duplicates measure precision, expressed as Relative Percent Difference. Duplicates are prepared from a single field sample and analysed as two separate extraction procedures in the laboratory. The RPD is calculated using the formula where D1 is the sample concentration and D2 is the duplicate sample concentration:

$$\frac{(D1 - D2) \times 100}{\{(D1 + D2)/2\}}$$



---

## **Appendix G: Data (QA/QC) Evaluation**



## Data (QA/QC) Evaluation

### A. INTRODUCTION

This Data (QA/QC) Evaluation forms part of the validation process for the DQOs documented in Section 6.1 of this report. Checks were made to assess the data in terms of precision, accuracy, representativeness, comparability and completeness. These 'PARCC' parameters are referred to collectively as DQIs and are defined in the Report Explanatory Notes attached in the report appendices.

#### 1. Field and Laboratory Considerations

The quality of the analytical data produced for this project has been considered in relation to the following:

- Sample collection, storage, transport and analysis;
- Laboratory PQLs;
- Field QA/QC results; and
- Laboratory QA/QC results.

#### 2. Field QA/QC Samples and Analysis

A summary of the field QA/QC samples collected and analysed for this investigation is provided in the following table:

Sample Type	Sample Identification	Frequency (of Sample Type)	Analysis Performed
Intra-laboratory duplicate (soil)	SDUP1 (primary sample TP16 0-0.1m)	Approximately 7% of primary samples	Heavy metals, TRH/BTEX, PAHs, OCPs, OPPs and PCBs
Intra-laboratory duplicate (soil)	SDUP2 (primary sample TP15 0-0.1m)	As above	Heavy metals, TRH/BTEX, PAHs
Inter-laboratory duplicate (soil)	SDUP3 (primary sample TP14 0-0.1m)	Approximately 7% of primary samples	Heavy metals, TRH/BTEX, PAHs, OCPs, OPPs and PCBs
Inter-laboratory duplicate (soil)	SDUP4 (primary sample TP13 0-0.1m)	As above	Heavy metals, TRH/BTEX, PAHs
Trip spike (soil)	TS-S1 (02/05/2023)	One for the investigation to demonstrate adequacy of preservation, storage and transport methods	BTEX
Trip blank (soil)	TB-S1 (02/05/2023)	One for the investigation to demonstrate adequacy of storage and transport methods	Heavy metals, TRH/BTEX, PAHs
Rinsate (soil SPT)	FR-SPT (03/05/2023)	One for the investigation to demonstrate adequacy of decontamination methods	Heavy metals, TRH/BTEX, PAHs



The results for the field QA/QC samples are detailed in Table Q1 attached to the investigation report and are discussed in the subsequent sections of this Data (QA/QC) Evaluation report.

### **3. Data Assessment Criteria**

JKE adopted the following criteria for assessing the field and laboratory QA/QC analytical results:

#### ***Field Duplicates***

Acceptable targets for precision of field duplicates in this report will be 30% or less, consistent with NEPM (2013). RPD failures will be considered qualitatively on a case-by-case basis taking into account factors such as the concentrations used to calculate the RPD (i.e. RPD exceedance where concentrations are close to the PQL are typically not as significant as those where concentrations are reported at least five or 10 times the PQL), sample type, collection methods and the specific analyte where the RPD exceedance was reported.

#### ***Trip Blanks and Rinsates***

Acceptable targets for trip blank and rinsate samples in this report will be less than the PQL for organic analytes. Metals will be considered on a case-by-case basis with regards to typical background concentrations in soils and published drinking water guidelines for waters.

#### ***Trip Spikes***

Acceptable targets for trip spike samples in this report will be 70% to 130%.

#### ***Laboratory QA/QC***

The suitability of the laboratory data is assessed against the laboratory QA/QC criteria which is outlined in the laboratory reports. These criteria were developed and implemented in accordance with the laboratory's NATA accreditation and align with the acceptable limits for QA/QC samples as outlined in NEPM (2013) and other relevant guidelines.

A summary of the acceptable limits adopted by the primary laboratory (Envirolab) is provided below:

#### ***RPDs***

- Results that are <5 times the PQL, any RPD is acceptable; and
- Results >5 times the PQL, RPDs between 0-50% are acceptable.

#### ***Laboratory Control Samples (LCS) and Matrix Spikes***

- 70-130% recovery acceptable for metals and inorganics;
- 60-140% recovery acceptable for organics; and
- 10-140% recovery acceptable for VOCs.

#### ***Surrogate Spikes***

- 60-140% recovery acceptable for general organics; and
- 10-140% recovery acceptable for VOCs.

#### ***Method Blanks***

- All results less than PQL.



## **B. DATA EVALUATION**

### **1. Sample Collection, Storage, Transport and Analysis**

Samples were collected by trained field staff in accordance with our standard field sampling procedures, which were designed to be consistent with relevant guidelines, including NEPM (2013) and other guidelines made under the CLM Act 1997.

Appropriate sample preservation, handling and storage procedures were adopted. Laboratory analysis was undertaken within specified holding times generally in accordance with Schedule B(3) of NEPM (2013) and the laboratory NATA accredited methodologies. Envirolab noted that the asbestos results were reported to be consistent with the recommendations in NEPM (2013), however this level of reporting is outside the scope of their NATA accreditation. In the absence of other available analytical methods for asbestos, this was found to be acceptable for the purpose of this investigation.

JKE note that minor transcription errors occurred in the field in relation to sampling depth intervals of the following samples:

- The soil sample collected from BH6 (0-0.1m) was identified on the COC as BH6 (0.02-0.3m); and
- The soil sample collected from BH7 (0.02-0.3m) was identified on the COC as BH7 (0-0.1m).

Throughout this report, on the respective borehole logs and within the summary tables attached in the appendices, the samples are referred to their corrected identifications (BH6 0-0.1m and BH7 0.02-0.3m respectively). JKE consider these minor transcription errors do not adversely impact on the representativeness and completeness of the data collected for this investigation.

Review of the project data also indicated that:

- COC documentation was adequately maintained;
- Sample receipt advice documentation was provided for all sample batches;
- All analytical results were reported; and
- Consistent units were used to report the analysis results.

### **2. Laboratory PQLs**

Appropriate PQLs were adopted for the analysis and all PQLs were below the SAC.

### **3. Field QA/QC Sample Results**

#### ***Field Duplicates***

The results indicated that field precision was acceptable. RPD non-conformances were reported for some analytes as discussed below:

- Elevated RPDs were reported for several PAH compounds in SDUP1/TP16 (0-0.1m);
- Elevated RPDs were reported for two PAH compounds in SDUP2/TP15 (0-0.1m);
- Elevated RPDs were reported for several PAH compounds and several heavy metals in SDUP3/TP14 (0-0.1m); and
- Elevated RPDs were reported for fluoranthene (a PAH compound) and mercury in SDUP4/TP13 (0-0.1m).



The RPD values outside the acceptable limits for PAH compounds have been attributed to low analyte concentration (less than 5x the PQL), which exacerbate the RPD values. The RPD exceedances for various heavy metals have been attributed to sample heterogeneity and the difficulties associated with obtaining homogenous duplicate samples of heterogeneous matrices. As both the primary and duplicate sample results were compared to the SAC, the exceedances are not considered to have had an adverse impact on the data set as a whole.

#### ***Trip Blank***

During the investigation, one soil trip blank was placed in the esky during sampling and transported back to the laboratory. The soil trip blank analysis results were all less than the PQLs with the exception of various heavy metals (chromium, copper, lead, nickel and zinc) with reported concentrations ranging from 1mg/kg to 7mg/kg. Low level metals concentrations are typical in washed sand which is utilised as blank material. In JKE's experience, the concentrations reported were consistent with background concentrations in a sand matrix and were not indicative of cross-contamination. On this basis, cross contamination between samples that may have significance for data validity did not occur.

#### ***Rinsates***

All results were below the PQL with the exception of TRH F1 (26µg/L), copper (0.3mg/L) and zinc (0.2mg/L). The detectable concentration of light fraction TRH is most likely attributed to trihalomethanes. These compounds are breakdown products from the chlorination process and are common in potable water at the concentration reported (the Australian drinking water guideline for total trihalomethanes is 250µg/L).

Low level metals concentrations are typical in potable water which is utilised for rinsing and the collection of rinsate samples. In JKE's experience, the concentrations reported were consistent with expected concentrations in potable water (the Australian drinking water guidelines for copper is 2mg/L whilst the aesthetic consideration for zinc is 3mg/L). On this basis, cross contamination between samples that may have significance for data validity did not occur.

#### ***Trip Spikes***

The results ranged from 97% to 98% and indicated that field preservation methods were appropriate.

#### **4. Laboratory QA/QC**

The analytical methods implemented by the laboratory were performed in accordance with their NATA accreditation and were consistent with Schedule B(3) of NEPM (2013). The frequency of data reported for the laboratory QA/QC (i.e. duplicates, spikes, blanks, LCS) was considered to be acceptable for the purpose of this investigation. A review of the laboratory QA/QC data identified the following minor non-conformances:

- Report 322581 – matrix spike recovery was not possible for zinc in one sample due to the inhomogeneous nature of the sample. However, the laboratory noted an acceptable recovery was obtained for the LCS;
- Report 322581 – Matrix spike recovery was not possible for copper in one sample due to the high concentration in the sample. An acceptable recovery was obtained for the LCS; and



- 
- Report 322581 – Matrix spike recoveries were not possible for several PAHs in two samples due to interference from the high analyte concentrations within the samples. Acceptable recoveries were obtained for the LCS.

**C. DATA QUALITY SUMMARY**

JKE is of the opinion that the data are adequately precise, accurate, representative, comparable and complete to serve as a basis for interpretation to achieve the investigation objectives.

Non-conformances were reported for some field QA/QC samples and laboratory QA/QC analysis. These non-conformances were considered to be sporadic and minor, and were not considered to be indicative of systematic sampling or analytical errors. On this basis, these non-conformances are not considered to materially impact the report findings.





---

## **Appendix H: Guidelines and Reference Documents**



---

Acid Sulfate Soils Management Advisory Committee (ASSMAC), (1998). Acid Sulfate Soils Manual

Canadian Council of Ministers of the Environment, (1999). Canadian soil quality guidelines for the protection of environmental and human health: Benzo(a)Pyrene (1997)

CRC Care, (2011). Technical Report No. 10 – Health screening levels for hydrocarbons in soil and groundwater Part 1: Technical development document

Contaminated Land Management Act 1997 (NSW)

Department of Land and Water Conservation, (1997). 1:25,000 Acid Sulfate Soil Risk Map Series

Managing Land Contamination, Planning Guidelines SEPP55 – Remediation of Land (1998)

National Health and Medical Research Council (NHMRC), (2021). National Water Quality Management Strategy, Australian Drinking Water Guidelines 2011

NSW Department of Environment and Conservation, (2007). Guidelines for the Assessment and Management of Groundwater Contamination

NSW EPA, (2014). Waste Classification Guidelines - Part 1: Classifying Waste

NSW EPA, (2015). Guidelines on the Duty to Report Contamination under Section 60 of the CLM Act 1997

NSW EPA, (2017). Guidelines for the NSW Site Auditor Scheme, 3rd Edition

NSW EPA, (2020). Consultants Reporting on Contaminated Land, Contaminated Land Guidelines

NSW EPA, (2022). Sampling Design Part 1 – Application

National Environment Protection Council (NEPC), (2013). National Environmental Protection (Assessment of Site Contamination) Measure 1999 as amended (2013)

Olszowy, H., Torr, P., and Imray, P., (1995). Trace Element Concentrations in Soils from Rural and Urban Areas of Australia. Contaminated Sites Monograph Series No. 4. Department of Human Services and Health, Environment Protection Agency, and South Australian Health Commission

Protection of the Environment Operations Act 1997 (NSW)

State Environmental Planning Policy (Resilience and Hazards) 2021 (NSW)

Western Australia Department of Health, (2021). Guidelines for the Assessment, Remediation and Management of Asbestos-Contaminated Sites in Western Australia